


**HAZARDOUS
SITE
EVALUATION
DIVISION**

Field Investigation Team Zone II



**CONTRACT NO.
68-01-7347**

ecology and environment, inc.
International Specialists in the Environment



R00011062
RCRA Records Center

Final Report
EPI/Preliminary Assessment
Drew Industrial Division Inc.
(Ashland Chemical Company)
(Olin Water Services)
Kansas City, Kansas
TDD #F-07-9003-005/PAN #FKS0285RA
Site #T98 Project #001
Prepared by: E & E/FIT for Region VII EPA
FIT Project Manager: Patty S. Roberts
Submitted to: Pete Culver, RPO
RCRA-EPI Contact: Mark Matthews
Date: October 22, 1991

TABLE OF CONTENTS

| <u>Section</u> | <u>Page</u> |
|---|-------------|
| 1 INTRODUCTION | 1-1 |
| 2 SITE LOCATION AND DESCRIPTION | 2-1 |
| 2.1 SITE LOCATION | 2-1 |
| 2.2 SITE DESCRIPTION AND WASTE HANDLING | 2-1 |
| 2.3 SITE CONTACTS | 2-5 |
| 3 SITE BACKGROUND | 3-1 |
| 3.1 GENERAL HISTORY | 3-1 |
| 3.2 PERMIT AND REGULATORY ACTIONS SUMMARY..... | 3-2 |
| 4 ENVIRONMENTAL SETTING | 4-1 |
| 4.1 CULTURAL AND ENVIRONMENTAL SETTING | 4-1 |
| 4.2 TOPOGRAPHY AND DRAINAGE | 4-1 |
| 4.3 SOILS | 4-2 |
| 4.4 STRATIGRAPHY | 4-2 |
| 4.5 GROUND WATER | 4-3 |
| 5 DESCRIPTION OF INDIVIDUAL SOLID WASTE MANAGEMENT UNITS | 5-1 |
| 5.1 HAZARDOUS WASTE CONTAINER STORAGE AREA | 5-1 |
| 5.1.1 Information Summary | 5-1 |
| 5.1.2 Further Information Needs | 5-4 |
| 5.2 VSR SUMP VAT AND DRAINAGE | 5-5 |
| 5.2.1 Information Summary | 5-5 |
| 5.2.2 Further Information Needs | 5-8 |
| 5.3 C/F BLENDING ROOM DRAINAGE | 5-8 |
| 5.3.1 Information Summary | 5-8 |
| 5.3.2 Further Information Needs | 5-10 |
| 5.4 CONTINUOUS SEWER DISCHARGE OUTLET AND ASSOCIATED PIPING | 5-10 |
| 5.4.1 Information Summary | 5-10 |
| 5.4.2 Further Information Needs | 5-12 |
| 5.5 DUMPSTERS | 5-12 |
| 5.5.1 Information Summary | 5-12 |
| 5.5.2 Further Information Needs | 5-13 |
| 5.6 SATELLITE ACCUMULATION AREA | 5-14 |
| 5.6.1 Information Summary | 5-14 |
| 5.6.2 Further Information Needs | 5-14 |
| 5.7 AREA OF CONCERN | 5-14 |
| 5.7.1 Information Summary | 5-14 |
| 5.7.2 Further Information Needs | 5-16 |
| 6 SUMMARY OF SITE VISIT | 6-1 |
| 7 SUMMARY AND CONCLUSIONS | 7-1 |
| 8 BIBLIOGRAPHY | 8-1 |

APPENDICES

| <u>Appendix</u> | <u>Page</u> |
|--|-------------|
| A SITE PHOTOGRAPHS | A-1 |
| B EPA PRELIMINARY ASSESSMENT FORM 2070-12 | B-1 |
| C RAW MATERIAL NUMERICAL INDEX | C-1 |
| D HAZARDOUS WASTE CONTAINER STORAGE AREA INVENTORY LIST | D-1 |
| E WASTEWATER DISCHARGE PERMIT | E-1 |
| F WASTEWATER DISCHARGE SAMPLING RESULTS | F-1 |
| G ASHLAND PRE-ACQUISITION PRELIMINARY ENVIRONMENTAL ASSESSMENT REPORT | G-1 |

LIST OF FIGURES

| <u>Figure</u> | <u>Page</u> |
|--------------------------------|-------------|
| 2-1 Site Location Map..... | 2-2 |
| 2-2 Facility Map | 2-4 |
| 4-1 Stratigraphic Column | 4-4 |
| 5-1 SWMU Location Map | 5-2 |

SECTION 1: INTRODUCTION

As part of the United States Environmental Protection Agency's (EPA) Environmental Priorities Initiative (EPI) Program, Region VII EPA has requested Ecology and Environment, Inc., Field Investigation Team (E & E/FIT) to conduct an EPI Preliminary Assessment (PA) of the Olin Water Services-Olin Corporation located at 305 Sunshine Road, Kansas City, Kansas. Recently, the Olin Water Services Branch was purchased by Ashland Oil, Inc. The facility is now named Drew Industrial Division (Ashland Chemical Company), a subsidiary company of Ashland Oil, Inc. However, for purposes of this EPI-PA, the site will be referred to as the Olin Water Services.

The EPI Program integrates the Resource Conservation and Recovery Act of 1976 (RCRA), the Hazardous and Solid Waste Amendments (HSWA) of 1984, the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (CERCLA), and the Superfund Amendments and Reauthorization Act of 1986 (SARA) in order to set priorities for the cleanup of the most environmentally significant sites first. This EPI-PA is essentially equivalent to RCRA's Preliminary Review/Visual Site Inspection (VSI) and identifies potential or actual releases at the facility and determines if remedial measures are necessary.

This report discusses information obtained from the EPA-RCRA, Olin Water Services, and Kansas Department of Health and Environment (KDHE). All solid waste management units (SWMUs) are described in detail. Observations obtained from the on-site reconnaissance conducted by E & E/FIT on April 27, 1990, are included along with site-specific information concerning the physical and environmental setting. Photographic documentation is contained within Appendix A. EPA's PA Form 2070-12 is included as Appendix B.

SECTION 2: SITE LOCATION AND DESCRIPTION





2.1 SITE LOCATION

The Olin Water Services-Olin Corporation is located in the southwest 1/4 of Section 27, Township 10 South, Range 25 East. The geographic coordinates are 39° 08'47" N latitude and 94° 36'58" W longitude. The site is situated at the intersection of Sunshine and Fiberglas roads, in the Fairfax Industrial District, north of downtown Kansas City, Kansas, in Wyandotte County (Figure 2-1).

2.2 SITE DESCRIPTION AND WASTE HANDLING

The Olin facility manufactures chemicals for industrial water treatment facilities. The company's manufacturing process consists of blending approximately 150 different inorganic and organic raw materials (liquid and powder) to produce approximately 250 different water treatment compounds (E & E 1990). The raw materials include solvents, acids, and caustics (Appendix C). The water treatment chemicals produced at the site have various applications ranging from corrosion control in boiling water and cooling water treatments to inorganic coagulants (polymers) in municipal and industrial wastewater clarification treatment processes.

The facility formulates water treatment products on a batch basis; the formulating schedule and amount of each particular product produced depends both on demand and warehouse inventory. The plant facility is utilized on a daily basis. After formulation, Olin performs analytical tests of the batches at its on-site laboratory to assure that product meets specifications; then the product is drummed for shipment or storage. Olin receives and ships both bulk and drummed materials. The amount of shipments can vary daily. It was reported that about 7.5 million pounds of raw materials as well as finished products were shipped and received by the Olin facility in 1989 (E & E 1990). The Olin facility does not receive or ship by rail; however, the railroad off-loading area north of Olin is operational and is used by Owen-Corning Fiberglas Company (E & E 1990).



Olin Water Services Kansas City, Kansas

Prepared by Lee Robertson
Ecology & Environment/FIT March, 1991

Waste Site Tracking #: KS0285
Source: USGS 7.5' N. Kansas City, MO-KS Quad.

Figure 2-1: SITE LOCATION

Olin Water Services occupies two buildings that are separated by railroad tracks (Figure 2-2). One building serves as a shipping and receiving warehouse for raw materials (unformulated new chemicals) and for finished products. The warehouse also contains some administrative offices. The second building is the plant facility and houses all the chemical manufacturing processes (Appendix A; Photo 1). On a daily basis, raw material and finished products are shuttled by truck to and from the blending areas. An area in the plant facility referred to as the Piece Drum Area also temporarily stores finished product (E & E 1990). These drums remain partially full until the next batch of similar products is made to fill them completely. Full drums of finished product are moved to the warehouse for shipment.

Directly south of the plant building is the production yard, where the company's RCRA-permitted hazardous waste container storage area is located, as well as hundreds of empty 55-gallon plastic drums (Photos 2 through 7). These drums are clean and are stored on four-foot wide pallets, stacked two or three drums high. Two dumpsters are located in the production yard and contain solid wastes such as scrap building materials and empty unusable drums, which have been triple rinsed and crushed. Two product aboveground storage tanks are also located east of the plant; the south tank is currently empty, and the north tank contains sodium hydroxide (Figure 2-2).

The hazardous waste container storage area and production yard is surrounded by a seven-foot high chain-link fence, topped by three strands of barbed wire. There are two gates located on the east and west allowing access for loading and unloading of materials. Generally, only the west gate is open during working hours (7:00 a.m. to 4:30 p.m.). At the end of each working day, the production plant is locked and all access gates are chained and padlocked. For identification of all pertinent site features see Figure 2-2 and Appendix A.

The raw materials that Olin uses and finished products that Olin produces at its facility display hazardous characteristics. Wastes generated during the manufacturing process are from liquid or dry chemical spillage from the formulating drum loading operations and non-reusable rinse water from the formulating process. The majority of non-reuseable rinse water is either recycled as make-up water for




Figure 2-2: SITE FACILITY

succeeding batches or is discharged to the sewer system after neutralization. If determined by analysis to be hazardous, it is drummed and placed in the container storage area (Bosky 1987). Raw material and finished products that are unusable or off-specification are also accumulated, containerized, and stored in the hazardous waste container storage area. The majority of identified waste stored in the permitted container storage area exhibit characteristics of reactivity, corrosivity, ignitability, and/or EP toxicity as denoted in 40 Code of Federal Regulations (CFR), Part 261, Subpart C (E & E 1990). F001 (methylene chloride) is also generated at the Olin's on-site laboratory; however, the waste quantity is minimal. Presently, no F001 wastes are stored in the container storage area. Various U-listed wastes (orthodichlorobenzene, pentachlorophenate) and non-hazardous wastes are also stored in Olin's hazardous waste container storage area. The last entry date in Olin's hazardous waste inventory list for placement of containerized wastes in the storage facility was November 4, 1989 (Appendix D). It was reported that the facility is minimizing wastes by re-using and reworking materials that would otherwise require disposal as a hazardous material (E & E 1990). On occasion, customers return off-specification products to the Olin facility to be reworked.

2.3 SITE CONTACTS

Persons familiar with operations or have regulatory involvement with the facility include:

William E. Dame
Plant Manager
305 Sunshine Road
Kansas City, Kansas 66115
(913) 621-6410

Larry M. Prouty
Manager, Regulatory Affairs
Olin Water Services-Olin Corporation
51 Corporate Woods-9393 W. 110th St.
Overland Park, Kansas 66210
(913) 451-3100

William C. Olatin
Environmental Engineer
Ashland Chemical Company
P.O. Box 2219
Columbus (Dublin), Ohio 43216
(614) 889-3065

Mark Matthews
U.S. Environmental Protection Agency
RCRA Branch/Waste Management Division
726 Minnesota Avenue
Kansas City, Kansas 66101
(913) 551-7635

Paul Cahoon
Kansas Department of Health and Environment
Bureau of Air and Waste Management
Forbes Field, Building 740
Topeka, Kansas 66620-7500
(913) 296-1600

SECTION 3: SITE BACKGROUND AND HISTORY

3.1 GENERAL HISTORY

The property at 305 Sunshine Road was used in the 1950s and early 1960s as an electro-circuit assembly plant. In the mid to late 1960s, the property was owned by Deday Chemical Company, which began manufacturing (blending) water treatment chemicals in about 1965. The facility was purchased by the Olin Corporation in 1970, and the Olin Water Services Division commenced operation in 1970. The facility in Kansas City, Kansas, employs about 30 employees including laboratory and manufacturing workers, and distributes water treatment products nationwide.

In December 1989, Olin Water Services-Olin Corporation was sold to Drew Industrial Division (Ashland Chemical Company) (E & E 1990). The facility soon will be re-named and will function as a Midwest Industrial Division regional supplier only (E & E 1990).^{*} Drew Industrial Division plans to remove the two product storage tanks located east of the production plant and replace them with a tank farm, consisting of 16 5,600-gallon to 9,600-gallon storage tanks (E & E 1990). Olin/Drew representatives are also considering expanding the north side of the warehouse. Furthermore, as part of the Drew/Olin purchase agreement, use of combustible/flammable materials and chromium products was to be discontinued at the Kansas City facility (Dame 1990). These products were for the most part discontinued about July 1990. Olin supplies about 2 55-gallon drums every three to four months to one customer for use as fuel oil treatment. Finally, under terms of the merger, all hazardous wastes stored in the RCRA-permitted hazardous waste container storage area are to be disposed of by Olin Water Services (Dame 1990).

During the period of 1980 to 1984, the Olin facility operated as an interim status hazardous waste management facility under a RCRA Part A Notification. Activities specified in the notification included storage of hazardous wastes in drum containers. Olin submitted an initial Part B Hazardous Waste Permit Application to EPA and KDHE on March 4, 1983. After numerous revisions and compliance activities, EPA made a tentative decision to issue a RCRA Part B Permit to the Olin Water Services on

September 21, 1984 and issued a public comment period, expiring on November 13, 1984. After an agreement on the contents of the Part B Permit Application, KDHE and EPA granted the Olin facility a final permit which became effective on April 6, 1985. The construction of a drum storage structure consisting of three-sided cinder block walls and covered roof was specified in the permit and completed on August 8, 1985. In 1987, Olin revised the original Part B Permit to include storage of drums by a linear height limitation, with total capacity not to exceed 200 55-gallon drums. This modification was subsequently incorporated into the Olin Part B Permit and approved on February 15, 1988.

In addition to being a hazardous waste storage facility, Olin has been classified as a generator of hazardous wastes from the preparation of liquid and powder water treatment formulations. The Olin Water Services is a State-lead site and under KDHE authority; the Olin facility is classified as a Kansas generator (generates between 25 and 1,000 kilograms of hazardous wastes per month) (Cahoon 1990). Because state regulations are more stringent, the Kansas generator status supersedes EPA's classification of a small quantity generator (1,000 kilograms of hazardous wastes per month).

The ownership, including the RCRA Part B Permit was scheduled to be transferred from Olin Water Services to Drew Industrial Division on December 29, 1989 (Woods 1989). For a more detailed permit and regulatory action summary see Section 3.2.

3.2 PERMIT AND REGULATORY ACTIONS SUMMARY

Following is a chronological history of the compliance history of the Olin Water Services facility.

CHRONOLOGICAL LISTING OF OLIN COMPLIANCE HISTORY

| | |
|-------------------|---|
| February 27, 1979 | Olin Water Services submitted a Hazardous Waste Generator Report to KDHE stating that the facility utilizes reactive, corrosive, ignitable and toxic materials. |
| May 1, 1979 | Olin submitted to KDHE an application for a hazardous waste storage permit. |

| | |
|--------------------|---|
| April 17, 1980 | KDHE conducted a hazardous waste generator's survey of the Olin's Water Services facility and found that the facility stores off-specification products on site for longer than 90 days. Periodically, these products are transported from the site for disposal. |
| November 18, 1980 | EPA/RCRA received Olin Water Services Part A Hazardous Waste Permit Application, and signed statement that the operation or construction of the facility began before November 19, 1980. |
| December 16, 1980 | EPA granted Olin an initial qualification for interim status as a hazardous waste management facility. |
| April 22, 1981 | EPA RCRA conducted an inspection at Olin Water and cited the facility for four areas of non-compliance. These non-compliance issues included inspection requirements not being carried out, containerized ignitable or reactive wastes being stored too close to the property line of the plant, and no adequate aisle space between storage drums. In addition, Olin Water Services did not have a contingency plan. |
| June 8, 1981 | Olin submitted to KDHE an application for a Kansas hazardous waste storage, treatment, and disposal facility permit. |
| September 11, 1981 | KDHE issued a Letter of Warning to Olin Water Services requesting corrective action of the April 1981 non-compliance issues by November 1, 1981. |
| October 27, 1981 | Olin responded to KDHE and provided corrective action to three of the four non-compliance items identified during the April 1981 EPA/RCRA inspection. Olin petitioned for modification of the requirement that containers holding ignitable or reactive waste must be located at least 50 feet from the property line of the plant. |
| July 26, 1982 | KDHE and EPA renewed Olin's Interim Status Permit to June 30, 1983. |
| August 31, 1982 | Olin submitted a variance request to KDHE/RCRA to petition for a variance to the regulation 40 CFR Section 265.176 that specifies that containers holding reactive |

or ignitable waste be stored 50 feet from the property line of the plant.

September 13, 1982

KDHE began the Part B Application process for Olin's hazardous waste storage facility. KDHE requested that this application be processed jointly by EPA and KDHE and that one permit issued to satisfy both state and federal requirements (EPA I.D. No. KSD000203638).

September 24, 1982

KDHE exempted the Olin Water Services from 40 CFR 265.176 until September 30, 1983 at which time KDHE planned to review the variance to determine if an extension was necessary.

December 21, 1982

KDHE conducted a RCRA inspection at Olin and found the facility to be in compliance with all state and federal regulations concerning generators and treatment, storage, and disposal facilities for hazardous waste.

January 6, 1983

EPA requested that Olin incorporate in the Part B Application a discussion of why the requirement of 40 CFR 265.176 could not be met and proposed alternatives to meet the intent of this regulation.

March 4, 1983

Olin submitted to EPA and KDHE 6 copies of the Part B Hazardous Waste Permit Application; copies were received on March 14.

May 5, 1983

EPA and KDHE reviewed the Olin Part B permit application, and had numerous regulatory comments, which Olin was required to respond to by June 24, 1983.

June 13, 1983

Olin requested an extension until July 18, 1983 to prepare its response to the joint EPA and KDHE comments regarding the Part B permit review on May 5, 1983.

June 21, 1983

KDHE and EPA renewed the facility's interim status until June 30, 1984.

June 23, 1983

EPA sent Olin a Letter of Warning approving the July 18, 1983, extension date and requiring the facility to mitigate the deficiencies in its Part B Permit Application by this date or face enforcement action.

| | |
|--------------------|---|
| July 18, 1983 | Olin responded to EPA and KDHE May 5, 1983, Part B comments. Olin excluded some portions of the 40 CFR Part 264 facility standards because these standards were not directly applicable to the permit process regulations contained in 40 CFR Part 122 (now Part 270). |
| September 13, 1983 | EPA and KDHE requested submittal of a complete Part B Permit Application. |
| November 23, 1983 | Olin submitted a revised Part A Hazardous Waste Permit Application correcting all oversights from the original Part A. |
| March 7, 1984 | KDHE completed the financial, technical, and management review of the Olin facility and recommends that the Part B Permit Application proceed according to schedule. |
| March 28, 1984 | EPA issued to Olin a Complaint, Compliance Order, and Notice of Opportunity for Hearing pursuant to Section 3008 (a) (1). |
| March 29, 1984 | EPA and KDHE reviewed Olin's July 18, 1983, response to the comment letter regarding completeness of Olin's Part B Permit. EPA and KDHE requested that the 40 CFR Part 264 information (outlining standards which define the management of hazardous waste) be received before the Part B Application was completed. Numerous other deficiencies were also addressed. |
| April 24, 1984 | KDHE conducted a RCRA inspection at the Olin facility and found them to be in compliance except for the fact that the limited number of signs posted around the facility did not meet the regulatory safety requirements. |
| April 26, 1984 | Olin responded to EPA/RCRA Part B Permit Application review comment letter dated March 29, 1984, and submitted numerous revisions to the Part B permit application including a revised Part A application. |
| May 3, 1984 | Olin filed an Answer and Request for Hearing, Motion to Dismiss, Memorandum in Support of Motion to Dismiss, Motion for Prehearing Conference and Certification of Record. |

| | |
|--------------------|--|
| May 31, 1984 | EPA denied Olin's Motion to Dismiss (Docket No. 84-H-0015). EPA reviewed the Olin's April 26, 1984, response to comment on the RCRA Part B Permit Application and had numerous regulatory comments. |
| June 22, 1984 | Olin responded to EPA Part B Permit Application review comment letter dated May 31, 1984. |
| July 11, 1984 | EPA responded to Olin's June 22, 1984, comment letter and had a few remaining review comments. |
| August 7, 1984 | Olin responded to EPA's July 11, 1984, review comment letter and made several revisions. |
| September 13, 1984 | Olin submitted to EPA and KDHE 5 revised copies of the Part B Permit Application, concerning waste analysis plan, drum stacking, and buffer zone requirements. |
| September 14, 1984 | Olin submitted to EPA and KDHE supplemental and revised information to correct and complete the Part B Permit Application. |
| September 20, 1984 | Olin submitted to EPA and KDHE 5 copies of the corrected Part 270.14(b) (4) of the Part B Permit addressing the warning signs on the south and west sides of the hazardous waste storage facility. |
| September 21, 1984 | EPA made a tentative decision to issue a RCRA permit to the Olin Water Services, Olin Corporation and issued a public comment period, which expired November 13, 1984. |
| NO DATE | EPA and KDHE issued joint Public Notice to the Olin Water Service facility for a Hazardous Waste Storage permit. If a decision was made to issue permits, the EPA permit would be issued under the authority of RCRA, while the KDHE permit would be issued under the authority of K.S.A. 65-3431 (i). |
| November 6, 1984 | Olin waived the previous security procedures and equipment requirements in the draft Part B Permit; instead a three-sided structure with cinder block walls and a covered roof structure was constructed. |

| | |
|--------------------|---|
| November 28, 1984 | Olin submitted to KDHE the revised pages to Section 270.14(b) (4) of the Part B Permit omitting the requirement that the facility raise the height of the fence adjacent to the storage area to 16 feet. |
| January 4, 1985 | The public comment period regarding Olin's Hazardous Waste Storage Permit ended. |
| January 23, 1985 | EPA and the Olin Water Services developed a Consent Agreement and Consent Order for proceedings under Section 3008(a)(1). |
| March 6, 1985 | KDHE decided that a final Part B Permit be issued to the Olin Water Service facility. The final permit would become effective on April 6, 1985, unless a review or hearing was requested. |
| March 15, 1985 | Final Consent Agreement and Final Order agreed upon by Olin Corporation, Water Service Division and the EPA. |
| August 8, 1985 | Olin completed construction of the hazardous waste storage containment facility. This facility is 38.5 feet from the production plant. |
| September 26, 1985 | Olin submitted to KDHE a revised Contingency Plan. |
| April 29, 1986 | KDHE notified Olin of the September 23, 1985, changes to the Kansas hazardous waste regulations specifying that a draft notice be placed on the property deed which details hazardous waste operations (K.A.R. 28-31-8). |
| July 29, 1986 | KDHE conducted a RCRA inspection at the Olin facility and found several items not in compliance with state and federal regulations for generators of hazardous waste and permit requirements for storage of hazardous wastes. On the day of the inspection liquid from the VSR sump vat was being discharged onto the ground. |
| October 8, 1986 | Olin advised KDHE that action has been taken to correct deficiencies noted during the July 29, 1986, RCRA inspection. |
| October 9, 1986 | Olin submitted to KDHE revised pages of the Part B Permit Application. KDHE approved |

| | |
|--------------------|--|
| | the modifications made on the revised pages and corrected the current Part B Permit. |
| October 24, 1986 | KDHE conducted a follow-up RCRA inspection and found the facility to be in substantial compliance with State and Federal regulations concerning generators of hazardous waste. During the follow-up inspection, a float-activated pump was being installed on the volatile steam return (VSR) sump vat to prevent sump overflow. |
| April 20, 1987 | KDHE and EPA conducted a joint RCRA Compliance Inspection of the Olin Water Service facility and the State Inspector determined that the facility was not meeting some of the requirements pursuant under the Kansas Hazardous Waste Management Law and/or the final permit. |
| May 22, 1987 | Olin requested changes to their initial Part B Permit to include modifications concerning drum stacking height limitations. |
| June 15, 1987 | Olin responded to the April 20, 1987, Compliance Inspection and corrected the deficiencies noted by KDHE. |
| July 2, 1987 | KDHE requested that the accumulated methylene chloride waste generated by Olin's laboratory be labeled as F001 wastes and be moved to the permitted hazardous waste storage area and shipped off site within 90 days. |
| July 8, 1987 | KDHE notified Olin of changes in RCRA regulations regarding closure, post-closure, and financial responsibility and requested modifications if appropriate. |
| August 7, 1987 | Olin requested an extension of time for the storage of the F001 spent solvent wastes due to pending contract disposal negotiations. |
| August 12, 1987 | KDHE approved Olin's request to extend until September 17, 1987, the 90-day period to store F001 waste. |
| September 25, 1987 | Olin requested another extension to remove three drums of F001 wastes; difficulties were encountered in running analyses and selecting a transporter. |

| | |
|--------------------|---|
| September 30, 1987 | KDHE approved the additional extension until October 17, 1987. |
| October 23, 1987 | KDHE reviewed Olin's Part B Permit modifications and tentatively approved the requested modifications to the hazardous waste drum storage stacking height to three high, but total storage capacity of only 200 55-gallon drums. |
| November 9, 1987 | Olin notified KDHE that the F001 wastes had been removed from its facility to a permitted waste facility in Doe Run, Kentucky. |
| November 23, 1987 | KDHE submitted to EPA Olin's proposed Part B Permit modifications for EPA's 15-day period of review and comment as specified in the EPA - Kansas Transition Plan. |
| December 17, 1987 | KDHE provided Public Notice that the Olin facility may modify its hazardous waste storage permit to store drums by a linear height limitation and to conduct some inspections less frequently. The notice also announced that KDHE was solely authorized to modify the original Olin Permit. |
| December 18, 1987 | KDHE tentatively decided to modify the RCRA permit issued to Olin Water Services and issued a 45-day public comment period. |
| December 28, 1987 | KDHE amended Olin's generator status to include consideration of F001 generated wastes. |
| February 15, 1988 | KDHE notified Olin that a final decision had been made to modify the Part B Permit to include the storage of drums with a linear height limitation and notice to conduct inspections less frequently. |
| April 20, 1988 | KDHE conducted a RCRA compliance inspection and found that the Olin facility was not meeting some requirements pursuant to rules under the Kansas hazardous waste management law or specified in the final permit. Some of these non-compliance issues concerned unmarked containers, a pallet of assorted laboratory chemicals not included in the facility's storage permit, and unavailable generator's biannual report. During this inspection the use of a satellite |

| | |
|-------------------|--|
| | accumulation area in the laboratory was discussed. |
| August 19, 1988 | KDHE conducted a follow-up RCRA inspection and found the facility to be in substantial compliance with state and federal hazardous waste regulations. |
| March 1, 1989 | KDHE conducted a RCRA compliance inspection and found no violations of the Kansas hazardous waste management statutes and/or regulations. |
| December 20, 1989 | KDHE conducted a RCRA compliance inspection and found the facility not to be in compliance with state and federal regulations concerning inspection schedules and personnel training. |
| December 1989 | Olin Water Services-Olin Corporation was sold to Drew Industrial Division (Ashland Chemical Company). |
| December 27, 1989 | Part B Permit (KSD000203638) transferred from the Olin Corporation to Drew Industrial Division (Ashland Chemical, Company). The transaction was closed on December 29, 1989. |
| January 10, 1990 | KDHE notified the Olin Water Services of the State's updated hazardous waste regulations. These include all regulations in 40 CFR 264, 265, 270, and 124 Subparts A, B, E, and F as in effect on July 1, 1989. K.A.R. 28-31-8 and 28-31-9 specifically adopt regulations applicable to the Olin TSD management operations. |
| January 22, 1990 | Olin Water Services notified KDHE that the facility had corrected the two non-compliance issues identified during the December 20, 1989, compliance inspection. |
| March 18, 1990 | Olin submitted a revised Notification of Hazardous Waste Activity form reflecting the change of ownership to Drew Industrial Division. |

SECTION 4: ENVIRONMENTAL SETTING

4.1 CULTURAL AND ENVIRONMENTAL SETTING

Olin Water Services is located in the Fairfax Industrial District of Kansas City, Wyandotte County, Kansas. This industrial area is located in a densely populated area of the city. The nearest residential area is Kansas City, Kansas (population 162,070), which lies between 1/2 and 1 mile south-southwest of the site. Population concentrations within four miles of the site would encompass areas of Kansas City, and Riverside, Kansas, and Kansas City and North Kansas City, Missouri (USGS 1964; USGS 1975). The nearest residential area lies 1/2 or more miles south-southwest. A city park is located about 1/2 mile directly south of the Olin facility, and Dunbar School is located approximately 3/4 miles southwest.

4.2 TOPOGRAPHY AND DRAINAGE

The Olin Water Services facility is in the southeast corner of Wyandotte County, which lies in the Osage Cuestas physiographic unit. The main topographic features of the county are the deeply dissected loess bluffs with rock outcrops rising about 105 feet above the site to the south-southwest, and the floodplain of the Missouri River (USDA 1977). The Missouri River is located about 3,200 feet north of the site. It flows west to east at an average flow rate of 54,780 cubic feet/second (cfs) and drains the northern and eastern parts of Wyandotte County within a four-mile radius of the site (USGS 1964; USGS 1975; USGS 1980).

The site topography has a maximum slope of one percent, which is typical of alluvial flood plains. Surface water drainage from the Olin site is probably toward the north-northeast where ultimately it is collected in a storm sewer along the northern property line (E & E 1990). The actual entry point into the Missouri River is unknown.

A surface water intake at the Kansas City, Missouri, Water Works facility is located northeast of the site (upgradient) on the north bank of the Missouri River about 2.5 miles above the Missouri-Kansas

confluence. In addition, two well fields composed of seven wells are located adjacent and north of the surface water intake. The Kansas City, Kansas, surface water intake which serves 80 percent of Wyandotte County is located upriver about 2 miles from the site (Hasan 1988).

The Olin facility, as well as the entire Fairfax Industrial District, is within the Fairfax-Jersey Creek Levy Unit as designated by the U.S. Army Corps of Engineers (Hasan 1988). This area is identified as being protected from a 500-year flood (Olin 1983).

The only known potential wildlife habitat is Goose Island, located directly east on the south bank of the Missouri River. To date, it is unknown if this habitat is utilized by any state or federally designated threatened or endangered species.

4.3 SOILS

The soils at the Olin Water Services site are of the Onawa Series (USDA 1977). Onawa soils are nearly level, calcareous, and somewhat poorly drained on flat to slightly depressional floodplains. They are mainly on bottomland along the Missouri River and are subject to occasional flooding. In the area of the Olin facility, the surface layer (approximately 6 to 20 inches in thickness) are of the Onawa (overwash) soil series. These soils consist of fine sandy loam to silt loam and developed from alluvium deposits from a rare major flood. The next layer is dark-gray and very dark-gray silty clay about 19 inches thick. It is underlain by grayish-brown coarse silt loam. Onawa soils are deep and permeability is low.

4.4 STRATIGRAPHY

The Olin Water Services site is underlain by Quaternary-age Missouri River alluvium consisting of sand, silt, and gravel deposits. The alluvial deposits range in thickness from 0 feet on the river bluffs, to more than 100 feet in the floodplain area (KGS 1963). Generally, the thickness of the alluvial deposit is directly related to the width of the floodplain. In the site vicinity the alluvial deposits are about 125 feet deep (Layne 1979). The upper 50 feet consists of finer sands and silt, which grade into coarser sands and gravel with increasing cobbles and boulders at about 100 feet (Layne 1979).

The Pennsylvanian-age bedrock outcropping in river bluffs within a four-mile radius of the site comprises the Kansas City Group and upper members of the Pleasanton Group (KGS 1963). In the site vicinity, the Kansas City Group is removed, leaving the upper members of the Pleasanton Group to directly underlie the Missouri River alluvium (KGS 1963). The Pleasanton Group consists of cyclothemic limestones and shales and occasionally sandstone. The group ranges in thickness from 20 to 150 feet. The Pleasanton Group is considered to be the basal aquitard for the limestones of the Kansas City Group (KGS 1963).

The Pennsylvanian rocks dip gently westward (KGS 1963). A generalized stratigraphic column illustrating geology in the site vicinity is included as Figure 4-1.

4.5 GROUND WATER

The aquifer of concern is located within the sands and gravels of the Missouri River alluvium. Depth to ground water in the Missouri River valley is generally between 15 and 30 feet depending on location and season. The levels fluctuate as influenced by river stage and the recharge from the surrounding uplands (Hasan 1988). The static water level near the Olin facility is about 21 feet (Layne 1979). The regional ground water flow is to the north and east, toward the Missouri River.

The Missouri alluvium is considered a high-capacity aquifer and provides wide spread industrial, agricultural (self-supplied), and municipal supplies. A large ground water sink in the Kansas City area is also found in alluvial valleys of the Kansas River. The Kansas City, Missouri, and Kansas City, Kansas, municipal water is derived almost exclusively by alluvial wells and surface water intakes along the Kansas and Missouri rivers (Hasan 1988). The nearest well field to the Olin Water Services site is located on the Missouri River, approximately 1.5 miles northeast of the Olin site (USGS 1964).




Figure 4-1: GENERALIZED STRATIGRAPHIC COLUMN

SECTION 5: DESCRIPTION OF INDIVIDUAL SOLID WASTE MANAGEMENT UNITS

5.1 HAZARDOUS WASTE CONTAINER STORAGE AREA

5.1.1 Information Summary

Unit Description

The hazardous waste container storage area (Appendix A; Photos 4 to 7) is a detached building located in the southwest corner of the production yard of the Olin Water Services facility (Figure 5-1). The overall dimension is about 31 by 26 feet, and the area available for storage is about 25 by 24 feet (Olin 1983). The floor of the building is a reinforced concrete slab surrounded on three sides by concrete block walls and covered by a steel roof with clear panels for lighting. The north side of the building is open and has a six-foot-wide ramp along the entire length. A concrete sump is located along the south wall of the container storage area and provides secondary containment. The drums are stored on 4-foot-wide pallets in 4 rows, 5 pallets deep with aisles on either side of the rows and stacked at a height not to exceed 12 feet. The total number of drums stored in the container area will not exceed 200 55-gallon drums (Olin 1987). Some of the drummed wastes have been stored in this facility for several years (E & E 1990). Warning signs are posted around the storage facility so as to be clearly legible at any position within 25 feet of the container storage area. Additional security is provided by a private security patrol which makes nightly patrols. The hazardous waste container storage area is a RCRA-regulated unit and is about 38.5 feet away from the production plant (Olin 1987).

Dates of Operation

1985 to present

Wastes Managed


The hazardous waste container area is used to store liquids and solids (powder), with the majority being aqueous wastes that are off-specification raw materials and products (Dame 1990). Character-

S u n s h i n e R o a d

F e b e r g i l a s R o a d


Olin Water Services Kansas City, Kansas

Plant Building



LEGEND

- SWMU 5.1 Hazardous Waste Container Storage Area
- SWMU 5.2 V.S.R. Sump Vat and Drainage
- SWMU 5.3 C/F Blending Room Drainage
- SWMU 5.4 Continuous Sewer Discharge Outlet and Associated Piping
- SWMU 5.5 Dumpsters
- SWMU 5.6 Satellite Accumulation Area
- 5.7 Area of Concern
- C/F Corrosive & Flammable
- V.S.R. Volatile Steam Return
- Collection Trench
- Above Ground Product Storage Tank
- Product Blending Tank/Storage Tank



Prepared by Lee Robertson
Ecology & Environment/FIT March 1991

Waste Site Tracking #: KS0285
Source: Olin Water Services, 1984




Figure 5-1: SWMU LOCATIONS

istic hazardous wastes (ignitable, corrosive, reactive, and/or toxic) are the major type of wastes stored in the facility with the exception of four drums of U-listed wastes and several drums of non-hazardous waste (polymers) (E & E 1990). All wastes stored in the facility are generated by Olin Water Services. On occasion, a customer may return an off-specification product to be reworked. The actual composition of the drummed characteristic wastes is unknown. In addition, the quantity of wastes varies, but the facility inventory records obtained during the April 1990 VSI showed that 138 drums are stored in the container storage area (Appendix D). The last entry noted in the facility inventory list was on November 4, 1989. The majority of waste listed consisted of D001 ignitable waste (93 drums) and D007 EP toxic wastes (33 drums). The inventory also listed eight drums of D002 corrosive materials; three drums of orthodichlorobenzene; and one drum of pentachlorophenate. Bill Dame, Olin Plant Manager, has reported that 13 drums of off-specification product (Olin #2806) have been removed since the April 1990 VSI. Therefore, 125 hazardous waste containers were being stored in this RCRA-regulated unit at this writing. This waste has been stored in this SWMU greater than 90 days.

Release Controls

The storage facility is designed to physically and structurally hold an area four pallets wide by five pallets deep. The floor is constructed of a monolithically poured concrete base and slopes to the south toward a containment sump constructed of concrete reinforced with carbon steel wire mesh (Figure 5-1). The sump cover is made of a carbon steel grate. The sump capacity is sufficient to provide for collection of 10 percent of the storage facility's free liquid capacity (Olin 1987). Run-on is prevented by the cinder block walls on the south, east, and west sides of the facility and an access ramp on the north side of the storage area. Under the terms of the Part B Permit, drums of aqueous waste material should be placed between ignitable and reactive solid materials and ignitable liquids to form a buffer zone (Olin 1987). During the VSI, it was unclear whether an adequate buffer zone was in place for this unit; however, the actual potential of a fire and/or violent reaction is inherently low due to the characteristics of

the chemicals utilized at the Olin facility.

The hazardous waste container storage area is inspected by Olin personnel for adequate aisle space, container deterioration, and condition of containment floor and sump. If liquid accumulates in the storage area it is pumped with a portable sump pump into 55- or 30-gallon container(s). The wastes are sampled and analyzed as outlined in the EPA/KDHE Part B Waste Analysis Plan (Olin 1983). If the liquid is found to meet all the sanitary sewer discharge requirements as addressed in Olin Water Services Wastewater Discharge Permit (#I880) (Appendix E) it will be discharged to the sanitary sewer via one of the trench drains inside the plant. However, if the accumulated wastes are determined to exhibit hazardous wastes characteristics, it will be placed in the hazardous waste container storage area (E & E 1990).

History of Releases

Available file information provided no documentation or indication of releases from this unit. Observations made during the VSI provided no indications of any releases from this unit. Drummed wastes were neatly stacked and did not exceed the 12-foot linear height requirement addressed in Olin's Part B Permit (Olin 1987; E & E 1990). Overall, the containers and the concrete floor of the hazardous container storage area were in adequate condition; however, a few drums were slightly dented, and an empty drum was blocking the aisle at the sump located in the back of the storage facility. The containment sump was not thoroughly inspected during the VSI, so the integrity of this containment feature is unknown.

5.1.2 Further Information Needs

The Olin/Drew purchase agreement called for all waste in the hazardous wastes container storage area to be disposed off site. Olin planned to have this completed by November 30, 1990 (Dame 1990). Further information is needed to verify whether removal of the hazardous waste from the container storage area has been accomplished. Furthermore, proper closure proceedings will need to be addressed by the new facility owners (Drew Industrial Division).

5.2 VSR SUMP VAT AND DRAINAGE

5.2.1 Information Summary

Unit Description

The volatile steam return (VSR) formulating area includes two rooms consisting of a blending area with five tanks and related equipment and an area referred to as the Drum-off Room (Figure 5-1). It should be noted that the name given to this blending area refers to the production of volatile amines which were produced in this area 20 years ago. This application, that the name implies, no longer exists for this formulation area. One of the blending tanks in the VSR Room was a Fuel Oil Treatment (FOT) tank, with a capacity of 1,000 gallons. An Olin representative reported that this tank had been out of service about a year due to the elimination of fuel treatment products. Since the VSI, this tank has been removed from the VSR Blending Room (Prouty 1990). The VSR tank, (capacity 2,000 gallons) is still used and is made of stainless steel (Appendix A, Photo 12). Three smaller stainless steel blending tanks with capacities of 100, 300, and 750 gallons are also utilized in the VSR Room and are located along the east wall. All tanks are situated on a monolithically poured concrete base. The VSR Drum-off Room is a packaging room for finished products; chemicals from the VSR blending tanks are pumped and containerized into drums.

The waste from the two rooms is collected in a self-contained sump vat located outside between the production plant and the empty product storage tank. The above-ground steel vat is about 2 feet by 6 feet and has a maximum capacity of 100 gallons (Appendix A, Photo 14). The VSR blending room has a one foot wide by two foot deep concrete in-floor trench with a covered metal grate (Appendix A, Photo 12). This floor trench is continuous with the containerized sump vat (Appendix A; Photo 14; Figure 5-1). The maximum capacity of the trench is also 100 gallons. The collection trench in the VSR Drum-off Room comprises the entire floor with an outlet located in the northeast corner with PVC piping extending outside to the containerized steel sump vat (Appendix A, Photos 13 and 15; Figure 5-1). When appropriate, a float-activated pump is installed on the VSR sump vat to prevent trench and sump overflow. When the pump is activated, waste from the VSR sump vat is

pumped into nearby 55-gallon drums. About four drums (200 gallons) of aqueous waste would accumulate on an average of 6 to 7 working days. After this period, the drums would be replaced. The VSR sump vat and drainage units do not require a RCRA permit.

Dates of Operation

Specific start date is unknown; however, it is known to be after 1970. The unit is active.

Waste Managed

Various raw materials (Appendix C) are utilized in the VSR formulating area and exhibit hazardous characteristics (reactive-corrosive-ignitable-toxic). The type of characteristic waste generated in this blending area varies depending on the compound produced. At one time, a large percentage of chromium product was produced in this blending area generating D007 characteristic waste (EP toxic for chromium). However, through the Olin/Drew purchase agreement, Olin Water Services in Kansas City has eliminated the production of chromium products. Currently, the majority of wastes generated in this formulating area include characteristic corrosive waste (D002). A minimal amount of characteristic reactive waste (D003) are also generated (Prouty 1990).

Any aqueous wastes generated in this blending area is from spillage from drum loading operations or non-reusable rinse water from the blending process. Wastes are collected in the trench and sump vat system and retained there until full capacity is reached (Prouty 1990). Full capacity is about 200 gallons and when the float activated pump and nearby 55-gallon drums for overflow are not in place, the accumulated wastes in the sump vat and trench would be pumped out about every 2 days (Dame 1991). The wastewater is tested about once or twice a week and the majority is either recycled as make-up water for succeeding batches or discharged down the sewer collection system after neutralization (Bosky 1987; Prouty 1990). All generated waste material is neutralized to meet the pretreatment agreements for Publicly Owned Treatment Works (POTW) discharge parameters outlined in Olin's wastewater discharge permit (#I880) (Appendix E). If analysis indicated that the liquid

exhibits hazardous waste characteristics or that the liquid does not meet the sewer discharge parameters, the waste will be placed into a suitable container and stored in the container storage area. As of January 17, 1985, there are two drums of VSR drum waste (D007) stored in the RCRA-regulated container storage area (Appendix D).

Release Controls

Any liquid spillage from the VSR formulating area is either washed down into the trenching and sump vat system or collected with an industrial absorbent and containerized (Bosky 1987). The wastewater collection trench and sump vat units are isolated from the main plant sewer discharge system and act as release control features for the VSR formulating area.

The integrity of the collection trenches are unknown. The sump vat itself is not surrounded by any secondary containment structure; however, it is mounted on a concrete pad base. These units are inspected by Olin on a regular basis.

History of Releases

A KDHE compliance inspection conducted on July 29, 1986, indicated a liquid discharge from the VSR sump vat onto the ground (Smith 1986). The exact amount of liquid discharge was not reported in the KDHE Compliance Inspection; however, a Drew representative reported that the seepage from the sump vat during the 1986 State inspection was the result of previous sump vat overflows of small unmeasurable quantities (merely wetting the sides of the sump vat). A sample obtained from this liquid revealed chromium contamination. After this incident, the facility installed a float activated pump on the VSR sump vat to prevent sump overflow (Fischer 1986). When the pump is activated, wastes from the VSR sump vat would be pumped into nearby 55-gallon drums and placed outside on a wooden pallet. The liquid level was checked daily to assure that the drum would not overflow. The drummed waste would be sampled and analyzed under the same analytical criteria as the sump vat wastes.

During the April 1990 FIT VSI, the float-activated pump and nearby 55-gallon drums for overflow were not in place for the VSR formulating

area. However, when chromium products were being manufactured, the VSR overflow system was operational (Dame 1990). Chromium residual that adhered to the VSR floor and drainage system was flushed and cleaned with water and the rinsate was accumulated in 2 to 4 55-gallon drums.

Since the July 1986 RCRA inspection, there has been no other documentation or indications of releases from this SWMU system. Presently, the VSR overflow system is no longer used by Olin Water Services because chromium products are no longer produced. The VSR sump vat and collection trench is monitored (visual inspection) from the inside of the VSR Blending Room (Dame 1990). Olin/Drew representatives are considering removing the VSR sump vat unit and incorporating an automatic on/off valve attachment to the present collection trench system; therefore, drainage could then be released to the plant's sewer discharge outlet. During the writing of the final draft of this report, Olin Water Services reported to FIT that the self-contained drainage system that was once emplaced in the VSR Blending Room had been eliminated; drainage from this formulating area is now connected to the plant's sewer system with an appropriate automatic on/off valve attachment to regulate whether it is continuous with the plant's sewer discharge system (Dame 1991).

Observations made during the April 1990 VSI provided no indications of releases from the VSR sump vat and drainage system. However, the paint on the steel containerized sump vat was corroded (Appendix A; Photo 14). A small amount of pasty liquid was noted on the floor in the VSR Blending Room. The blending product tanks were in adequate condition.

5.2.2 Further Information Needs

None required at this time.

5.3 C/F BLENDING ROOM DRAINAGE

5.3.1 Information Summary

Unit Description

The Corrosive or Flammable (C/F) Blending Room consists of a 2,000-gallon blending tank and utility storage tank. The utility

storage tank has a capacity of 2,000 gallons and stores raw material for use in the blending process. Both tanks are situated on a monolithically poured concrete base. Finished compounds are packaged in the C/F Blending Room by Olin personnel. Like the VSR Room, the name given to the C/F Blending Room was dedicated 20 years ago. Currently, the area is not restricted to only formulating corrosive or flammable products.

The aqueous waste from this formulation area is collected in an in-floor concrete trench topped with a metal grate (Appendix A; Photo 16). This concrete floor drainage trench measures one foot by two feet and is located in front of the two tanks, running north to south; and along the entrance running east/west (Figure 5-1). The maximum capacity of the C/F drainage system is 100 gallons. An on/off valve located in the center of the C/F drainage system regulates whether it is continuous with the plant's sewer discharge system (Appendix A; Photo 17; Figure 5-1). The C/F Blending Room drainage does not require a RCRA permit.

Dates of Operation

The specific start date is unknown; however, it is known to be after 1970. The unit is active.

Wastes Managed

The C/F Blending Room is used interchangeably with the VSR Formulation Area. Similarly to the VSR Room, a variety of materials (Appendix C) exhibiting hazardous characteristics are used to produce the finished water treatment compounds. The type, analysis, and management of wastes generated in this blending room are also similar to the current operations of VSR Formulating Area (See Section 5.2). It is unknown whether any wastes generated in the C/F Blending Room during the aqueous batching process is recycled as make-up water for succeeding batches. The C/F Blending Room is also utilized as a drum-off area (packaging area) for polymers (non-hazardous material). After the packaging process is completed, the generated wastes would be drummed because of its high chemical oxygen demand (COD) characteristic. The last time this type of material was placed in the hazardous container storage area was 1989 (Dame 1991). During the batching process, the majority of generated wastes after analysis by Olin personnel is

discharged directly into the municipal sanitary sewer system (E & E 1990).

Release Controls

If spillage occurs in the C/F Blending Room, it is washed into the 100 gallon collection trench (aqueous materials). Similarly to the VSR room, the trench is embedded into the concrete floor and acts as a containment feature for the C/F Blending Room. The integrity of the trench is unknown. Unlike the VSR room, the collection trench in the C/F Blending Room discharges to the plant's sanitary sewer line. However, a control valve can isolate the C/F Blending Room drainage from flowing continuously with the main sewer line. The trench is emptied only after it reaches full capacity and appropriate analysis has been conducted by Olin personnel. This unit is checked by Olin on a regular basis.

History of Release

Available file information provided no documentation or indication of releases from this unit. Observations made during the VSI provided no indications of releases from this unit. The blending product tanks also appeared to be in good condition.

5.3.2 Further Information Needs

None required at this time.

5.4 CONTINUOUS SEWER DISCHARGE OUTLET AND ASSOCIATED PIPING

5.4.1 Information Summary

Unit Description

The plant discharge drain is a 12-inch piping system which extends throughout the plant building (E & E 1990). The overall layout of the plant's drainage system is unknown; however, the discharge outlet to the POTW is located on the southwest side of the plant building (Figure 5-1). The Sodium Chloride Blending Room collection trench as well as all other trenches and drains in the plant building, except for the C/F and VSR Blending Rooms, are open continuously to the municipal sewer system (Prouty 1990). The Sodium Chloride Blending Room/Area has two

reinforced plastic storage tanks, each having a 2,000 gallon capacity. Wastes are collected in a collection trench topped with a metal grate running north-south in front of the two blending tanks (Figure 5-1). The Olin Water Services open drainage system falls under the auspices of a POTW Wastewater Discharge Permit (#1880); the issue date is November 14, 1989; the expiration date is November 14, 1994 (Appendix E). The plant's drainage flows into a sanitary/industrial sewer line which runs south from the Olin property to the Fairfax Pump Station located at 1520 W. 2nd Street (Gill 1990). The plant's sewer system does not require a RCRA permit.

Dates of Operation

The specific startup date is unknown. The unit is active.

Wastes Managed

Any spillage or washdown water from the sodium chloride batching process or any other area in the plant building (except for the C/F and VSR Blending Rooms) are routed to the plant's discharge outlet. Olin representatives have verified that the generated wastes from the sodium chloride blending process is minimal and meets all POTW discharge parameters (Dame 1990; Prouty 1990). Therefore, neutralization does not occur before discharging to the municipal sewer system.

A separate blending room called the Powder Blending Room is located west of the VSR Drum-off Room (Figure 5-1). This room is not utilized very much and is where Olin formulates flammable solids (D001) such as sodium sulfite and sodium hydrosulfite (Dame 1990). It is unknown if this blending area maintains a collection trench/drain for spillage or washdown water and discharges to the plant's discharge system. It is thought that dry spillage from drum loading is swept up and placed into a product drum (Bosky 1987).

The Olin Wastewater Discharge Permit has indicated that the permittee will not discharge any wastewater having a pH lower than 5.5 or higher than 9.5 or containing any other prohibited substance or material in accordance with the Code of City Ordinances, Chapter 30, Articles I - VII (Appendix E). Sampling does occur at two periods throughout the year; samples are collected during normal working hours

at the plant's discharge outlet before wastewater enters the municipal sanitary sewer system.

The facility's average daily discharge flow for the entire plant is about 450 gallons with the maximum being 600 gallons (Gill 1990).

Release Controls

Similar to the other wastewater collection trenches/drains within the manufacturing plant, the sodium chloride collection trench is embedded into the concrete floor. The trench executes as a release control for this area in the plant building. The integrity of this collection system and the overall plant drainage is unknown. This SWMU is inspected regularly by Olin personnel.

History of Releases

Available file information provided no indication of any spills from this unit. In addition, the floor in the Sodium Chloride Blending Room was clean and the blending tanks appeared in good condition. Throughout the plant building, good housekeeping practices were observed. It has been reported that the Olin Water Services has not been deficient on its wastewater permit requirement for the past two years. In addition, Olin has probably never exceeded the limitations outlined in the POTW permit (Gill 1990). Samples collected by Olin personnel in January 1990 at the POTW discharge outlet indicate that the facility is within discharge limitations (Appendix F).

5.4.2 Further Information Needs

A map illustrating the overall layout of the plant building's drainage system would be helpful to completely assess this SWMU.

5.5 DUMPSTERS

5.5.1 Information Summary

Unit Description

There are two dumpsters located in the production yard. These two solid waste disposal units are adjacent to the loading dock area southeast of the plant building (Figure 5-1). Both nonhazardous waste

receptacles are made of steel. The dimensions of both are about 6 feet high by 10 feet wide by 5 feet deep. The hauling company is Shostak Iron and Metal Company, telephone 321-9210. These units are SWMUs and do not require a RCRA permit.

Dates of Operation

The specific start date is unknown. The unit is active.

Waste Managed

The dumpster located east of the south loading dock contains solid wastes such as scrap building materials and empty unusable drums, which have been triple rinsed and crushed (Appendix A; Photos 10 and 11). The dumpster located in the southeast corner of the same loading dock usually contains sanitary trash, plastic, and some crushed, triple-rinsed drums (Prouty 1990). The drums are recycled until they are no longer usable. The drum rinsing process takes place directly in the formula-ting batch tanks in the VSR and C/F Blending rooms only. A manlift reaches to the top of the tank where an Olin employee rinses and cleans the drum (Prouty 1990). The non-hazardous solid waste contained in these dumpsters are periodically disposed at the Johnson County Landfill. The amount of waste generated varies; it is usually less than two tons a year (E & E 1990).

Release Controls

These SWMUs are made of steel and rest on a monolithically poured concrete slab. These units are inspected regularly by the Olin personnel.

History of Releases

File information provided no documentation of releases from the units. Observations made during the VSI indicated no releases from these units.

5.5.2 Further Information Needs

None required at this time.

5.6 SATELLITE ACCUMULATION AREA

5.6.1 Information Summary

The Olin Water Services operates an on-site laboratory in the plant building (Figure 5-1). This lab is not utilized to a great extent and has become strictly a Quality Control (QC) lab (Dame 1990). Presently, the lab is used to conduct disposal analysis (testing waste generated by Olin), water analysis for customers, and some biochemical analysis. Small amounts of "F-listed" chlorinated solvents (methylene chloride) are being used in the Olin laboratory to clean lab ware. The resulting waste is accumulated in five-gallon safety cans and stored temporarily under the lab sink; this has been designated a satellite accumulation area. When the container is full, it is transferred to a 30-gallon drum which is also stored in the laboratory (Dame 1990). When the 30-gallon drum reaches capacity, which takes several years, it is stored in the permitted hazardous container storage area until shipment. These temporary waste containers are SWMUs, and do not require a RCRA permit. The FIT was unable to determine the start-up date of this SWMU, but the unit is currently active. This unit has no release controls. No releases or housekeeping problems were observed during the VSI.

5.6.2 Further Information Needs

None required at this time.

5.7 AREA OF CONCERN

5.7.1 Information Summary

There are two above-ground product storage tanks located on the east side of the production plant (Figure 5-1). The south tank is internally divided into three 2,000-gallon compartments (Appendix A; Photo 9; Appendix G). This tank once contained flammable material and has been empty since the Drew/Olin purchase agreement in December 1989, and January 1990. When utilized, the southern compartment of the 6,000 gallon tank contained morpholine and the center and northern compartments stored cyclohexylamine since 1985. Historically, the center tank has been used for several different materials. Initially, kerosene was stored in the center section; and in the 1970s, the compartment was used for storage of aromatic naphtha (Appendix G). The

north tank (capacity 10,000 gallons) currently contains sodium hydroxide (Appendix A; Photo 8). Prior to the April 1990 VSI, Jim Fischer of KDHE reported to FIT that during his most recent compliance inspection he found soil discoloration near the north product storage tank (sodium hydroxide tank). However, during the April 1990 VSI, no evidence of a spill or pooling liquid was observed. It should be noted that the stained area may have been washed away by precipitation. The FIT was unable to determine the start-up dates of these two tanks. Currently, there are no secondary containment features surrounding the tanks. Future plans are to remove the two product storage tanks and replace them with a tank farm, consisting of about 16 5,600-gallon to 9,600-gallon storage tanks (E & E/FIT 1990).

An environmental audit was conducted by Drew/Ashland representatives, as outlined in the December Drew/Olin purchase agreement (Appendix G). The environmental audit was conducted by a subcontractor in November 1989 for purposes of decision making regarding the purchase of Olin property. The audit consisted of the installation of three monitoring wells on the Olin Water Services site and the collection of twelve soil borings (depths ranging in 1.5 to 9.0 feet) with nine being submitted to the laboratory for analysis. Analysis for ground water and soil samples consisted of volatile organic compounds (VOCs), semi-volatile organic compounds, pesticides, and total metals for soil samples, and dissolved metals for water samples. For a complete copy of laboratory results and sample locations see Appendix G.

Analytical water sample analysis indicated trichloroethylene (TCE) in all three monitoring wells at concentrations ranging from 5.9 and 34 µg/L and 1,2-dichloroethylene (1,2-DCE) in monitoring well #2 at a concentration of 23 µg/L. Monitoring well #1 had the highest TCE concentration and is located east of the plant building between the two aboveground storage product tanks (Appendix G; Figure 1).

The soil boring analyses indicated soil contamination around the aboveground storage tanks and in the lot south of the plant building. The analysis indicated the majority of the soil contamination at a depth down to 4 feet and near the southernmost aboveground storage tank (Appendix G; Tables 1 to 3). Common fuel constituents such as benzene,

toluene, xylene, and ethylbenzene were detected in soils near the south tanks at concentrations ranging from 5.7 µg/kg to 2,700 µg/kg. In addition, dichlorobenzene was found in two of the soil borings with the highest concentration at 9,300 µg/kg. Soil investigations also indicated TCE at a concentration of 58 µg/kg in the south lot of the plant building near the empty drum storage area. Several polycyclic aromatic hydrocarbons (PAHs) were also detected at one soil boring location (SB-10) near the south tank (Appendix G; Figure 1). This sample was collected at a 1.5 to 3.5 foot interval and PAH concentrations ranged from 930 µg/kg to 2,200 µg/kg. Pentachlorophenol (PCP), a wood preservative was detected at 22,000 µg/kg at the same interval and location.

1,1,2,2-tetrachloroethane was also found at deeper depths (7 and 9 feet) at SB-10 as well as in a number of shallower borings around both aboveground tanks (concentrations ranged from 11 µg/kg to 500 µg/kg). Morpholine and cyclohexnone were also detected at low concentrations (ranging from 220 µg/kg to 990 µg/kg) in several shallow soil borings around the south tank (Appendix G; Table 2). These two compounds were once stored in the southernmost aboveground tank. The most significant metal concentration was chromium at 260 µg/kg collected at a 1.5 to 3.5 foot soil interval near the south tank. This concentration is almost 10 times greater than all other chromium concentrations detected in the eastern section of the plant building (Appendix G; Table 3).

5.7.2 Further Information Needs

The Drew Pre-Acquisition Investigation (PAI) report has indicated that soil and ground water contamination has occurred on the property of the Olin Water Services facility. Drew representatives have indicated that a follow-up investigation has also been conducted. This report should also be reviewed to further characterize the potential problems of the Olin facility.

SECTION 6: SUMMARY OF SITE VISIT

The VSI of Olin Water Services was conducted on April 27, 1990. The VSI began at 0900 hours and was completed by 1230 hours. The inspection was conducted by FIT personnel Patty Roberts and Otavio Silva, EPA/RCRA representative Mark Matthews, and KDHE/RCRA representative Paul Cahoon. The Olin Water Services representatives were William Dame and Larry Prouty. William Olasin from the Ashland Chemical Company was also present. The VSI began with an inspection of the warehouse, which serves as a shipping and receiving area. This warehouse also houses some administrative offices. No SWMUs were identified in this building.

After inspecting the inside of the warehouse, the FIT inspected the east perimeter of the plant building where two aboveground product storage tanks are located. Next, FIT inspected the interior of the plant facility, which houses all the chemical formulating areas as well as the Olin laboratory. The RCRA-regulated hazardous container storage area located in the production yard was also inspected. After the reconnaissance of the plant facility and its perimeter, six SWMUs and one area of concern as detailed in Section 5 were identified. Photo documentation was conducted during the VSI and is included as Appendix A. No indication of any releases were observed by the FIT during the VSI.

SECTION 7: SUMMARY AND CONCLUSIONS

The E & E/FIT was tasked under the U.S. EPA's EPI program to conduct a background review and VSI of the Olin Water Services-Olin Corporation site located in Kansas City, Kansas. The VSI was conducted on April 27, 1990, in coordination with RCRA and company officials. The scope of the EPI/PA was to identify, characterize, and determine releases from SWMUs at the facility.

Olin Water Services has been in operation since 1970 and manufactures chemicals for industrial water treatment facilities. Processes include batch blending of approximately 150 different raw materials, to formulate approximately 250 water treatment compounds. The waste generated during this blending process can vary and exhibits hazardous characteristics, such as ignitability, corrosivity, reactivity, and/or toxicity. Wastes generated during the blending process consist of spillage from loading operations or rinsewater; most of this waste is recycled or discharged down the sanitary sewer system after analysis designates that it is within the parameters outlined under the POTW permit (#I880). The majority of wastes that are accumulated is from raw material and finished products that are unuseable as off-specification. These various wastes as well as any other designated hazardous waste are stored in the RCRA-regulated hazardous container storage area. Olin operates as a storage facility under a Part B Permit notification. In addition to being a storage facility, the Olin site has been classified as a Kansas generator; that is, the facility generates between 25 and 1,000 kilograms of hazardous wastes per month.

The FIT identified six SWMUs during the VSI at the facility. The SWMUs were identified and a brief description of each is as follows.

Hazardous Waste Container Storage Area

This SWMU is a 3-sided cinder block building located in the production yard. The maximum number of drums stored in this facility is not to exceed 200 55-gallon drums. Both hazardous and non-hazardous (liquid and solids) wastes are stored in this storage area for a

long-term basis. Future plans are to dispose of all hazardous wastes in the container storage area.

VSR Sump Vat and Drainage

This SWMU consists of an outside sump vat and in-floor trenches from the VSR Blending and Drum-off rooms. When appropriate an activated pump is installed on the VSR sump vat and overflow is pumped into nearby 55-gallon drums. Spill over, washdown water, or any other wastes from the chemical formulating process is collected in this self-contained drainage system. The generated waste is analyzed and the majority is either recycled or discharged down the sanitary sewer collection system after neutralization. If determined hazardous it is retained in the permitted container storage area.

C/F Blending Room Drainage

This SWMU comprises an in-floor concrete trench topped with a metal grate encompassing the majority of the C/F Blending Room. This drainage system intercepts waste spillage or washdown water and has a maximum capacity of 100 gallons. An on and off valve connected to the C/F trench regulates, if this unit is continuous with the municipal sanitary sewer collection system. Generated wastes are analyzed and managed in the same manner as the VSR Blending Room.

Continuous Sewer Discharge Outlet and Associated Piping

The plant discharge drain is a 12-inch piping system which extends throughout the plant building. This drainage system intercepts spill over or washdown water from all concrete areas in the plant building except for the VSR and C/F Blending Rooms. However, during the writing of the final draft of this report, Olin Water Services/Drew reported to FIT that the VSR Blending Room self-contained drainage system had been eliminated and is currently connected with the plant's sewer discharge system. The newly incorporated drainage system has an on/off valve attachment to regulate drainage flow. The discharge outlet to the POTW is located on the southwest side of the plant building. Wastewater is analyzed and discharged to the Kansas River under the auspices of a pretreatment agreement with the city.

Dumpsters

This SWMU consists of two steel non-hazardous solid waste receptacles. The amount of solid waste varies throughout the year and consists mostly of scrap building material and clean, unuseable drums.

Satellite Accumulation Area (lab wastes)

This unit is inside the Olin laboratory and consists of a 5-gallon safety can and a 30-gallon drum of collected chlorinated solvents (F001). F001 wastes are stored in the 30-gallon drum until full, then sealed and moved to the permitted container storage area, until shipment.

Areas of Concern

During the VSI, two above-ground product storage tanks located on the east side of the production plant, were also inspected. A concern has been noted by a State official pertaining to an alleged spill around the northern-most storage tank (sodium hydroxide). However, FIT observed no evidence of a spill or potential problem with this area.

In 1986, a release did occur from the VSR sump vat located between the plant and the southern-most storage tank. The resulting problem revealed chromium contamination. To mitigate the problem, Olin formulated an overflow pumping and temporary storage system during the production of chromium products in the VSR blending area. No other releases around the sump vat area have been documented.

Olin was purchased by Drew Industrial Division in December 1989, and has future plans to construct a 16-tank farm in the east section of the production plant. Drew conducted an environmental audit in November 1989, including the installation of three monitoring wells, one of which is located in the eastern section of the Olin property. The results of this Pre-Acquisition Investigation indicated that the soil is contaminated with VOCs, PAHs, and metals in the eastern portion of the plant building, with the majority of the contamination around the former morpholine and cyclohexylamine tank. The investigation also showed that the ground water at the facility is contaminated, with the most significant contaminant being TCE at 34 µg/L in monitoring well #1. For

more details, see Section 5.7 and Appendix G.

Observations made during the April 1990 VSI of the above-mentioned SWMUs and the facility as a whole indicate that the operational procedures are of good standing. In general, the plant building and production yard was clean and well organized. Waste handling practices were acceptable, with no releases or spills noted.

SECTION 8: BIBLIOGRAPHY

- Bosky, John W., April 20, 1987, Environmental Engineer, U.S. EPA, EPA/KDHE RCRA Compliance Inspection Report, Olin Water Services-Olin Corporation, Kansas City, Kansas.
- Cahoon, Paul, July 5, 1990, Kansas Department of Health and Environment, telephone conversation with Patty Roberts, E & E/FIT.
- Dame, William E., October 10, 1990, Plant Manager, Olin Water Services, telephone conversation with Patty Roberts, E & E/FIT.
- Dame, William E., October 9, 1991, Plant Manager, Olin Water Services, telephone conversation with Patty Roberts, E & E/FIT.
- Ecology and Environment, Inc., Field Investigation Team (E & E/FIT), April 1990, Log Book for Preliminary Assessment of Olin Water Services Site, Kansas City, Kansas, TDD #F-07-9003-005.
- Fischer, Jim, November 3, 1986, RCRA Inspector, Kansas Department of Health and Environment, KDHE/RCRA Follow-up Compliance Inspection Letter, Olin Water Services-Olin Corporation, Kansas City, Kansas.
- Fischer, Jim, April 1990, RCRA Inspector, Kansas Department of Health and Environment, telephone conversation with Patty Roberts, E & E/FIT.
- Gill, Glenn, July 2, 1990, Manager, Water Pollution Control Department, telephone conversation with Patty Roberts, E & E/FIT.
- Hason, Syed E., et al., 1988, Geology of Greater Kansas City, Missouri and Kansas, United States of America, Bulletin of the Association of Engineering Geologists, Vol. 25 #3 227-342.
- Kansas Geological Survey, 1963, The Geologic History of Kansas, Bulletin 162, Lawrence, Kansas.
- Olasin, William C., September 19, 1991, Environmental Engineer, Ashland Chemical Company, letter to Lyndell L. Harrington P.E., U.S. Environmental Protection Agency - RCRA Branch.
- Layne Western Co., 1979, Well Log for Owens-Corning Fiberglas Corporation, Kansas City, Missouri.
- Olin Water Services, March 10, 1983, EPA/KDHE Part B Hazardous Waste Permit Application for Container Storage Facility, Initial Filing, Kansas City, Kansas EPA I.D. #KSD000203638.
- Olin Water Services, November 18, 1987, EPA/KDHE Part B Hazardous Waste Permit Application for Container Storage Facility, Revised Pages, Kansas City, Kansas, EPA I.D. #KSD000203638.

Prouty, Larry, October 5, 1990, Manager, Regulatory Affairs, Olin Water Services, telephone conversation with Patty Roberts, E & E/FIT.

Smith, Ronald L., July 29, 1986, RCRA Inspector, Kansas Department of Health and Environment, KDHE RCRA Compliance Inspection Report, Olin Water Services-Olin Corporation, Topeka, Kansas.

U.S. Department of Agriculture, 1977, Soil Survey of Leavenworth and Wyandotte Counties, Kansas, Washington, D.C.

U.S. Geological Survey, 1964, 7.5 Minute Topographic Maps, North Kansas City, Parkville Quadrangles, Kansas-Missouri, Washington D.C.

U.S. Geological Survey, 1975, 7.5 Minute Topographic Maps, Kansas City, Shawnee Quadrangles, Missouri-Kansas, Washington, D.C.

U.S. Geological Survey, 1980, Water Resources Data for Missouri, Rolla, Missouri.

Woods, Kristina M., December 27, 1989, Environmental Attorney, Ashland Chemical Company, Letter to John Goetz, Kansas Department of Health and Environment.

APPENDIX A

SITE PHOTOGRAPHS

Ecology and Environment, Inc.

PHOTOGRAPHIC RECORD

SITE NAME: Olin Water Services

SITE LOCATION: Kansas City, Kansas

TDD/PAN#: F-07-9003-005/FKS0285RA

No: 1

Subject

Olin Water Services Plant
Building and Warehouse.

Photographer

Otavio Silva

Witness

Patty Roberts

Date/Time

4/27/90 - 1235 hours

Direction

Southeast



No: 2

Subject

Production Yard

Photographer

Otavio Silva

Witness

Patty Roberts

Date/Time

4/27/90 - 1237 hours

Direction

East



Ecology and Environment, Inc.

PHOTOGRAPHIC RECORD

SITE NAME: Olin Water Services

SITE LOCATION: Kansas City, Kansas

TDD/PAN#: F-07-9003-005/FKS0285RA

No: 3

Subject

Production Yard Empty Drum
Storage Area.

Photographer

Otavio Silva

Witness

Patty Roberts

Date/Time

4/27/90 - 1145 hours

Direction

Southwest



No: 4

Subject

Hazardous Waste Container
Storage Area

Photographer

Otavio Silva

Witness

Patty Roberts

Date/Time

4/27/90 - 1130 hours

Direction

Southwest



PHOTOGRAPHIC RECORD

SITE NAME: Olin Water Services

SITE LOCATION: Kansas City, Kansas

TDD/PAN#: F-07-9003-005/FKS0285RA

No: 5

Subject

First row of the Hazardous Waste Container Storage Area.

Photographer

Otavio Silva

Witness

Patty Roberts

Date/Time

4/27/90 - 1132 hours

Direction

South



No: 6

Subject

Second and third rows of the Hazardous Waste Container Storage Area.

Photographer

Otavio Silva

Witness

Patty Roberts

Date/Time


4/27/90 - 1134 hours

Direction

Southeast



PHOTOGRAPHIC RECORD



SITE NAME: Olin Water Services

SITE LOCATION: Kansas City, Kansas

TDD/PAN#: F-07-9003-005/FKS0285RA

No: 7

Subject

Fourth row of the Hazardous Waste Container
Storage Area.

Photographer

Otavio Silva

Witness

Patty Roberts

Date/Time

4/27/90 - 1136 hours

Direction

South

No: 8

Subject

Sodium hydroxide tank. The tank
capacity is 10,000 gallons.

Photographer

Otavio Silva

Witness

Patty Roberts

Date/Time

4/27/90 - 1150 hours

Direction

Southwest



Ecology and Environment, Inc.

PHOTOGRAPHIC RECORD

SITE NAME: Olin Water Services

SITE LOCATION: Kansas City, Kansas

TDD/PAN#: F-07-9003-005/FKS0285RA

No: 9

Subject

Empty product storage tank.
The tank once contained
flammable material.
Capacity is 6,000 gallons.

Photographer

Otavio Silva

Witness

Patty Roberts

Date/Time

4/27/90 - 1152 hours

Direction

Southwest



No: 10

Subject

Dumpster for non-hazardous
solid waste disposal.

Photographer

Otavio Silva

Witness

Patty Roberts

Date/Time

4/27/90 - 1145

Direction

Northeast



PHOTOGRAPHIC RECORD

SITE NAME: Olin Water Services

SITE LOCATION: Kansas City, Kansas

TDD/PAN#: F-07-9003-005/FKS0285RA

No: 11

Subject

Contents of dumpster.

Photographer

Otavio Silva

Witness

Patty Roberts

Date/Time

4/27/90 - 1147 hours

Direction

East



No: 12

Subject

Volatile Steam Return (VSR) blending room.
In the background is VSR blending tank
(capacity 2,000 gallons).

Photographer

Otavio Silva

Witness

Patty Roberts

Date/Time

4/27/90 - 1115 hours

Direction

Northeast



PHOTOGRAPHIC RECORD



SITE NAME: Olin Water Services

SITE LOCATION: Kansas City, Kansas

TDD/PAN#: F-07-9003-005/FKS0285RA

No: 13

Subject

VSR Drum-off room. In background is the drainage outlet which leads to the containerized sump vat.

Photographer

Otavio Silva

Witness

Patty Roberts

Date/Time

4/27/90 - 1117 hours

Direction

Southeast

No: 14

Subject

VSR sump vat.

Photographer

Otavio Silva

Witness


Patty Roberts

Date/Time

4/27/90 - 1107 hours

Direction

West



PHOTOGRAPHIC RECORD



SITE NAME: Olin Water Services

SITE LOCATION: Kansas City, Kansas

TDD/PAN#: F-07-9003-005/FKS0285RA

No: 15

Subject
VSR sump vat and piping system from VSR
Drum-off room.

Photographer
Otavio Silva

Witness
Patty Roberts

Date/Time
4/27/90 - 1109 hours

Direction
South

No: 16

Subject
Corrosive or Flammable C/F) blending room.
In background is the C/F blending tank
(capacity 2,000 gallons).

Photographer
Otavio Silva

Witness
Patty Roberts

Date/Time
4/27/90 - 1120 hours

Direction
Southwest



PHOTOGRAPHIC RECORD



SITE NAME: Olin Water Services

SITE LOCATION: Kansas City, Kansas

TDD/PAN#: F-07-9003-005/FKS0285RA

No: 17

Subject

C/F Blending room waste collection trench.
Blue object is the on and off valve for
disposal to the Fairfax sanitary sewer system.

Photographer

Otavio Silva

Witness

Patty Roberts

Date/Time

4/27/90 - 1122 hours

Direction

Northwest

No: 18

Subject

Sodium Chloride Blending room waste
collection trench. Further north is the plant's
discharge outlet to the Fairfax sanitary sewer
system (not shown in photograph).

Photographer

Otavio Silva

Witness

Patty Roberts

Date/Time

4/27/90 - 1125 hours

Direction

West



Negatives for Photographic Record

Site Name OLIN WATER SERVICES

Site Location KANSAS CITY, KANSAS

TDD/PAN # F-07-9003-005/FKS0285RA



ecology and environment, inc.
OVERLAND PARK, KANSAS

APPENDIX B

EPA PRELIMINARY ASSESSMENT FORM 2070-12

| EPA | | POTENTIAL HAZARDOUS WASTE SITE PRELIMINARY ASSESSMENT PART 1 - SITE INFORMATION AND ASSESSMENT | | | | I. IDENTIFICATION | |
|--|--|--|--|---------------------------------------|---------------------------------------|-------------------|--------------|
| | | 01 STATE KS | | 02 SITE NUMBER KSD000203638 | | | |
| II. SITE NAME AND LOCATION | | | | | | | |
| 01 SITE NAME (Legal, common, or descriptive name of site) Ashland Chemical, Inc. (Olin) | | | 02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER 3155 Fiberglass Road | | | | |
| 03 CITY Kansas City | | | 04 STATE KS | 05 ZIP CODE 66115 | 06 COUNTY Wyandotte | 07 COUNTY CODE | 08 CONG DIST |
| 09 COORDINATES 39° 08' 47.0" N | | | LATITUDE 094° 36' 58.0" W | | LONGITUDE | | |
| 10 DIRECTIONS TO SITE (Starting from nearest public road) From I-635, exit on Kansas Highway 5 east. Stay on 5 Highway until Sunshine Road. Continue east on Sunshine Road until Fiberglass Road. Site is located at the intersection of Sunshine and Fiberglass roads. | | | | | | | |
| III. RESPONSIBLE PARTIES | | | | | | | |
| 01 OWNER (If known) Drew Inc. (Ashland Chemical Co.) | | | 02 STREET (Business, mailing, residential) P.O. Box 2219 | | | | |
| 03 CITY Columbus (Dublin) | | | 04 STATE OH | 05 ZIP CODE 43216 | 06 TELEPHONE NUMBER (614) 889-3065 | | |
| 07 OPERATOR (If known and different from owner) Ashland Chemical Co. | | | 08 STREET (Business, mailing, residential) 3155 Fiberglass Road | | | | |
| 09 CITY Kansas City | | | 10 STATE KS | 11 ZIP CODE 66115 | 12 TELEPHONE NUMBER (913) 621-6410 | | |
| 13 TYPE OF OWNERSHIP (Check one) <input checked="" type="checkbox"/> A. PRIVATE <input type="checkbox"/> B. FEDERAL: _____ <input type="checkbox"/> C. STATE <input type="checkbox"/> D. COUNTY <input type="checkbox"/> E. MUNICIPAL (Agency name) <input type="checkbox"/> F. OTHER: _____ <input type="checkbox"/> G. UNKNOWN (Specify) | | | | | | | |
| 14 OWNER/OPERATOR NOTIFICATION ON FILE (Check all that apply) <input checked="" type="checkbox"/> A. RCRA 3001 DATE RCVD: 11/18/80 <input type="checkbox"/> B. UNCONTROLLED WASTE SITE (CERCLA 103 c) DATE RCVD: _____ <input type="checkbox"/> C. NONE MO/DAY/YR MO/DAY/YR | | | | | | | |
| IV. CHARACTERIZATION OF POTENTIAL HAZARD | | | | | | | |
| 01 ON SITE INSPECTION BY (Check all that apply) <input checked="" type="checkbox"/> YES DATE 04/27/90 <input checked="" type="checkbox"/> A. EPA <input checked="" type="checkbox"/> B. EPA CONTRACTOR <input checked="" type="checkbox"/> C. STATE <input type="checkbox"/> D. OTHER CONTRACTOR <input type="checkbox"/> NO MO/DAY/YR <input type="checkbox"/> E. LOCAL HEALTH OFFICIAL <input type="checkbox"/> F. OTHER: _____ (Specify) CONTRACTOR NAME(S): Ecology and Environment, Inc. | | | | | | | |
| 02 SITE STATUS (CHECK ONE) <input checked="" type="checkbox"/> A. ACTIVE <input type="checkbox"/> B. INACTIVE <input type="checkbox"/> C. UNKNOWN | | | 03 YEARS OF OPERATION 1970 current UNKNOWN BEGINNING YEAR ENDING YEAR | | | | |
| 04 DESCRIPTION OF SUBSTANCES POSSIBLY PRESENT, KNOWN, OR ALLEGED This facility generates hazardous wastes from the preparation of liquid and powder water treatment formulations. Wastes identified and stored at the facility include D001 to D003, and D007 characteristic wastes. Various U-listed wastes could also be present. | | | | | | | |
| 05 DESCRIPTION OF POTENTIAL HAZARD TO ENVIRONMENT AND/OR POPULATION No imminent threat to the environment and/or population. The VSR Sump should be routinely inspected for failure as no secondary containment is present. | | | | | | | |
| V. PRIORITY ASSESSMENT | | | | | | | |
| 01 PRIORITY FOR INSPECTION (Check one. If high or medium is checked, complete Part 2 - Waste Information and Part 3 - Description of Hazardous conditions and Incidents) <input type="checkbox"/> A. HIGH <input type="checkbox"/> B. MEDIUM <input type="checkbox"/> C. Low <input checked="" type="checkbox"/> D. NONE *Facility routinely inspected by RCRA (Inspection required promptly) (Inspection required) (Inspect on time available basis) (No further action needed. Complete current disposition form) | | | | | | | |
| VI. INFORMATION AVAILABLE FROM | | | | | | | |
| 01 CONTACT Mark Matthews | | 02 OF (Agency/Organization) EPA/RCRA | | | 03 TELEPHONE NUMBER (913) 551-7635 | | |
| 04 PERSON RESPONSIBLE FOR ASSESSMENT Patty Roberts | | 05 AGENCY E & E | 06 ORGANIZATION FIT | 07 TELEPHONE NUMBER (913) 432-9961 | 08 DATE 10/22/91 MO/DAY/YR | | |

EPA

POTENTIAL HAZARDOUS WASTE SITE

PRELIMINARY ASSESSMENT

PART 2 - WASTE INFORMATION

I. IDENTIFICATION

01 STATE
KS

02 SITE NUMBER
KSD00020368

II. WASTE STATES, QUANTITIES, AND CHARACTERISTICS

01 PHYSICAL STATES

(Check all that apply)

| X A. SOLID | E. SLURRY |
|------------|-----------|
| 1 | 1 |
| 2 | 2 |
| 3 | 3 |
| 4 | 4 |
| 5 | 5 |
| 6 | 6 |
| 7 | 7 |
| 8 | 8 |
| 9 | 9 |
| 10 | 10 |
| 11 | 11 |
| 12 | 12 |
| 13 | 13 |
| 14 | 14 |
| 15 | 15 |
| 16 | 16 |
| 17 | 17 |
| 18 | 18 |
| 19 | 19 |
| 20 | 20 |
| 21 | 21 |
| 22 | 22 |
| 23 | 23 |
| 24 | 24 |
| 25 | 25 |
| 26 | 26 |
| 27 | 27 |
| 28 | 28 |
| 29 | 29 |
| 30 | 30 |
| 31 | 31 |
| 32 | 32 |
| 33 | 33 |
| 34 | 34 |
| 35 | 35 |
| 36 | 36 |
| 37 | 37 |
| 38 | 38 |
| 39 | 39 |
| 40 | 40 |
| 41 | 41 |
| 42 | 42 |
| 43 | 43 |
| 44 | 44 |
| 45 | 45 |
| 46 | 46 |
| 47 | 47 |
| 48 | 48 |
| 49 | 49 |
| 50 | 50 |
| 51 | 51 |
| 52 | 52 |
| 53 | 53 |
| 54 | 54 |
| 55 | 55 |
| 56 | 56 |
| 57 | 57 |
| 58 | 58 |
| 59 | 59 |
| 60 | 60 |
| 61 | 61 |
| 62 | 62 |
| 63 | 63 |
| 64 | 64 |
| 65 | 65 |
| 66 | 66 |
| 67 | 67 |
| 68 | 68 |
| 69 | 69 |
| 70 | 70 |
| 71 | 71 |
| 72 | 72 |
| 73 | 73 |
| 74 | 74 |
| 75 | 75 |
| 76 | 76 |
| 77 | 77 |
| 78 | 78 |
| 79 | 79 |
| 80 | 80 |
| 81 | 81 |
| 82 | 82 |
| 83 | 83 |
| 84 | 84 |
| 85 | 85 |
| 86 | 86 |
| 87 | 87 |
| 88 | 88 |
| 89 | 89 |
| 90 | 90 |
| 91 | 91 |
| 92 | 92 |
| 93 | 93 |
| 94 | 94 |
| 95 | 95 |
| 96 | 96 |
| 97 | 97 |
| 98 | 98 |
| 99 | 99 |
| 100 | 100 |

X B. POWDER, FINES X F. LIQUID

| C. SLUDGE | | G. GAS | |
|-----------|----|--------|-----|
| 1 | 2 | 3 | 4 |
| 5 | 6 | 7 | 8 |
| 9 | 10 | 11 | 12 |
| 13 | 14 | 15 | 16 |
| 17 | 18 | 19 | 20 |
| 21 | 22 | 23 | 24 |
| 25 | 26 | 27 | 28 |
| 29 | 30 | 31 | 32 |
| 33 | 34 | 35 | 36 |
| 37 | 38 | 39 | 40 |
| 41 | 42 | 43 | 44 |
| 45 | 46 | 47 | 48 |
| 49 | 50 | 51 | 52 |
| 53 | 54 | 55 | 56 |
| 57 | 58 | 59 | 60 |
| 61 | 62 | 63 | 64 |
| 65 | 66 | 67 | 68 |
| 69 | 70 | 71 | 72 |
| 73 | 74 | 75 | 76 |
| 77 | 78 | 79 | 80 |
| 81 | 82 | 83 | 84 |
| 85 | 86 | 87 | 88 |
| 89 | 90 | 91 | 92 |
| 93 | 94 | 95 | 96 |
| 97 | 98 | 99 | 100 |

D. OTHER

(Specify)

02 WASTE QUANTITY AT SITE

(Measures of waste quantities must be independent)

TONS

CUBIC YARDS

NO. OF DRUMS ~ 125

03 WASTE CHARACTERISTICS

(Check all that apply)

X A. TOXIC E. SOLUBLE I. HIGHLY VOLATILE

X B. CORROSIVE F. INFECTIOUS J. EXPLOSIVE

C. RADIOACTIVE G. FLAMMABLE X K. REACTIVE

D. PERSISTENT X H. IGNITABLE X L. INCOMPATIBLE

M. NOT APPLICABLE

III. WASTE TYPE (by waste characteristics)

| CATEGORY | SUBSTANCE NAME | 01 GROSS AMOUNT | 02 UNIT OF MEASURE | 03 COMMENTS |
|----------|-------------------------|-----------------|--------------------|---|
| SLU | SLUDGE | | | |
| OLW | OILY WASTE | | | |
| SOL | SOLVENTS | unknown | N/A | [methylene chloride, hydrazine, n-butyl |
| PSD | PESTICIDES | | | alcohol, 1,2-dichlorobenzene] |
| OCC | OTHER ORGANIC CHEMICALS | unknown | N/A | [pentachlorophenol, ethylenebis, salts, |
| IOC | INORGANIC CHEMICALS | | | and esters] |
| ACD | ACIDS | unknown | N/A | ethylenebisdithiocarbamic acid |
| BAS | BASES | | | |
| MES | HEAVY METALS | unknown | N/A | chromium |

IV. HAZARDOUS SUBSTANCES (See Appendix for most frequently cited CAS Numbers)

| 01 CATEGORY | 02 SUBSTANCE NAME | 03 CAS NUMBER | 04 STORAGE/DISPOSAL METHOD | 05 CONCENTRATION | 06 MEASURE OF CONCENTRATION |
|-------------|--------------------------------------|-----------------|----------------------------|------------------|-----------------------------|
| MES | chromium | 7440-47-3 | drums | unknown | N/A |
| SOL | n-butyl alcohol | 71-36-3 | drums | unknown | N/A |
| SOL | 1,2-dichlorobenzene | 95-50-1 | drums | unknown | N/A |
| SOL | [ethylenebisdithiocar- amic acid] | 111-54-6 | drums | unknown | N/A |
| OCC | [ethylenebis salts and esters] | [not available] | drums | unknown | N/A |
| SOL | hydrazine | 302-01-2 | drums | unknown | N/A |
| OCC | pentachlorophenol | 87-86-5 | drums | unknown | N/A |
| SOL | methylene chloride | 75-09-2 | drums | unknown | N/A |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |
| | | | | | |

7. FEEDSTOCKS (See Appendix for CAS Numbers)

| CATEGORY | 01 FEEDSTOCK NAME | 02 CAS NUMBER | CATEGORY | 01 FEEDSTOCK NAME | 02 CAS NUMBER |
|----------|-------------------|---------------|----------|-------------------|---------------|
| FDS | | | FDS | | |
| FDS | | | FDS | | |
| FDS | | | FDS | | |
| FDS | | | FDS | | |

VI. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

EPA/RCRA files
April 27, 1990 E & E/FIT VSI

| POTENTIAL HAZARDOUS WASTE SITE PRELIMINARY ASSESSMENT | | I. IDENTIFICATION | |
|---|--|--------------------------|-------------------------------|
| EPA | PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS | 01 STATE KS | 02 SITE NUMBER KSD00020368 |
| II. HAZARDOUS CONDITIONS AND INCIDENTS | | | |
| A. GROUND WATER CONTAMINATION | | | |
| 01 | 02 | POTENTIAL | ALLEGED |
| 03 POPULATION POTENTIALLY AFFECTED: _____ | | 04 NARRATIVE DESCRIPTION | |
| None reported or known to date. | | | |
| B. SURFACE WATER CONTAMINATION | | | |
| 01 | 02 | POTENTIAL | ALLEGED |
| 03 POPULATION POTENTIALLY AFFECTED: _____ | | 04 NARRATIVE DESCRIPTION | |
| None reported or known to date. | | | |
| C. CONTAMINATION OF AIR | | | |
| 01 | 02 | POTENTIAL | ALLEGED |
| 03 POPULATION POTENTIALLY AFFECTED: _____ | | 04 NARRATIVE DESCRIPTION | |
| None reported or known to date. | | | |
| D. FIRE/EXPLOSIVE CONDITIONS | | | |
| 01 | 02 | POTENTIAL | ALLEGED |
| 03 POPULATION POTENTIALLY AFFECTED: _____ | | 04 NARRATIVE DESCRIPTION | |
| None reported or known to date. | | | |
| E. DIRECT CONTACT | | | |
| 01 | 02 | POTENTIAL | ALLEGED |
| 03 POPULATION POTENTIALLY AFFECTED: _____ | | 04 NARRATIVE DESCRIPTION | |
| None reported or known to date. | | | |
| F. CONTAMINATION OF SOIL | | | |
| 01 | 02 | POTENTIAL | ALLEGED |
| 03 AREA POTENTIALLY AFFECTED: _____ | | 04 NARRATIVE DESCRIPTION | |
| (Acres) | | | |
| The State has reported that the soil may be contaminated under the product (sodium hydroxide) storage tank, located east of the production plant. | | | |
| G. DRINKING WATER CONTAMINATION | | | |
| 01 | 02 | POTENTIAL | ALLEGED |
| 03 POPULATION POTENTIALLY AFFECTED: _____ | | 04 NARRATIVE DESCRIPTION | |
| None reported or known to date. | | | |
| H. WORKER EXPOSURE/INJURY | | | |
| 01 | 02 | POTENTIAL | ALLEGED |
| 03 WORKERS POTENTIALLY AFFECTED: _____ | | 04 NARRATIVE DESCRIPTION | |
| None reported or known to date. | | | |
| I. POPULATION EXPOSURE/INJURY | | | |
| 01 | 02 | POTENTIAL | ALLEGED |
| 03 POPULATION POTENTIALLY AFFECTED: _____ | | 04 NARRATIVE DESCRIPTION | |
| None reported or known to date. | | | |

EPA

PRELIMINARY ASSESSMENT

PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

II. HAZARDOUS CONDITIONS AND INCIDENTS (CONTINUED)

| 01 | J. DAMAGE TO FLORA | 02 | OBSERVED (DATE:) | POTENTIAL | ALLEGED |
|----|--------------------|----|-------------------|-----------|---------|
| | | | | | |

04 NARRATIVE DESCRIPTION

None reported or known to date.

| | |
|----|--------------------|
| 01 | K. DAMAGE TO FAUNA |
|----|--------------------|

| 02 | OBSERVED (DATE:) | POTENTIAL | ALLEGED |
|----|-------------------|-----------|---------|
|----|-------------------|-----------|---------|

04 NARRATIVE DESCRIPTION (Include name(s) of species)

None reported or known to date.

01 L. CONTAMINATION OF FOOD CHAIN

| 02 | OBSERVED (DATE:) | POTENTIAL | ALLEGED |
|----|-------------------|-----------|---------|
|----|-------------------|-----------|---------|

04 NARRATIVE DESCRIPTION

None reported or known to date.

| | |
|----|-----------------------------------|
| 01 | M. UNSTABLE CONTAINMENT OF WASTES |
|----|-----------------------------------|

| 02 | OBSERVED (DATE:) | POTENTIAL | ALLEGED |
|----|-------------------|-----------|---------|
|----|-------------------|-----------|---------|

(Spills/runoff/standing liquids/leaking drums)

03 POPULATION POTENTIALLY AFFECTED:

None reported or known to date.

| | |
|----|--------------------------------|
| 01 | N. DAMAGE TO OFF-SITE PROPERTY |
|----|--------------------------------|

| 02 | OBSERVED (DATE:) | POTENTIAL | ALLEGED |
|----|-------------------|-----------|---------|
|----|-------------------|-----------|---------|

04 NARRATIVE DESCRIPTION

None reported or known to date.

01 — O. CONTAMINATION OF SEWERS,
STORM DRAINS, WWTPs

| 02 | OBSERVED (DATE:) | POTENTIAL | ALLEGED |
|----|-------------------|-----------|---------|
|----|-------------------|-----------|---------|

04 NARRATIVE DESCRIPTION

None reported or known to date.

01 P. ILLEGAL/UNAUTHORIZED DUMPING

| 02 | OBSERVED (DATE:) | POTENTIAL | ALLEGED |
|----|-------------------|-----------|---------|
|----|-------------------|-----------|---------|

04 NARRATIVE DESCRIPTION

None reported or known to date.

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

None reported or known to date.

III. TOTAL POPULATION POTENTIALLY AFFECTED:

IV. COMMENTS

PA Form may be updated during Final Report submission to EPA.

V. SOURCES OF INFORMATION (Cite specific references. e.g., state files, sample analysis, reports)

EPA/RCRA files
April 27, 1990, E & E/FIT VSI

APPENDIX C

RAW MATERIAL NUMERICAL INDEX

RAW MATERIAL

4/12/90

NUMERICAL INDEX**Raw Material**Code NumberInventory NameCAS No.

| | | |
|------|--|---|
| 0004 | Acetic Acid | 64-19-7 |
| 0009 | ACRYSOL® QR-1086 | N.A. |
| 0010 | Actrafoam S | N.A. |
| 0011 | Aerosol GPG | 577-11-7 |
| 0013 | Agefloc WT-40 | 26062-79-3 |
| 0014 | Agefloc A-50 | 42751-79-1 |
| 0015 | Agefloc CF-50 | 1327-41-9 |
| 0016 | Alumina-Hydrated | 21645-51-2 |
| 0017 | AMP-95 | 124-68-5 |
| 0018 | Polyacrylic Acid | 9003-01-4 |
| 0019 | ALCOMER 123L | 64742-47-8, 8032-32-4 |
| 0020 | Aluminum Chlorohydrate Sol., 50% | 1327-41-9 |
| 0021 | Aquatreat DNM-30 | 128-04-1 & 142-59-6 |
| 0022 | Aqua Ammonia | 1336-21-6 |
| 0029 | American Cyanamid E-1883 | N.A. |
| 0033 | AF-10-FG | N.A. |
| 0035 | ARCO S-SMA-1000L/PERCHEM 5786/ VERSA-TL 7 | (68037-40-1) 1310-73-2 - Sod. Hydrox. |
| 0039 | Armeen 18D | 124-30-1 |
| 0040 | BTC 1010 | 7173-51-5 |
| 0044 | BARDAC 205M | 68424-95-5 |
| 0045 | Bayhibit AM | 37971-36-1 |

| | | |
|------|-----------------------|--|
| 0046 | BARQUAT 4240Z | 5197-80-8 |
| 0050 | Belclene 200 | 26099-09-2 |
| 0051 | Belclene 500 | 71050-62-9 |
| 0053 | Belcor® 575 | 23783-26-8 |
| 0054 | Biomet TBTO | 56-35-9 |
| 0057 | Bio-Terge PAS-8S | 5324-84-5 |
| 0089 | BTC-2125 | 68391-01-5* & 68956-79-6* |
| 0091 | Butyl Alcohol | 71-36-3 |
| 0092 | Poly-Solv EB | 111-76-2 |
| 0106 | CH-22HM | 8002-05-9, 1309-48-4, 21645-51-2 |
| 0108 | Caustic Soda | 1310-73-2 |
| 0109 | Calcium Nitrate | 10124-37-5 |
| 0111 | Calgon RP-1240-10 | N.A. |
| 0112 | Caustic Soda | 1310-73-2 |
| 0113 | Caustic Potash Liquid | 1310-58-3 |
| 0115 | CDB Clearon | 51580-86-0 |
| 0121 | 12% Manganese CEM-ALL | 15956-58-8, 27253-32-3 |
| 0122 | Chem-Solv DM | 111-77-3 |
| 0123 | Chem-Solv DB | 112-34-5 |
| 0124 | Chesnut Extract | 1401-55-4 |
| 0125 | CMC- 7LBT | 9004-32-4 |
| 0126 | Cobratec 99 | 95-14-7 |
| 0127 | Cobratec TT-50 S | 64665-57-2 |
| 0128 | Chromic Acid | 1333-82-0 |
| 0129 | Citric Acid | 77-92-9 |
| 0130 | Cobalt Sulfate | 10124-43-3 |
| 0136 | Copper Sulfate | 7758-99-8 |

| | | |
|------|---|---|
| 0137 | Copper Sulfate Liquid | 7758-98-7 |
| 0139 | Chlorine | 7782-50-5 |
| 0143 | POLY-TERGENT® CS-1 | N.A. |
| 0145 | Cupric Nitrate, Trihydrate | 10031-43-3 |
| 0148 | Cyclohexylamine | 108-91-8 |
| 0149 | Cyanamer P-35 | 9003-06-9 |
| 0150 | Cyanamer P-35 | 9003-06-9 |
| 0151 | Cyanamer P-38 | 9003-06-9 |
| 0155 | Dequest 2000/PHOS 2 | 6419-19-8 |
| 0156 | Dequest 2010 | 2809-21-4 |
| 0158 | Dequest 2005 | 2235-43-0 |
| 0159 | Diethyl Ethanol Amine | 100-37-8 |
| 0160 | Disodium Phosphate | 7558-79-4 |
| 0161 | Disodium EDTA | 139-33-3 |
| 0163 | Ethylene Glycol, Inhibited | 107-21-1 |
| 0164 | POLY-TERGENT® 2EP | 28519-02-0, 25167-32-2, 7757-82-6 |
| 0166 | DANTOBROM® RW Biocide | 126-06-7, 118-52-5 ACCESS #54445 |
| 0167 | Diethylhydroxylamine (DEHA) (Hydroquinone) | 3710-84-7 123-31-9 |
| 0180 | Hampene 220 | 64-02-8 |
| 0183 | Ethomeen 18/60 | 26635-92-7 |
| 0184 | Ethomeen S/15 | 61791-24-0 |
| 0189 | Exxon Aromatic 200 | 64742-94-5 64742-06-9 91-20-3 |
| 0192 | Ferrous Sulfate/Heptahydrate | 7782-63-0 |
| 0193 | Ferric Chloride Solution | 7705-08-0 |
| 0194 | Ferric Sulfate Solution 50% | 10028-22-5 |

| | | |
|------|--|---|
| | | 7664-93-9 |
| 0204 | GOOD-RITE® K-XP82 | 9003-01-4 |
| 0206 | GUARTEC CIP | 68611-04-1 |
| 0209 | HAMP-ENE® ACID | 60-00-4 |
| 0211 | HAMP-ENE® 100S | 64-02-8 |
| 0212 | Hampene 100/Vin Keel 100 | 64-02-8 |
| 0214 | Hexametaphosphate (OLIN POLYPHOS® 62533-93-1) | 68915-31-1 |
| 0226 | Hybase M-12 | 68476-30-2 61789-87-5 546-93-0 |
| 0236 | Hydrochloric Acid, Inhibited | 7647-01-0 |
| 0237 | Hydrogen Peroxide, 50% | 7722-84-1 |
| 0239 | Hydrazine 35% | 302-01-2 |
| 0240 | Hydroxyacetic Acid | 79-14-1 |
| 0261 | Kathon 886F | 26172-55-4 2682-20-4 |
| 0273 | Magnifloc 905N | N.A. |
| 0275 | Magnifloc 1820A | N.A. |
| 0276 | Magnifloc 587C/Agefloc WT-20 N.A. 2606-79-3 | |
| 0277 | Magnifloc 581C/ CPS Agefloc A-50 HV | N.A. 42751-79-1 |
| 0283 | Magnifloc 515-C | N.A. |
| 0284 | Magnifloc 1849-A | N.A. |
| 0285 | Magnifloc 1906N | N.A. |
| 0286 | Magnifloc 1596C | 64742-47-8, 7783-20-2 |
| 0291 | Maracell XE | 68131-31-7 |
| 0293 | Marasperse N-22 | 8061-51-6 |
| 0294 | Mazu DF 210S | 7732-18-5, 9003-04-7 9005-67-8, 9004-65-3 57-11-4, 1338-41-6 63148-62-9, 7631-86-9 50-00-0, 99-76-3 94-13-3, 57-55-6 |

| | | |
|------|------------------------------|--|
| 0295 | MECT 5 | 21564-17-0, 6317-18-6 |
| 0296 | MECT 10 | 21564-17-0, 6317-18-6 |
| - | Methyl Violet Indicator | N.A. |
| 0304 | Monosodium Phosphate | 7558-80-7 |
| 0305 | Monofax 1214 | N.A. |
| 0308 | Morpholine | 110-91-8 |
| 0312 | Muriatic Acid | 7647-01-0 |
| 0317 | Narlex D-72 | 68037-40-1 |
| 0318 | National Starch FLOC-AID 19 | N.A. |
| 0330 | O B Hibit | 1303-96-4, 532-32-1 7758-87-4, 7758-29-4 9003-11-6 |
| 0336 | Sodium Chlorate (OPM-2) | 7775-09-9 |
| 0340 | PERCHEM™ 550 | 26062-79-3 |
| 0341 | CALLAWAY 3379 | N.A. |
| 0342 | Percol 710 | 64742-52-5 8032-32-4 |
| 0343 | Percol 780 | (8012-95-1 mineral oil) |
| 0346 | Percol LT 26 | N.A. |
| 0347 | Percol 757 | N.A. |
| 0348 | Percol 778 | N.A. |
| 0349 | Percol LT 27 | N.A. |
| 0350 | Petro AG Special | 26264-58-4 27178-87-6 |
| 0353 | Magnifloc 1594C | 8002-05-9 |
| 0360 | Phosphoric Acid | 7664-38-2 |
| 0361 | Phosphonic Acid, Green (70%) | 7664-38-2 |
| 0364 | Pluronic F-68 | 9003-11-6 |
| 0365 | Olin Poly G WS-5100 | 9038-95-8 |
| 0368 | Polyphosphoric Acid | 8017-16-1 |
| 0370 | Potassium Carbonate | 584-08-7 |

| | | |
|----------------|-------------------------------|--|
| 0371 | Potassium Hydroxide, Crystals | 1310-58-3 |
| 0372 | Potassium Tetra Borate | 1332-77-0 |
| 0378 | Praestol K 225 FL | N.A. |
| 0379 | Praestol K 280 FL | 64742-47-8 9016-45-9 |
| 0380 | Praestol K133L | 64742-47-8 67-63-0 |
| 0381 | Praestol A 310 FL | N.A. |
| 0387 | PRO FLOC P (Chitosan) | 9012-76-4 |
| 0388 | Propylene Glycol, Inhibited | 57-55-6 |
| 0390 | Quebracho | 1401-55-4 |
| 0397 | Percol LT22S | N.A. |
| 0410 | SECOFLOC 800 | 7647-01-0, 7732-18-5 141-43-5, 50-00-0 |
| 0420 | Sodium Chloride | 7647-14-5 |
| 0428 | Santosite | 7757-83-7 |
| 0430-0431-0432 | Scav-Ox | 302-01-2 |
| 0433-0439 | Scav-Ox II (Organic Catalyst) | 302-01-2 |
| 0435-0436-0437 | Scav-Ox Plus | 302-01-2 |
| 0440 | Sodium Sulfate | 7757-82-6 |
| 0441 | Silicate of Soda | 1344-09-8 |
| 0443 | Sodium Carbonate, anhydrous | 497-19-8 |
| 0444 | Soda Ash | 497-19-8 |
| 0452 | Sodium Bichromate | 10588-01-9 |
| 0455 | Sodium Chlorite Solution 31% | 7647-15-6 |
| 0456 | Sodium Bisulfate | 7681-38-1 |

| | | |
|------|--|------------|
| 0457 | Sodium Chlorate (99.5%) | 7775-09-9 |
| 0458 | Sodium Borate - 5H ₂ O | 1330-43-4 |
| 0459 | Sodium Chlorite | 7758-19-2 |
| 0460 | Sodium Chlorite (Technical) 50% | 7758-19-2 |
| 0461 | Sodium Chromate | 7775-11-3 |
| 0462 | Sodium Carbonate Solution | N.A. |
| 0463 | Sodium Citrate, dihydrate | 68-04-2 |
| 0464 | Sodium Hydrosulfite | 7775-14-6 |
| 0465 | Sodium Hypochlorite | 7681-52-9 |
| 0466 | Sodium Bisulfite, Anhydrous | 7681-57-4 |
| 0468 | Sodium Meta Silicate | 6834-92-0 |
| 0469 | Sodium Molybdate | 7631-95-0 |
| 0471 | Sodium Sulfide, Flake | 1313-82-2 |
| 0480 | Sodium Nitrite | 7632-00-0 |
| 0481 | Wayzole TT-85S/Cobratec TT85 | 64665-57-2 |
| 0482 | Sodium Polymethacrylate | N.A. |
| 0483 | GOOD-RITE K-XP82D | 9003-04-7 |
| 0484 | Sodium Sesquicarbonate, dihydrate | 533-96-0 |
| 0485 | Sodium Polyphosphates, Glassy | 68915-31-1 |
| 0488 | Sulfamic Acid | 5329-14-6 |
| 0489 | Starch | 9005-25-8 |
| 0491 | Sulfuric Acid 66° Be | 7664-93-9 |
| 0493 | Sybron Bi-Chem LC 1002 CG - 1738 Blend | N.A. |
| 0494 | Sybron Bi-Chem DC 1002 CG - 1738 Blend | N.A. |
| 0495 | Sybron Bi-Chem LC 1002 CG | N.A. |
| 0496 | Sybron Bi-Chem DC 1002 CG | N.A. |
| 0497 | Sybron Bi-Chem LC 1008 SF | N.A. |

| | | |
|------|--|------------|
| 0498 | Sybron Bi-Chem DC 1008 SF | N.A. |
| 0499 | Sybron Bi-Chem LC 1738 CW | N.A. |
| 0500 | Sybron Bi-Chem DC 1738 CW | N.A. |
| 0501 | Sybron Bi-Chem LC 1008 SF - 1738 Blend | N.A. |
| 0502 | Sybron Bi-Chem DC 1008 SF - 1738 Blend | N.A. |
| 0505 | T DET N-11 | 9016-45-9 |
| 0518 | Poly-Tergent B-350 | 26027-38-3 |
| 0520 | Poly-Tergent SL-62 | N.A. |
| 0521 | Poly-Tergent S-305-LF | N.A. |
| 0525 | TPPP Solution | 7320-34-5 |
| 0526 | Tetrapotassium Pyrophosphate, Powder | 7320-34-5 |
| 0527 | Tetrasodium pyrophosphate (TSPP) | 7722-88-5 |
| 0528 | Tolutriazole | 29385-43-1 |
| 0532 | Triethanolamine 99% | 102-71-6 |
| 0533 | Triethanolamine 69.3% | 102-71-6 |
| 0534 | Tripolyphosphate | 7758-29-4 |
| 0538 | Tri Sodium Phosphate | 7601-54-9 |
| 0540 | Triton X-114 | 9036-19-5 |
| 0541 | Triton X-100/Harcros-DET 0-9 | 9036-19-5 |
| 0542 | Triton CF-54 | 69279-01-2 |

| | | |
|-----------|--|--|
| 0584 | Methylene Bis Thiocyanate | 6317-18-6 64742-95-6 |
| 0590 | WSCP | 31512-74-0 |
| 0596 | XD-7287 L | 10222-01-2 112-60-7 25322-68-3 7732-18-5 7647-15-6 |
| 0597 | Witconate P-10-59 | 26264-05-1 |
| 0602 | Zinc Chloride Solution | 7646-85-7 |
| 0609 | Zinc Nitrate 50% | 7779-88-6 |
| 0610 | Zinc Oxide | 1314-13-2 |
| 0620 | Zinc Sulfate | 7733-02-0 |
| OLIN 1803 | Sodium Sulfite, Synthetic Anhydrous Catalyzed & Decharacterized | 7757-83-7 68131-31-7 10124-43-3 |
| OLIN 1804 | Sodium Sulfite, Catalyzed | 7757-83-7 10124-43-3 |

APPENDIX D

HAZARDOUS WASTE CONTAINER STORAGE AREA INVENTORY LIST

[illegible]

PRODUCT:

OLIN 3102

STP TOXIC

DATE

IN

LOG

2-25-85

WDRS

105

NET

POUNDS

150

BALANCE

150

DRUMS

ENTRY

1

BAL.

1

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47

PRODUCT:

DLIN 6901

EPTONIC

DATE
IN
LOG

2-18-85

WDRS

104

NET
POUNDS

940

BALANCE

940

ENTRY

4

DRUMS

BAL.

4

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47

DATE
IN
LOG

WDRS

NET
POUNDS

BALANCE

ENTRY

DRUMS

13 AC

[illegible]

PRODUCT:

BAD MONOMER

CORA - UP TOXIC

DATE

IN

WDRS

NET

POUNDS

BALANCE

DRUMS

ENTRY

BAL.

LOG

2-5-85

099

291

291

1

1

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47

PRODUCT:

EXPER. 0846-38

CORR + EP TOXIC (chrome)

DATE

IN

LOG

3-21-84

WDRS

070A

NET
POUNDS

3500

BALANCE

3500

DRUMS

ENTRY

5

BAL.

5

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47

| PRODUCT: | 1 | 2 | 3 | 4 | 5 | 6 | |
|-----------|--------|-----|------|------------|---------|-------|----|
| | DATE | IN | WDRS | NET POUNDS | BALANCE | DRUMS | |
| | LOG | | | | | ENTRY | |
| OLIN 2059 | 7-6-83 | 037 | | 400 | 400 | 1 | 1 |
| EP TOXIC | | | | | | | |
| | | | | | | | 2 |
| | | | | | | | 3 |
| | | | | | | | 4 |
| | | | | | | | 5 |
| | | | | | | | 6 |
| | | | | | | | 7 |
| | | | | | | | 8 |
| | | | | | | | 9 |
| | | | | | | | 10 |
| | | | | | | | 11 |
| | | | | | | | 12 |
| | | | | | | | 13 |
| | | | | | | | 14 |
| | | | | | | | 15 |
| | | | | | | | 16 |
| | | | | | | | 17 |
| | | | | | | | 18 |
| | | | | | | | 19 |
| | | | | | | | 20 |
| | | | | | | | 21 |
| | | | | | | | 22 |
| | | | | | | | 23 |
| | | | | | | | 24 |
| | | | | | | | 25 |
| | | | | | | | 26 |
| | | | | | | | 27 |
| | | | | | | | 28 |
| | | | | | | | 29 |
| | | | | | | | 30 |
| | | | | | | | 31 |
| | | | | | | | 32 |
| | | | | | | | 33 |
| | | | | | | | 34 |
| | | | | | | | 35 |
| | | | | | | | 36 |
| | | | | | | | 37 |
| | | | | | | | 38 |
| | | | | | | | 39 |
| | | | | | | | 40 |
| | | | | | | | 41 |
| | | | | | | | 42 |
| | | | | | | | 43 |
| | | | | | | | 44 |
| | | | | | | | 45 |
| | | | | | | | 46 |
| | | | | | | | 47 |

[illegible]

PRODUCT:

Mixed Lab Solvents

FOOI

DATE

IN

WDRS

NET

POUNDS

BALANCE

DRUMS

ENTRY

BAL.

10-16-87

157

1176

1176

3

3

10-20-87

157

<1176>

0

<3>


0

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47

| |
|----|
| 1 |
| 2 |
| 3 |
| 4 |
| 5 |
| 6 |
| 7 |
| 8 |
| 9 |
| 10 |
| 11 |
| 12 |
| 13 |
| 14 |
| 15 |
| 16 |
| 17 |
| 18 |
| 19 |
| 20 |
| 21 |
| 22 |
| 23 |
| 24 |
| 25 |
| 26 |
| 27 |
| 28 |
| 29 |
| 30 |
| 31 |
| 32 |
| 33 |
| 34 |
| 35 |
| 36 |
| 37 |
| 38 |
| 39 |
| 40 |
| 41 |
| 42 |
| 43 |
| 44 |
| 45 |
| 46 |
| 47 |

Q3

| PRODUCT: | 1 | 2 | 3 | 4 | 5 | 6 | |
|-------------|----------|------|--------|---------|-------|------|----|
| | DATE | | NET | | | | |
| | IN | WDRS | POUNDS | BALANCE | DRUMS | | |
| FLAM. SOLID | LOG | | | | ENTRY | BAL. | |
| | 10-22-81 | 002 | 4055 | 4055 | 9 | 9 | 1 |
| | 12-30-83 | 002 | <995> | 3060 | <2> | 7 | 2 |
| | | | | | | | 3 |
| | | | | | | | 4 |
| | | | | | | | 5 |
| | | | | | | | 6 |
| | | | | | | | 7 |
| | | | | | | | 8 |
| | | | | | | | 9 |
| | | | | | | | 10 |
| | | | | | | | 11 |
| | | | | | | | 12 |
| | | | | | | | 13 |
| | | | | | | | 14 |
| | | | | | | | 15 |
| | | | | | | | 16 |
| | | | | | | | 17 |
| | | | | | | | 18 |
| | | | | | | | 19 |
| | | | | | | | 20 |
| | | | | | | | 21 |
| | | | | | | | 22 |
| | | | | | | | 23 |
| | | | | | | | 24 |
| | | | | | | | 25 |
| | | | | | | | 26 |
| | | | | | | | 27 |
| | | | | | | | 28 |
| | | | | | | | 29 |
| | | | | | | | 30 |
| | | | | | | | 31 |
| | | | | | | | 32 |
| | | | | | | | 33 |
| | | | | | | | 34 |
| | | | | | | | 35 |
| | | | | | | | 36 |
| | | | | | | | 37 |
| | | | | | | | 38 |
| | | | | | | | 39 |
| | | | | | | | 40 |
| | | | | | | | 41 |
| | | | | | | | 42 |
| | | | | | | | 43 |
| | | | | | | | 44 |
| | | | | | | | 45 |
| | | | | | | | 46 |
| | | | | | | | 47 |



PRODUCT:

DLIN 3301

COMBUST. LIQ.

DATE

IN

LOG

WDRS

NET

POUNDS

BALANCE

DRUMS

ENTRY

BAL.

7-6-83

052

487

487

1

1

9-20-84

052

475

962

1

2

3-14-85

052

450

1412

1

3

[illegible]

PRODUCT:

OLIN 2802

IGN-OK.

DATE

IN

LOG

6-28-92

BYDRA

057

NET

POUNDS

456

BALANCE

456

DRUMS

ENTRY

1

BAL.

1

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47

PRODUCT:
OLIN 6988
IGN.

DATE
IN
LOG

WDRS

NET
POUNDS

BALANCE

ENTRY

DRUMS
BAL.

2-19-85

103

5850

5850

13

13

2-19-87

/

<900>

4950

<2>

11

10-19-87

/

<450>

4500

<1>

10

11-2-87

/

<1350>

3150

<3>

7

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47

[illegible]

PRODUCT:

OLIN 6980

IGN.

DATE

IN

LOG

1-8-86

WDRS

123

NET

POUNDS

5295

BALANCE

5295

DRUMS

ENTRY

11

BAL.

11

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47

PRODUCT:
INTERMEDIATE "CC"
Ignit 66 - D001

DATE

IN

LOG

6-22-88

WARS

181

NET

POUNDS

332

BALANCE

332

DRYMS

ENTRY

1

RAL

1

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47

PRODUCT:

041N 6994

Ign. - D001

DATE

IN

LOG

11-14-88

WDRS

208

NET

POUNDS

3290

BALANCE

3290

DRUMS

ENTRY

8

BAL

8

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47

PRODUCT:

04IN 5025
Ign-D001

DATE

IN

LOG

4-7-89

WDRS

215

NET

POUNDS

1860

BALANCE

1860

DRUMS

ENTRY

4

BAL

4

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47

PRODUCT:

OLIN 2608

Corr. D002

DATE

IN

LOG

WDAS

NET

POUNDS

BALANCE

DRUMS

ENTRY

RML

4-7-89

214

1770

1770

6

0

10-4-89

214

<1770>

0

<6>

0

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47

PRODUCT:
LAB SUPPLY WASTE - BASE
CORROSIVE - D002

DATE
IN
LOG
6-8-88

WDRS
177

NET
POUNDS
340

BALANCE
340

REMS
ENTRY
DAL
1
1

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47

PRODUCT:

REAGENT WASTE

CORR.

DATE

IN

WDRS

NET

POUNDS

BALANCE

DRUMS

ENTRY

BAL.

LOG

7-5-82

056

371

371

1

1

6-8-87

056

(371)

0

(1)

0

Pulled from waste storage
area 6/8/87 to include
in reagent waste program.

W. J. Kane

PRODUCT:

BUCKMAN SDMBT

CORR.

DATE

12

LOG

6-30-86

WDRS

134

NET

POUNDS

2436

BRADY

2436

DEAMS

ENTRY

5

BAL.

TEST

Nov. 4, 1987 - Added 2 lbs. Sulfuric Acid
to each drum to drop
pH to 12.5 - No longer
hazardous waste.

W. E. Davis

PRODUCT:

Q-1N 6900

4070

DATE

IN

LOG

11-14-88

WDRS

209

NET

POUNDS

1055

BALANCE

1055

ORAMS

ENTRY

3

BAL

3

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

21

22

23

24

25

26

27

28

29

30

31

32

33

34

35

36

37

38

39

40

41

42

43

44

45

46

47

PRODUCT:

Orthodichlorobenzene

Toxic 4070

DATE

IN

LOG

WDRS

NET

POUNDS

BALANCE

DRUMS

ENTRY

BAL

6-22-88

5-26-89

179

✓

1841

(1841)

1841

0

4

(4)

4

0

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47

PRODUCT:

VSR DRAIN WASTE

GP TOXIC CHANGE

DATE

IN

LOG

WDRS

NET

POUNDS

BALANCE

DRUMS

ENTRY

BAL.

1-17-85

092

370

370

1

1

1-17-85

093

341

711

1

2

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47

APPENDIX E

WASTE WATER DISCHARGE PERMIT



WASTEWATER DISCHARGE PERMIT

CITY OF KANSAS CITY, KANSAS
WATER POLLUTION CONTROL DEPARTMENT



Permit # 1880

Issue Date November 14, 1989

Permit Type Permanent

Expiration Date November 14, 1994

Classification II

Amount \$40.00

The below named holder of this permit may discharge wastewater into the Municipal sewer system in accordance with wastewater characteristics as listed and City Ordinance #51421.


Olin Water Services
(Firm)
3155 Fiberglas Road
(Street Address)
Kansas City, Kansas 66115
(City, State and Zip Code)

Special Conditions: (1) Report all accidental spills by phone and in writing to the Water Pollution Control

Department at (913) 371-4240. (2) See Pages 2-7.

Important: This permit has been issued based on the information provided on your permit application and/or surveillance by the Water Pollution Control Department. A new discharge permit shall be required when the wastewater characteristics indicated on this permit are exceeded.

APPROVED:


DIRECTOR

Gmj 11.14.89

**KANSAS CITY, KANSAS WATER POLLUTION CONTROL DEPARTMENT
WASTEWATER DISCHARGE PERMIT**

PAGE 2

Company Name: Olin Water Services Permit Number: I880

I. WASTEWATER DISCHARGE AND MONITORING REQUIREMENTS

A. The permittee is authorized to discharge wastewater which does not exceed the following limitations:

| Parameter | Maximum Daily Concentration Limit (mg/L) | Average Monthly Concentration Limit (mg/L) | Type of* Monitoring | Sample Type Required** | Frequency |
|--------------|--|--|---------------------|------------------------|---------------|
| CN Cyanide | 2.0 | | E, SV, SF | G | *4 Days/6 Mo. |
| Cd Cadmium | 1.5 | | E, SV, SF | 24 Hr. (F) | 3 Days/6 Mo. |
| Cr Chromium | 4.0 | | E, SV, SF | 24 Hr. (F) | 3 Days/6 Mo. |
| Cu Copper | 3.0 | | E, SV, SF | 24 Hr. (F) | 3 Days/6 Mo. |
| Pb Lead | 2.0 | | E, SV, SF | 24 Hr. (F) | 3 Days/6 Mo. |
| Zn Zinc | 5.0 | | E, SV, SF | 24 Hr. (F) | 3 Days/6 Mo. |
| Ni Nickel | 5.0 | | E, SV, SF | 24 Hr. (F) | 3 Days/6 Mo. |
| Hg Mercury | 0.3 | | E, SV, SF | 24 Hr. (F) | 3 Days/6 Mo. |
| As Arsenic | 1.0 | | E, SV, SF | 24 Hr. (F) | 3 Days/6 Mo. |
| Ag Silver | | | E, SV, SF | 24 Hr. (F) | 3 Days/6 Mo. |
| Sulfides | 1.0 | | E, SV, SF | G | 3 Days/6 Mo. |
| Surfactants | 100 | | E, SV, SF | G | 3 Days/6 Mo. |
| Oil & Grease | 100 | | E, SV, SF | G | *4 Days/6 Mo. |
| TTO | | | E, SV, SF | G | 3 Days/6 Mo. |
| Total Metals | | | E, SV, SF | | 3 Days/6 Mo. |
| pH | X 5.5-9.5 | | E, SV, SF | G | *4 Days/6 Mo. |

NOTES:

1. All metals and cyanide parameters are to be reported as Total (T).
2. Limits were not adjusted using the combined wastestream formula, as per (Part 403.6(E)). (Refer to Attachment A, if necessary.)
3. If there were two limitations for the same parameters, the most stringent limitation was used.
4. "(X)" in Table A will denote the parameters to be analyzed by your industry.
5. Total Suspended Solids (TSS), Biochemical Oxygen Demand (BOD), and Chemical Oxygen Demand (COD) will be required for Industrial Self-Monitoring and City Surveillance Monitoring, in addition to those parameters listed in Table A above.

*E - Enforcement Monitoring

SV - City Surveillance Monitoring

SF - Industrial Self-Monitoring

** (G) = Grab; (T) = Time Composite; (F) = Flow Composite 24 Hours

KANSAS CITY, KANSAS WATER POLLUTION CONTROL DEPARTMENT
WASTEWATER DISCHARGE PERMIT

PAGE 3

Company Name: Olin Water Services Permit Number: I880

B. The permittee shall not discharge any wastewater:

1. Having a pH lower than 5.5 or higher than 9.5.
2. Containing any other prohibited substance or material in accordance with the Code of City Ordinances, Chapter 30, Articles I-VII.

C. Sampling Location (Describe)

Sample point is located on the far west of the plant drain on the south end
of the building.

D. Testing Procedures

Analyses of pollutants shall be performed by a laboratory certified by the Kansas Department of Health & Environment in accordance with techniques prescribed in 40 CFR, Part 136, as amended. Samples shall be taken in compliance with the monitoring requirements specified and shall be taken at the above-mentioned location (Part C) and at a time in which the sample will be representative of the permittee's wastewater discharge as it enters the City sewer system during normal working hours.

Schedule of Semi-Annual Reporting Periods

| <u>Sampling Period</u> | <u>Report Due</u> |
|---|--------------------|
| <u>3 Consecutive Process Days Between April 15 - May 30</u> | <u>June 30</u> |
| <u>3 Consecutive Process Days Between Oct. 15 - Nov. 30</u> | <u>December 31</u> |

These reports shall be submitted to the Department at the following address:

Water Pollution Control Department
Municipal Office Building
701 N. 7th Street, Room 421
Kansas City, Kansas 66101

Additional Sampling

If the permittee monitors any pollutant at the location designated herein more frequently than required by this permit using approved analytical methods as specified in Part D, the results of such monitoring results shall be provided to the Department.

PAGE 4

| EVENT | DATE |
|---|--------------------------|
| a. Submit Baseline Report (BR) | _____ |
| b. Submit Initial Quarterly or Semi-Annual Monitoring Report | <u>June/December</u> |
| c. Achieve Compliance With Prohibited (Local) Discharge Limits | _____ |
| d. Achieve Compliance With Categorical (Federal) Discharge Limits | _____ |
| e. Accidental Spill Prevention Plan | <u>On File: 10-26-89</u> |
| f. Compliance Progress Report | _____ |
| g. 90 Day Compliance Report | _____ |
| h. Retain All Records | <u>3 Years</u> |
| <p>i. Nothing in this permit shall be construed to modify in any way the requirements of the Federal Clean Water Act, 33 U.S.C. Section 1251 <u>et seq.</u>, pertaining to the pretreatment of discharges into publicly owned treatment works, including the General Pretreatment Regulations, 40 CFR Part 403, and any applicable Categorical Pretreatment Standards, 40 CFR Chapter 1, Subchapter N, nor shall this permit be construed to affect in any way the liability of the permittee for any failure to comply with such requirements.</p> | |

**KANSAS CITY, KANSAS WATER POLLUTION CONTROL DEPARTMENT
WASTEWATER DISCHARGE PERMIT**

PAGE 5

Company Name: Olin Water Services Permit Number: I880

2. **SLUG LOADS OR ACCIDENTAL DISCHARGES:** The Director or his representative shall be notified immediately of any known slug load or accidental discharge into the municipal sewer system by phone (371-4240) and within ten (10) days in writing. This notification shall be a detailed statement describing the causes of the accidental discharge and the measures being taken to prevent future occurrence. Notification will not relieve users of liability for any expense, loss, or damage to the sewer system, treatment plant, or treatment process, or for any fines imposed on account thereof by any public, State, or Federal agency.
3. **PROPER DISPOSAL OF PRETREATMENT SLUDGES AND SPENT CHEMICALS:** The disposal of sludges and spent chemicals generated shall be done in accordance with Section 405 of the Clean Water Act and Subtitles C and D of the Resource Conservation and Recovery Act, as specified in the solvent management plant.
4. **PERMIT MODIFICATIONS:** During the term of the permit, the conditions may need to be revised to meet federal requirements. In addition, permit conditions may change if the discharge from any permittee causes excessive operation and/or maintenance problems in the wastewater collection system and/or wastewater treatment plant.

This permit shall be modified within nine (9) months of the promulgation of a National Categorical Pretreatment Standard. Compliance with the standard shall be within the timeframe specified in the applicable standard.

5. **PERMIT TRANSFERS:** This permit is issued to a specific user for a specific operation. It shall not be reassigned or transferred or sold to a new owner, new user, different premises, or to a new or changed operation without Department approval. Sale of a user's facilities shall obligate the purchaser to seek prior written approval from the Director to enable the discharge to continue.
6. **REVOCATION OF PERMIT:** The permit issued to the Industrial User by the City may be revoked when, after inspection, monitoring, or analysis, it is determined the discharge of wastewater to the sanitary sewer is in violation of Federal, State, or local laws, ordinances, or regulations. Additionally, falsification or intentional misrepresentation of data or statements pertaining to the permit application or any other required reporting forms may be cause for permit revocation. Upon revocation of this permit, all wastewater discharges to the sewer system shall be immediately ceased.

**KANSAS CITY, KANSAS WATER POLLUTION CONTROL DEPARTMENT
WASTEWATER DISCHARGE PERMIT**

PAGE 6

Company Name: Olin Water Services Permit Number: 1880

7. **REPORTING CHANGE IN DISCHARGE:** Any change of more than 10 percent in discharge strength or volume, modification of waste collection or a pretreatment system, elimination of a discharge, changes in operational procedures, or other factors which would significantly alter the nature and frequency of discharge, shall be reported to the Director in writing.
8. **CONTROL STRUCTURE (MANHOLE):** When required by the Director, the Owner of any property serviced by a building sewer carrying industrial wastes shall install a suitable control manhole, together with such necessary meters and other appurtenances in the building sewer, to facilitate observation, sampling, and measurement of the wastes. Such a manhole, when required, shall be accessible 24 hours per day, safely located, installed by the Owner at his expense, and maintained by him so as to be safe and accessible at all times.
9. **PREVENTION PLAN:** The Industrial User shall develop an accidental spill prevention plan to eliminate or minimize the accidental or slug discharge of pollutants into the sewer system which could have an adverse effect on the City's pretreatment plant, sludge, or collection system.
10. **RIGHT OF ENTRY:** The Industrial User shall, after reasonable notification by the City, allow the City or its representative exhibiting proper credentials and identification to enter upon the premises of the User at all reasonable hours for the purpose of inspection, sampling, or records inspection. Reasonable hours in the context of inspection and sampling includes any time the Industrial User is operating any process which results in a process wastewater discharge to the City's sewer system.
11. **DILUTION:** No Industrial User shall increase the use of portable or process water or in any way attempt to dilute a discharge as a partial or complete substitute for adequate pretreatment to achieve compliance with the limitations contained in this permit. Dilution is not treatment.
12. **SIGNATORY REQUIREMENTS:** All reports required by this permit shall be signed by a principal executive officer of the User or his designee.
13. **FALSIFYING INFORMATION OR TAMPERING WITH MONITORING REQUIREMENTS:** Knowingly making any false statement on any report or other document required by this permit or knowingly rendering any monitoring device or method inaccurate may

KANSAS CITY, KANSAS WATER POLLUTION CONTROL DEPARTMENT
WASTEWATER DISCHARGE PERMIT

PAGE 7

Company Name: Olin Water Services Permit Number: I880

result in punishment under the criminal laws of the City, as well as being subjected to civil penalties and relief.

14. **BYPASSING:** Any diversion from or bypass of facilities necessary to maintain compliance with this permit is prohibited.
15. **REMOVAL FROM SERVICE:** The permittee shall inform the Department before an industrial waste treatment facility is removed from service.
16. **POLLUTANTS:** In the event the Environmental Protection Agency amends or promulgates new effluent or applicable toxic pollutant limitations for any of the pollutants which are more stringent than limitations specified in this permit, the permit will be modified and reissued to incorporate the new limitation(s).
17. **ENFORCEMENT:** Nothing in this permit shall be construed to relieve the permittee from civil or criminal penalties for violations and/or non-compliance as specified in this permit or City ordinances, whether or not such violations and/or non-compliance are due to factors beyond the permittee's control.
18. **SEVERABILITY:** The provisions of this permit are severable, and if any provision of this permit or the application of any provision of this permit to any circumstance is held invalid, the application of such provision to other circumstances and the remainder of this permit shall not be affected thereby.

APPROXIMATE SCALE
1" = 50'

8" C.W.M.

8" C.W.M.

12" C.W.M.

8"

D.H.

N

REICHOLD CHEMICAL
FILE NO. 848450

8" C.W.M.

3155'

A

Office & Labs.

Office & Labs.

Labs.

Lab.

(1940)
200'x150'x160'
x 58'x110'

(16)

Mixing
&
Furnaces

10,000 Gal.
Caustic Tk.

Mixing
Rm.

100'
(Service)

Mixing
Rm.

GATE

2-600 Gal.
365 Mixing Tk.

68.3'

8" W.C.B.

3-15 KVA
1-25 KVA
on Poles

Expanded Metal
Flam. Lig.
Stgo

6" Wire

HAZARDOUS WASTE DRUM
STORAGE AREA (PROPOSED DIMENSIONS)

68'

FIBERGLASS RD

REICHOLD CHEMICAL

D.H.

GARDNER ASPHALT CORP.

APPENDIX F

WASTE WATER DISCHARGE SAMPLING RESULTS



Olin Plant
Kansas City, KS

PRODUCT - SPECIAL ANALYSIS
DATA ONLY

Laboratory No.: 90Q0003
Date Collected: 01/05/90
Date Received: 01/09/90
Date Analyzed: 01/12/90
Analyst: DH/js

6/8

1 - 90Q0003 Plant Drain

| CONSTITUENT | expressed as mg/L | 1 |
|------------------------|----------------------|------|
| pH (neat) | units | 7.95 |
| Chemical Oxygen Demand | COD | 30 |
| Zinc | Zn | 0.64 |
| Copper | Cu | <0.1 |
| Chromium | Cr | <0.1 |
| Nickel | Ni | <0.1 |
| Lead | Pb | <0.1 |

B.Dame B. Whiles

LF



Olin Plant
Kansas City, KS

PRODUCT - SPECIAL ANALYSIS
DATA ONLY

Laboratory No.: 90Q0006
Date Collected: 01/10/90
Date Received: 01/12/90
Date Analyzed: 01/12/90
Analyst: DH/jr
WS

1 - 90Q0006 Plant Drain Collected 2:45 p.m.

| CONSTITUENT | expressed as mg/L | 1 |
|------------------------|----------------------|------|
| pH (neat) | units | 7.6 |
| Chemical Oxygen Demand | COD | 145 |
| Zinc | Zn | 0.11 |
| Copper | Cu | <0.1 |
| Chromium | Cr | <0.1 |
| Nickel | Ni | <0.1 |
| Lead | Pb | <0.1 |

B.Dame B. Whites

LF



Olin Plant
Kansas City, KS

PRODUCT - SPECIAL ANALYSIS
DATA ONLY

Laboratory No.: 90Q0005
Date Collected: 01/11/90
Date Received: 01/12/90
Date Analyzed: 01/12/90
Analyst: DH/ja
LS

1 - 90Q0005 Plant Drain Collected 3:00 p.m.

| CONSTITUENT | expressed as mg/L | 1 |
|------------------------|----------------------|------|
| pH (neat) | units | 7.7 |
| Chemical Oxygen Demand | COD | 80 |
| Zinc | Zn | 0.10 |
| Copper | Cu | <0.1 |
| Chromium | Cr | <0.1 |
| Nickel | Ni | <0.1 |
| Lead | Pb | <0.1 |

B.Dame B. Whiles LF



Olin Plant
Kansas City, KS

PRODUCT - SPECIAL ANALYSIS
DATA ONLY

Laboratory No.: 90Q0007
Date Collected: 01/12/90
Date Received: 01/16/90
Date Analyzed: 01/16/90
Analyst: DH/js

Handwritten signature/initials

1 - 90Q0007 Plant Drain Collected 3:00 p.m.

| CONSTITUENT | expressed as mg/L | 1 |
|------------------------|----------------------|------|
| pH (neat) | units | 8.5 |
| Chemical Oxygen Demand | COD | 150 |
| Zinc | Zn | 1.62 |
| Copper | Cu | <0.1 |
| Chromium | Cr | <0.1 |
| Nickel | Ni | <0.1 |
| Lead | Pb | <0.1 |

B.Dame B. Whiles

LF

APPENDIX G


ASHLAND PRE-ACQUISITION PRELIMINARY
ENVIRONMENTAL ASSESSMENT REPORT

CIVIL & ENVIRONMENTAL CONSULTANTS, INC.
DRAFT REPORT OF FINDINGS
PRELIMINARY ENVIRONMENTAL ASSESSMENT
OLIN WATER SERVICES
KANSAS CITY, KANSAS
AS EDITED BY
GROUNDWATER TECHNOLOGY, INC.

PREPARED FOR:

WILLIAM C. OLASIN
ENVIRONMENTAL ENGINEER
ASHLAND CHEMICAL, INC.
P.O. BOX 2219
COLUMBUS, OHIO 43216

PREPARED BY:


MARK P. DAVIS
GEOLOGIST

REVIEWED BY:


RONALD M. KLEMOVICH, P.E.
PROJECT MANAGER

FOR:

MICHAEL R. BRENOEL
VICE PRESIDENT
REGIONAL MANAGER

JUNE 24, 1991
042601057

RECEIVED

SEP 27 1991

PRMT. SECTION

c:\klem\ashland\1



GROUNDWATER
TECHNOLOGY

TABLE OF CONTENTS

| | | |
|-------|--|----|
| 1.0 | INTRODUCTION | 1 |
| 2.0 | FACILITY DESCRIPTION | 2 |
| 3.0 | PHYSICAL SETTING | 4 |
| 4.0 | CEC SCOPE OF WORK | 5 |
| 5.0 | METHODOLOGY | 6 |
| 5.1 | CEC SOIL BORINGS | 6 |
| 5.2 | CEC MONITORING WELLS | 6 |
| 6.0 | INVESTIGATION FINDINGS | 8 |
| 6.1 | TITLE SEARCH | 8 |
| 6.2 | GROUNDWATER | 8 |
| 6.3 | SOILS | 10 |
| 6.3.1 | <u>Borings SB-1 through SB-4 and SB-10 through SB-12</u> | 10 |
| 6.3.2 | <u>Borings SB-5 through SB-9</u> | 10 |
| 7.0 | SUMMARY | 14 |
| 7.1 | GROUNDWATER | 14 |
| 7.2 | SOILS | 14 |

LIST OF FIGURES

| | | |
|----------|-------------------------------|---|
| Figure 1 | Site Layout | 3 |
| Figure 2 | Water Table Contour Map | 9 |

LIST OF TABLES

| | | |
|---------|---|----|
| Table 1 | Soil Sample Volatile Organic Results | 11 |
| Table 2 | Soil Sample Semi-Volatile Organic Results | 12 |
| Table 3 | Soil Sample Metals Results | 13 |

LIST OF APPENDICES

| | |
|------------|---------------------------------|
| Appendix A | Boring and Well Completion Logs |
| Appendix B | Analytical Results |

1.0 INTRODUCTION

At the request of Ashland Chemical, Inc. (Ashland), a preacquisition preliminary environmental site assessment was performed in November, 1989, by Civil & Environmental Consultants (CEC), of Pittsburgh, Pennsylvania, at the Olin Water Services facility, 3155 Fiberglas Road, Kansas City, Kansas. CEC's Report of Findings, dated December 18, 1989, was prepared for and reviewed by Ashland for purposes of decision making regarding purchasing the property.

Groundwater Technology, Inc. (Groundwater Technology) was requested to edit and redraft the document to remove references relating to: conjecture, information redundancy, speculative recommendations and cost estimates, subjective conclusions, unbased qualifications, or other Ashland property acquisitions. The intent of the editing process performed by Groundwater Technology was to produce a concise statement of the facts and presentation of CEC's findings and data for submittal by Ashland to the Kansas Department of Health and Environmental (KDHE). No deletion of raw data or modifications to any of the original Figures or Tables from the CEC document, as received by Groundwater Technology, has been performed. For purposes of this presentation, original copies of CEC's Figures and Tables are included and referenced herein. No validation or technical review of any analytical data has been performed by Groundwater Technology. Groundwater Technology's quality control consistent with that of preparing and editing a consulting document for presentation to a client has been performed.


2.0 FACILITY DESCRIPTION

The Olin Water Services facility in Kansas City produces water-treatment products for reduction of boiler scale, biocidal, and other industrial water treatment applications. Raw materials are mixed in tanks within the manufacturing portion of the facility, and then transferred to appropriate containers for distribution.

The western portion of the property is owned by Olin, and is bounded on the east by railroad tracks, and on the north and west by public streets. The facility includes a manufacturing building, a drum storage area, and a hazardous-waste storage area (Figure 1). Immediately east of the manufacturing building are two aboveground product-storage tanks, which were installed in 1965. The northern tank is, and has been historically, used for storage of 50% sodium hydroxide (caustic). The southern tank is internally divided into three 2,000-gallon compartments. the southern compartment is used for morpholine storage, and the northern compartment is used to store cyclohexylamine. The center tank has historically been used for storage of several different materials. Initially, kerosene was stored in the center section. In the early 1970's, kerosene usage declined, and the compartment was then used for storage of aromatic naphtha. Around 1985, naphtha use was phased out, and the section filled with cyclohexylamine, which is currently stored in the tank.


The eastern portion of the facility is leased and used for Olin offices, as well as warehousing and shipping operations. Olin leases approximately two-thirds of the building, while the other third is currently vacant.

The eastern and western portions of the facility are separated by a railroad spur currently in sporadic use. Another railroad spur is located east of the leased building.



PAGE 3

FIGURE 1

| | | | |
|---|---|---------------------|-----------------------------------|
|  Civil & Environmental Consultants, Inc. <small>Formerly: 21 • 750 Hobart Drive • Pittsburgh, Pennsylvania 15220 (412) 921-9400 • (800) 360-9224 • Fax (412) 921-1610</small> | DATE: 12/1/89 SCALE: N T S | APPROVED BY: | DWN. BY: M.T.M |
| | | | CHKD. BY: |
| | SITE LAYOUT OLIN WATER SERVICES KANSAS CITY, KS | | SHEET 1 OF 1 |
| | | | DRAWING NUMBER 89208-A1 |

3.0 PHYSICAL SETTING

The Olin Water Services facility is located in the Fairfax Industrial District or northern Kansas City, Kansas, approximately one-half mile south of the Missouri River.

Borings installed by CEC at the site indicate that the site is underlain by approximately 12 feet of clayey silt. Beneath the silt is a fine, uniform sand that reportedly coarsens with depth, and immediately overlies bedrock. The thickness of this unit is not known. The water table occurs approximately 18 to 20 feet below grade in the sand unit. Regional groundwater flow in the water table aquifer is apparently to the north and east, toward the Missouri River.

The Fairfax District of Kansas City is largely an industrial area with many types of businesses present. Historical records indicate the area has been the site of industrial activity for several decades. Businesses adjacent to the Olin property include Rheinhold Chemical Company to the west, and Owens-Corning Fiberglas to the north.

4.0 CEC SCOPE OF WORK

In order to investigate the possibility of environmental contamination at the site prior to acquisition by Ashland, CEC proposed the following scope of work:

1. Installation of four shallow monitoring wells to allow collection of groundwater samples for analysis of Target Compound List (TCL) organics, as well as Target Analyte List (TAL) metals.
2. Advancement of nine shallow soil borings to allow collection of subsurface soil samples for TCL organics and TAL metals analyses.
3. Survey of wellhead elevations to determine groundwater flow directions based on measured static water levels in the new monitoring wells.
4. Title review and deed search to determine past ownership of the property and possible associated land use.
5. Preparation of a final report detailing our findings and interpretations.



5.0 METHODOLOGY

5.1 CEC SOIL BORINGS

The soil borings at the Olin facility were advanced using 3-1/4 inch I.D. hollow-stem augers and a CME 5-foot continuous split-spoon sampler. After reaching the desired depth, the sampler was removed from the hole and the sample examined for geologic materials, visible signs of contamination, and scanned for the presence of organic vapors using the HNu photoionizer. Appropriate portions of the samples were placed in laboratory-supplied jars in anticipation of submittal to the laboratory for required analyses. After completion of each boring, augers and samplers were cleaned by removal of soil adhering to surfaces, and the sampler was then wiped clean with potable water. Borings were backfilled with cuttings from the hole.

5.2 CEC MONITORING WELLS

Borings for the monitoring wells installed at the site were initially drilled using the 3-1/4 inch I.D. hollow-stem augers and 5-foot continuous sampler. Geologic materials were logged and examined as described above. After advancement of the initial boring to the final desired depth, the augers were removed from the hole. The boring was then reamed to 10-inch diameter using 6-1/4 inch I.D. hollow-stem augers. The annular space in the augers was sealed during drilling using a wooden plug that was subsequently knocked out of the augers and left at the bottom of the hole. Well installation then proceeded through the augers due to flowing sands encountered at depth.

Wells were constructed of 4-inch diameter Schedule 40 PVC pipe with 10-foot sections of 0.010 inch machine-slotted screens. Filter packs were composed of clean, well-sorted sand placed to a level approximately 2 feet above the top of the screen. A two-foot bentonite seal was then installed, and the remaining annular space sealed with a neat cement/bentonite slurry. Wells were completed with locking caps and flush-mount protective covers.



Well development was performed using a special surge block that allowed removal of drilling fines from the well bore, as well as creating a surge of water through the screen to loosen and remove fines from the sand pack. Development proceeded until little or no fine materials were produced by the well (typically 30 to 50 well volumes of water).

Immediately following development of the wells, samples of groundwater were collected for laboratory analysis of TCL organics and TAL metals. Samples were collected in a clean PVC bailer and transferred directly to laboratory-supplied bottles.

After completion of the wells, a wellhead survey was performed to determine relative elevations of the wells to within 1/100 of a foot. Static water levels were then measured, allowing determination of groundwater flow directions at the site.



6.0 INVESTIGATION FINDINGS

6.1 TITLE SEARCH


CEC initiated a title search of the property at Wyandotte County offices. However, due to complicated historical transactions involving the site, it was decided that CEC would terminate their deed search and, if desired, Ashland would contract a local service to obtain the necessary information. Ashland was informed, and confirmed this decision.

6.2 GROUNDWATER

CEC directed the installation of three monitoring wells on the Olin Water Services site. The boring and well completion logs are included in **Appendix A**. The well locations are depicted in **Figure 1**. Based on wellhead elevations and measurement of static water levels, groundwater flow was found to be directed toward the northeast (**Figure 2**).

Complete copies of the laboratory results of analysis of volatile organic compounds (VOC's), semi-volatile organic compounds, PCB's, pesticides, and dissolved metals for the groundwater samples collected from the three monitoring wells are included in (**Appendix B**). PCB's, pesticides, and semi-volatile organic results are all below method detection limits. VOC results are also all below method detection limits with the exceptions of trichloroethylene (TCE) and 1,2-dichloroethylene (1,2-DCE). TCE was detected in all three monitor wells at concentrations ranging between 5.9 and 34 ug/L and 1,2-DCE was detected in only one well, MW-2, at a concentration of 23 ug/L. Dissolved metals concentrations are in the range of background values presented in literature sources.





LEGEND

●

MONITORING
WELLS

81.15

WATER TABLE
ELEVATION

PAGE 9

NOTE: ELEVATION BASED ON RELATIVE PLANT DATUM.

| | | | |
|---|--|--------------------------------------|---------------------------|
| <div> <div> </div> <div> Civil & Environmental Consultants, Inc. <small> Former Plains 21 • 700 Holiday Drive • Pittsburgh, Pennsylvania 15220 (412) 921-5400 • (800) 360-7234 • Fax (412) 921-1810 </small> </div> </div> | <div> <div>DATE: 12/1/89</div> <div>SCALE: N T S</div> </div> | <div> <div>APPROVED BY:</div> </div> | <div>FIGURE 2</div> |
| | | | <div>DWN. BY: M.T.M</div> |
| | | | <div>CHKD. BY:</div> |
| | | | <div>SHEET 1 OF 1</div> |
| | <div> WATER TABLE CONTOUR MAP OLIN WATER SERVICES KANSAS CITY, KS </div> | | <div>DRAWING NUMBER</div> |
| | | | <div>89208 - A</div> |

6.3 SOILS

Positive volatile organic results for soil samples collected at the site are summarized in **Table 1**. **Table 2** presents positive semi-volatile organic results, and **Table 3** presents metals results. Copies of the soil boring logs, including HNu results, are included in **Appendix A**. Copies of the complete analytical results are included in **Appendix B**.

6.3.1 Borings SB-1 through SB-4 and SB-10 through SB-12

Soil borings SB-1 through SB-4 were intended to investigate near-surface soils in the vicinity of the two aboveground tanks. Borings locations are shown in **Figure 1**. As described in Section 5.1, soil samples collected were logged in the field and scanned for organic vapors using the HNu. Readings of up to 25 ppm were indicated by the HNu, prompting the advancement of additional borings SB-10 through SB-12. Borings SB-10 through SB-12 were advanced in an effort to better define the lateral and vertical extent of potentially impacted soils in the vicinity of the cyclohexamine storage tank. In addition to the soil borings, a surface soil sample was collected from an area of visible staining located between the railroad tracks (see **Figure 1**).

6.3.2 Borings SB-5 through SB-9

Soil borings SB-5 through SB-9 were intended to investigate the possibility of impacted near surface soils in the general areas of the property which are presently paved. Borings were completed approximately four feet deep. If no obvious signs of impacted soils were detected in these borings, no soil samples were to be submitted to the laboratory for analysis. Only SB-5, which indicated organic vapors of 3 ppm with the HNu, was sampled and analyzed for TCL volatile organics.

TABLE 1
SOIL SAMPLE VOLATILE ORGANIC RESULTS
(ug/kg)

| Boring: Sample Depth (feet): | SB-1 <u>1.5-4.0</u> | SB-2 <u>1.5-4.0</u> | SB-5 <u>1.5-4.0</u> | SB-10 <u>1.5-3.5</u> | SB-11 <u>1.5-3.5</u> | RR <u>Surface</u> |
|---------------------------------|------------------------|------------------------|------------------------|-------------------------|-------------------------|----------------------|
| Toluene | 9.4 | 6.6 | ND | ND | ND | 35 |
| Tetrachloroethylene | ND | 17 | ND | ND | ND | ND |
| Ethylbenzene | 5.7 | ND | ND | ND | ND | ND |
| Xylene | 12 | ND | ND | 2,700 | ND | 16 |
| Trichloroethylene (TCE) | ND | ND | 58 | ND | ND | ND |
| 1,2-dichlorobenzene | ND | ND | ND | 9,300 | 5,900 | ND |
| 1,4-dichlorobenzene | ND | ND | ND | 1,700 | ND | ND |
| Methylene Chloride | ND | ND | ND | ND | ND | 8 |
| Benzene | ND | ND | ND | ND | ND | 7 |

*Positive results only.

Report of Findings
Page 11

TABLE 2*
SOIL SAMPLE SEMI-VOLATILE ORGANIC RESULTS
(ug/kg)

| Boring: Sample Depth (feet): | SB-1 1.5-4.0 | SB-2 1.5-4.0 | SB-3 1.5-4.0 | SB-4 1.5-4.0 | SB-10 1.5-3.5 | SB-10 5.0-7.0 | SB-10 7.0-9.0 | SB-11 1.5-3.5 | RR Surface | Normal Background Concentrations** |
|-------------------------------------|-----------------|-----------------|-----------------|-----------------|------------------|------------------|------------------|------------------|---------------|--|
| Pyrene | ND | ND | ND | ND | 2,100 | ND | ND | ND | 9,100 | 100 |
| Naphthalene | ND | ND | ND | ND | 520 | ND | ND | ND | ND | -- |
| Pentachlorophenol | ND | ND | ND | ND | 22,000 | ND | ND | ND | ND | -- |
| Phenanthrene | ND | ND | ND | ND | 930 | ND | ND | ND | ND | -- |
| Fluoranthrene | ND | ND | ND | ND | 1,900 | ND | ND | ND | ND | -- |
| Benzo(a)anthracene ¹ | ND | ND | ND | ND | 1,300 | ND | ND | ND | ND | 5 - 120 |
| Chrysene ¹ | ND | ND | ND | ND | 1,500 | ND | ND | ND | ND | 20 |
| Benzo(b)fluoranthrene ¹ | ND | ND | ND | ND | 2,200 | ND | ND | ND | ND | 20 |
| Benzo(k)fluoranthrene ¹ | ND | ND | ND | ND | 1,100 | ND | ND | ND | ND | 10 |
| Benzo(a)pyrene ¹ | ND | ND | ND | ND | 1,600 | ND | ND | ND | ND | -- |
| Indeno(1,2,3-cd)pyrene ¹ | ND | ND | ND | ND | 1,200 | ND | ND | ND | ND | 50 - 75 |
| Benzo(g,h,i)perylene | ND | ND | ND | ND | 1,100 | ND | ND | ND | ND | -- |
| 1,1,2,2-tetrachloro-ethane | 260 | 280 | 500 | 310 | ND | 460 | 440 | 11 | ND | 100 |
| 1-methyl-2,4-pentanediol | 2000 | 390 | ND | ND | ND | ND | ND | ND | ND | -- |
| 1-methyl-N-nitroso-2-butanamine | 690 | ND | ND | ND | ND | ND | ND | ND | ND | -- |
| Morpholine | 990 | 270 | ND | ND | 370 | ND | ND | ND | ND | -- |
| Cyclohexanone | ND | 220 | ND | ND | ND | ND | ND | 330 | ND | -- |

Positive results only.

*Reference: International Association for Research on Cancer, 1983

Known or suspected carcinogen

Report of Findings
Page 12

TABLE 3
SOIL SAMPLE METALS RESULTS

| Boring: Sample Depth (feet): | SB-1 1.5-4.0 | SB-2 1.5-4.0 | SB-3 1.5-4.0 | SB-4 1.5-4.0 | SB-10 1.5-3.5 | SB-11 1.5-3.5 | SB-12 1.0-3.0 | Normal Background Concentrations** |
|---------------------------------|-----------------|-----------------|-----------------|-----------------|------------------|------------------|------------------|--|
| Aluminum | 15000 | 16000 | 27000 | 6800 | 9300 | 13000 | 7900 | -- |
| Antimony | <2.5 | <2.6 | 3.1 | <2.6 | <4.9 | <5.6 | <5.2 | -- |
| Arsenic | 20 | 8.5 | 17 | 9.8 | 3.7 | 9.6 | 2.3 | 6 |
| Barium | 210 | 220 | 280 | 210 | 110 | 260 | 88 | 430 |
| Beryllium | 1.2 | 1.2 | 1.1 | 0.87 | <0.48 | <0.56 | <0.52 | -- |
| Cadmium | 0.69 | 0.52 | 1.1 | 0.37 | 0.58 | 1.6 | <0.51 | 0.50 |
| Calcium | 16000 | 14000 | 20000 | 33000 | 33000 | 11000 | 3300 | -- |
| Chromium | 18 | 18 | 25 | 27 | 14 | 260 | 14 | 100 |
| Cobalt | 7.9 | 7.7 | 13 | 6.2 | 5.1 | 9.1 | 4.6 | 8 |
| Copper | 16 | 14 | 29 | 11 | 10 | 24 | 5.9 | 25 |
| Iron | 18000 | 17000 | 31000 | 16000 | 9700 | 19000 | 7200 | -- |
| Lead | 23 | 22 | 36 | 15 | 18 | 33 | 10 | 10 |
| Magnesium | 7200 | 7000 | 7900 | 5700 | 3300 | 6700 | 1600 | -- |
| Manganese | 340 | 1400 | 1600 | 460 | 310 | 810 | 190 | 850 |
| Mercury | 0.042 | 0.034 | <0.033 | <0.025 | 0.022 | 0.046 | 0.018 | 0.30 |
| Nickel | 17 | 25 | 28 | 13 | 11 | 21 | 9.5 | 40 |
| Potassium | 2200 | 3300 | 3800 | 1300 | 1600 | 2800 | 1000 | -- |
| Selenium | | | | | <0.97 | <1.1 | <1.0 | 0.50 |
| Silver | <1.0 | <1.0 | <1.2 | <1.1 | <0.97 | <1.1 | <1.0 | 0.05 |
| Sodium | 390 | 370 | 430 | 320 | 940 | 2400 | 860 | -- |
| Thallium | | | | | <0.87 | <1.1 | <1.0 | 5 |
| Vanadium | 34 | 44 | 51 | 19 | 19 | 36 | 13 | -- |
| Zinc | 56 | 72 | 82 | 52 | 46 | 100 | 32 | 50 |
| Soil pH | 7.9 | 7.7 | 8.1 | 8.0 | 9.7 | 9.1 | 8.4 | |

All concentrations in mg/kg on dry weight basis

*Reference: Metals in Soils: A Brief Summary, Office of Toxic Substances, USEPA

7.0 SUMMARY

7.1 GROUNDWATER

Based on wellhead elevations and measured static water levels in the monitoring wells, groundwater flow was found to be from southwest to northeast. Analytical water sample analyses indicate the presence of ppb concentrations of trichloroethylene (TCE) and 1,2-dichloroethylene (1,2-DCE) in wells MW-1, 2 and 3 and MW-2 respectively.

7.2 SOILS

Soils investigations (boring SB-5) indicates the presence of a ppb concentration of TCE in near surface soil below the parking lot south of the manufacturing portion of the facility. Analysis of an additional near surface soil sample, from the area around the aboveground storage tanks east of the building (the 1.5-3.5 foot interval of boring SB-10) indicates the localized presence of several semi-volatile organic components at this location. Neither the deeper soil samples from SB-10, nor similar depth samples from borings SB-1, 2 and 11 detected the same semi-volatile organic compounds. 1, 1,2, 2-tetrachloroethane was an exception in the above ground tank area, as it was detected in a number of the borings and at varying depths. Common fuel constituents; benzene, toluene, xylene, and ethylbenzene, were also detected at several near surface boring locations. In addition, dichlorobenzene was found in two of the borings.





Environmental, Health & Safety

G. W. Hammer
Director
(614) 889-3052

Ashland Chemical, Inc.
Subsidiary of
Ashland Oil, Inc.

Address: 2219
P.O. Box 2219
Columbus, Ohio 43216

RECEIVED *Zip*

SEP 27 1991

PERMIT SECTION

September 19, 1991

Lyndell L. Harrington, P.E.
Chief, Permit Section, RCRA Branch
U.S. EPA
Region VII
726 Minnesota Avenue
Kansas City, Kansas 66101

RE: EPA ID No. KSD000203638
Kansas City, Kansas Facility
Information Request

Dear Mr. Harrington:

Per your letter dated August 16, 1991, and received August 20, 1991 Drew Chemical, a Division of Ashland Chemical, Inc. submits the included information.

1. A final report of analytical data which was collected at the above facility during a pre-acquisition investigation. A draft report of a follow up investigation is not in final copy at this time. Please notify me if the agency requires that report also.
2. The alleged spill incident occurred on July 29, 1986, not July 29, 1990. During a routine inspection by the Kansas Department of Health and Environment on July 29, 1986 staining was noted on the sides of the VSR Sump Vat, but no material was being released at that time. The staining was a result of previous overflows of small unmeasurable quantities, which merely wetted the sides of the sump vat. Dates of the prior events are unknown.

If you have questions or need additional information please contact me at 614-889-3065.

Very truly yours,

William C. Olasin

William C. Olasin
Environmental Engineer

Headquarters
5200 Blazer Parkway
Dublin, Ohio 43017

Cable Address: Aroplaz OH
Telex: 245385
Answerback: ASHCHEM
Fax: (614) 889-3461
(614) 889-4250



Ashland Chemical's
Commitment to
Quality and Productivity

APPENDIX A
BORING AND WELL COMPLETION LOGS

SOIL BORING LOGS

| <u>Boring Number</u> | | | <u>HNu Readings</u> |
|----------------------|-------------|---|---|
| SB-1 | 0-1 ft. | Crushed stone | 12 ppm in hole |
| | 1-4 ft. | Black clayey silt, damp | |
| SB-2 | 0-1 ft. | Crushed stone | 25 ppm in hole |
| | 1-4 ft. | Dark gray clayey silt, dry to damp | |
| SB-3 | 0-1 ft. | Crushed stone | 1 ppm in hole |
| | 1-4 ft. | Dark gray and brown clayey silt, trace organics, dry to damp | |
| SB-4 | 0-1 ft. | Crushed stone | 0 ppm in hole |
| | 1-4 ft. | Dark gray silt, some fine sand near bottom, dry to damp | |
| SB-5 | 0-10 in. | Asphalt | 3 ppm in hole |
| | 1-4 ft. | Black silt, some wood and coal fragments, fine sand at bottom | |
| SB-6 | 0-1 ft. | Asphalt | 0 ppm in hole |
| | 1-4 ft. | Brown and black silt, brown sand at bottom, dry to damp | |
| SB-7 | 0-1 ft. | Asphalt | 0 ppm in hole |
| | 1-4 ft. | Dark gray silt, some wood fragments, dry to damp | |
| SB-8 | 0-1 ft. | Asphalt | 0 ppm in hole |
| | 1-4 ft. | Dark gray silt, dry to damp | |
| SB-9 | 0-1 ft. | Asphalt | 0 ppm in hole |
| | 1-4 ft. | Black silt with red brick fragments, brown silt, damp | |
| SB-10 | 0-1.5 ft. | Crushed stone | 4 ppm on sample 2 ppm on sample 1 ppm on sample |
| | 1.5-3.5 ft. | Dark gray silt, dry to damp | |
| | 5-7 ft. | Gray-brown silt, moist | |
| | 7-9 ft. | Gray-brown silt, moist | |
| SB-11 | 0-1.5 ft. | Crushed stone | 8 ppm on sample |
| | 1.5-3.5 ft. | Gray silt, black oily layer at 2.5 ft. | |
| SB-12 | 0-1 ft. | Crushed stone | 0 ppm on sample 0 ppm on sample |
| | 1-3 ft. | Brown silt, dry to damp | |
| | 5-7 ft. | Brown silt, damp | |



Civil & Environmental Consultants, Inc.

PROJECT
ELEVATION

Ashland 101in

GCL 0 HRS.

HRS.

DATE

11/20/89

FIELD ENGINEER

M KATH

PROJECT NO. 89208

BORING NO. MW-1

PAGE NO.

1 OF

| DEPTH FEET | BLOWS PER SIX INCHES OR CORE RECOVERY, MIN | SAMPLE NO. TYPE & SPON RECOVERY OR % ROCK RECOVERY | CASING BLOWS | DESCRIPTION | | | | USCS OR ROCK BROKENNESS | REMARKS |
|---------------|---|--|--------------|-------------|--|----------|-----------------------------------|----------------------------|--------------|
| | | | | PROFILE | SOIL DENSITY - CONSISTENCY OR ROCK HARDNESS | COLOR | MATERIAL CLASSIFICATION | | |
| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 |
| 1 | | | | | | | Railroad Ballast | | |
| 2 | | | | 5-1 | | Dk grey | Silt, some wood chips, damp | | 0 ppm |
| 3 | | | | | | | | | |
| 4 | | | | | | | | | |
| 5 | | | | | | | | | |
| 6 | | | | 5-2 | | Dk green | clayey silt, trace pebbles, moist | | 0 ppm |
| 7 | | | | | | | some wet layers evidence of | | |
| 8 | | | | | | | wet fractures in pores | | |
| 9 | | | | | | | | | |
| 10 | | | | | | Dk green | clayey silt, some wet layers | | |
| 11 | | | | 5-3 | | | | | 0 ppm |
| 12 | | | | | | | | | |
| 13 | | | | | | Dk green | brown v. well sorted fine sand | | |
| 14 | | | | | | | moist to wet - distinct contact | | |
| 15 | | | | | | | @ 12.5 ft | | |
| 16 | | | | k | | | | | |
| 17 | | | | 5 | | lt brown | v. well sorted fine sand dry | | 0 ppm |
| 18 | | | | | | | to damp fluffy | | |
| 19 | | | | | | | | | |
| 20 | | | | | | | | | |
| 21 | | | | | | Dk green | v. well sorted fine sand, | | 0 ppm |
| 22 | | | | 5-5 | | | wet loose | | sand blowing |
| 23 | | | | | | | | | gases 1.5 |
| 24 | | | | | | | | | |
| 25 | | | | | | | | | |
| 26 | | | | | | | | | |
| 27 | | | | 5-6 | | | | | |
| 28 | | | | | | | | | |
| 29 | | | | | | | | | |
| 30 | | | | | | | | | |

REMARKS

Sampled using CME 5 ft continuous sampler w/ 3 in. dia. augers

S.P.C. -

bags

cement -

bags

PROJECT NO.

BORING NO.

MW-1

POCKET PENETROMETER READINGS

SCREEN 30-20


20-17



Civil & Environmental Consultants, Inc.

PROJECT NAME: Ashland 10/in PROJECT NO.: 89208
WELL NO.: MW-1 DATE: _____ LOCATION: Kansas City, KS.
DRILLING METHOD: H.S.A. GEOLOGIST: M. Knuth

ELEVATION / DEPTH



NOTES: survey elevations using relative datum



Civil & Environmental Consultants, Inc.

PROJECT
ELEVATION

Ashland/Olin

GOL 0 HRS.

HRS.

PROJECT NO. 89208

BORING NO. MW-2

DATE

11/21

FIELD ENGINEER

M. K. Kutz

PAGE NO. 1 OF 1

| DEPTH FEET | BLOWS PER SIX INCHES OR CORE RECOVERY, MIN | SAMPLE NO. TYPE & SPHON RECOVERY OR % ROCK RECOVERY | CASING BLOWS | DESCRIPTION | | | | USCS OR ROCK BROKENNESS | REMARK |
|---------------|---|---|--------------|-------------|---|-------|---|----------------------------|--------|
| | | | | PROFILE | SOIL DENSITY- CONSISTENCY OR ROCK HARDNESS | COLOR | MATERIAL CLASSIFICATION | | |
| 1 | | | | | | | | | |
| 2 | | | | | | | Asphalt | | |
| 3 | | | | 5-1 | | | DK brn & black silt, trace sand & small pebbles damp | | 0.00m |
| 4 | | | | | | | | | |
| 5 | | | | | | | | | |
| 6 | | | | 5-2 | | | Brown clayey silt damp trace organic matl. | | 0.00m |
| 7 | | | | | | | | | |
| 8 | | | | | | | | | |
| 9 | | | | | | | | | |
| 10 | | | | | | | Brown clayey silt damp to 10ft | | 0.00m |
| 11 | | | | 5-3 | | | Brown well sorted fine sand, dm loose | | 0.00m |
| 12 | | | | | | | | | |
| 13 | | | | | | | | | |
| 14 | | | | | | | | | |
| 15 | | | | | | | | | |
| 16 | | | | 5-4 | | | Brown well sorted fine sand & silt | | 0.00m |
| 17 | | | | | | | | | |
| 18 | | | | | | | 16-16.5 ft - very clay lens matl | | |
| 19 | | | | | | | | | |
| 20 | | | | | | | | | |
| 21 | | | | 5-5 | | | Brown well sorted fine-med sand silt'd | | |
| 22 | | | | | | | | | |
| 23 | | | | | | | | | |
| 24 | | | | | | | | | |
| 25 | | | | | | | | | |
| 26 | | | | | | | | | |
| 27 | | | | | | | | | |
| 28 | | | | | | | | | |
| 29 | | | | | | | | | |
| 30 | | | | | | | | | |

REMARKS: screen 30'-20' sand 30'-18' bent 18'-15'

46 blows 42 points

PROJECT NO.

BORING NO.


POCKET PENETROMETER READINGS



Civil & Environmental Consultants, Inc.

PROJECT NAME: Ashland/Olin PROJECT NO.: 8920
WELL NO.: MW-2 DATE: _____ LOCATION: Kansas City, KS.
DRILLING METHOD: ASA GEOLOGIST: M. Kuth

ELEVATION / DEPTH



NOTES: Survey elevations using relative datum



Civil & Environmental Consultants, Inc.

PROJECT
ELEVATION

Ashland / Olin

GCL 0 HRS.
HRS.

PROJECT NO. 24208

BORING NO. MW-3

DATE 11/27

FIELD ENGINEER

M. KNOTA

PAGE NO. 1 OF 1

| DEPTH FEET | BLOWS PER SIX INCHES OR CORE RECOVERY, MIN | SAMPLE NO., TYPE & SPHON RECOVERY OR % ROCK RECOVERY | CASING BLOWS | DESCRIPTION | | | | USCS OR ROCK BROKENNESS | REMARKS |
|---------------|---|--|--------------|-------------|--|-------|----------------------------|----------------------------|---------|
| | | | | PROFILE | SOIL DENSITY - CONSISTENCY OR ROCK HARDNESS | COLOR | MATERIAL CLASSIFICATION | | |
| 1 | | | | | | | | | |
| 2 | | | | | | | | | |
| 3 | | | | | | | | | |
| 4 | | | | | | | | | |
| 5 | | | | | | | | | |
| 6 | | | | | | | | | |
| 7 | | | | | | | | | |
| 8 | | | | | | | | | |
| 9 | | | | | | | | | |
| 10 | | | | | | | | | |
| 11 | | | | | | | | | |
| 12 | | | | | | | | | |
| 13 | | | | | | | | | |
| 14 | | | | | | | | | |
| 15 | | | | | | | | | |
| 16 | | | | | | | | | |
| 17 | | | | | | | | | |
| 18 | | | | | | | | | |
| 19 | | | | | | | | | |
| 20 | | | | | | | | | |
| 21 | | | | | | | | | |
| 22 | | | | | | | | | |
| 23 | | | | | | | | | |
| 24 | | | | | | | | | |
| 25 | | | | | | | | | |
| 26 | | | | | | | | | |
| 27 | | | | | | | | | |
| 28 | | | | | | | | | |
| 29 | | | | | | | | | |
| 30 | | | | | | | | | |

REMARKS

SCREEN 24-17 SAND 24-17 bent 17-14 cement 7 6995

69 0000

62 0015

PROJECT NO.

BORING NO.


POCKET PENETROMETER READINGS



Civil & Environmental Consultants, Inc.

PROJECT NAME: Ashland/Olin PROJECT NO.: 89208
WELL NO.: MW-3 DATE: _____ LOCATION: Kansas City, Ks.
DRILLING METHOD: H.S.N. GEOLOGIST: M. Knuth

ELEVATION / DEPTH



NOTES: Survey elevations using relative datum

APPENDIX B
ANALYTICAL RESULTS

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10141

Received: 22 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89208/Olin, KC

REPORT OF ANALYTICAL RESULTS

Page 1

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY | | | |
|---------------------|---|------------|---------|---------|--|
| 10141-1 | SB-1 (11-21-89) | Client | | | |
| 10141-2 | SB-2 (11-21-89) | | | | |
| 10141-3 | SB-3 (11-21-89) | | | | |
| 10141-4 | SB-4 (11-21-89) | | | | |
| PARAMETER | 10141-1 | 10141-2 | 10141-3 | 10141-4 | |
| Aluminum, mg/kg dw | 15000 | 6500 | 27000 | 6800 | |
| Antimony, mg/kg dw | <2.5 | <2.6 | 3.1 | <2.6 | |
| Arsenic, mg/kg dw | 20 | 8.5 | 17 | 9.8 | |
| Barium, mg/kg dw | 210 | 220 | 280 | 210 | |
| Beryllium, mg/kg dw | 1.2 | 1.2 | 1.1 | 0.87 | |
| Cadmium, mg/kg dw | 0.69 | 0.52 | 1.1 | 0.37 | |
| Calcium, mg/kg dw | 16000 | 14000 | 20000 | 33000 | |
| Chromium, mg/kg dw | 18 | 18 | 25 | 27 | |
| Cobalt, mg/kg dw | 7.9 | 7.7 | 13 | 6.2 | |
| Copper, mg/kg dw | 16 | 14 | 29 | 11 | |
| Iron, mg/kg dw | 18000 | 17000 | 31000 | 16000 | |
| Lead, mg/l | 23 | 22 | 36 | 15 | |
| Magnesium, mg/kg dw | 7200 | 7000 | 7900 | 5700 | |
| Manganese, mg/kg dw | 340 | 1400 | 1600 | 460 | |
| Mercury, mg/kg dw | 0.042 | 0.034 | <0.033 | <0.025 | |
| Nickel, mg/kg dw | 17 | 25 | 28 | 13 | |
| Potassium, mg/kg dw | 2200 | 3300 | 3800 | 1300 | |
| Selenium, mg/kg dw | <1.0 | <0.98 | <1.1 | <1.0 | |
| Silver, mg/kg dw | <1.0 | <1.0 | <1.2 | <1.1 | |
| Sodium, mg/kg dw | 390 | 370 | 430 | 320 | |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10141

Received: 22 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89208/Olin, KC

REPORT OF ANALYTICAL RESULTS

Page 2

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY | | | |
|--------------------|---|------------|---------|---------|--|
| 10141-1 | SB-1 (11-21-89) | Client | | | |
| 10141-2 | SB-2 (11-21-89) | | | | |
| 10141-3 | SB-3 (11-21-89) | | | | |
| 10141-4 | SB-4 (11-21-89) | | | | |
| PARAMETER | 10141-1 | 10141-2 | 10141-3 | 10141-4 | |
| Thallium, mg/kg dw | <1.0 | <0.98 | <1.1 | <1.0 | |
| Vanadium, mg/kg dw | 34 | 44 | 51 | 19 | |
| Zinc, mg/kg dw | 56 | 72 | 82 | 52 | |
| Cyanide, mg/kg dw | <1.2 | <1.2 | <1.3 | <1.2 | |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10141

Received: 22 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89208/Olin, KC

REPORT OF ANALYTICAL RESULTS

Page 4.

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY | | | |
|-------------------------------------|---|------------|---------|---------|---------|
| 10141-1 | SB-1 (11-21-89) | Client | | | |
| 10141-2 | SB-2 (11-21-89) | | | | |
| 10141-3 | SB-3 (11-21-89) | | | | |
| 10141-4 | SB-4 (11-21-89) | | | | |
| PARAMETER | | 10141-1 | 10141-2 | 10141-3 | 10141-4 |
| Trans-1,3-Dichloropropene, ug/kg dw | | <5 | <5 | <5 | <5 |
| Trichloroethylene, ug/kg dw | | <5 | <5 | <5 | <5 |
| Dibromochloromethane, ug/kg dw | | <5 | <5 | <5 | <5 |
| 1,1,2-Trichloroethane, ug/kg dw | | <5 | <5 | <5 | <5 |
| Benzene, ug/kg dw | | <5 | <5 | <5 | <5 |
| Cis-1,3-Dichloropropene, ug/kg dw | | <5 | <5 | <5 | <5 |
| Bromoform, ug/kg dw | | <5 | <5 | <5 | <5 |
| 2-Hexanone, ug/kg dw | | <10 | <10 | <10 | <10 |
| 4-methyl-2-pentanone, ug/kg dw | | <10 | <10 | <10 | <10 |
| Tetrachloroethylene, ug/kg dw | | <5 | 17 | <5 | <5 |
| Toluene, ug/kg dw | | 9.4 | 6.6 | <5 | <5 |
| Chlorobenzene, ug/kg dw | | <5 | <5 | <5 | <5 |
| Ethylbenzene, ug/kg dw | | 5.7 | <5 | <5 | <5 |
| Styrene, ug/kg dw | | <5 | <5 | <5 | <5 |
| Xylenes, ug/kg dw | | 12 | <5 | <5 | <5 |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10141

Received: 22 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89208/Olin, KC

REPORT OF ANALYTICAL RESULTS

Page 5.

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY | | | |
|---|---|------------|---------|---------|---------|
| 10141-1 | SB-1 (11-21-89) | Client | | | |
| 10141-2 | SB-2 (11-21-89) | | | | |
| 10141-3 | SB-3 (11-21-89) | | | | |
| 10141-4 | SB-4 (11-21-89) | | | | |
| PARAMETER | | 10141-1 | 10141-2 | 10141-3 | 10141-4 |
| TCL Semivolatiles | | | | | |
| Phenol, ug/kg dw | | <470 | <470 | <470 | <470 |
| bis(2-Chloroethyl) ether, ug/kg dw | | <470 | <470 | <470 | <470 |
| 2-Chlorophenol, ug/kg dw | | <470 | <470 | <470 | <470 |
| 1,3-Dichlorobenzene, ug/kg dw | | <470 | <470 | <470 | <470 |
| 1,4-Dichlorobenzene, ug/kg dw | | <470 | <470 | <470 | <470 |
| Benzyl alcohol, ug/kg dw | | <940 | <940 | <940 | <940 |
| 1,2-Dichlorobenzene, ug/kg dw | | <470 | <470 | <470 | <470 |
| 2-Methylphenol (o-cresol), ug/kg dw | | <470 | <470 | <470 | <470 |
| bis(2-Chloro-1-methylethyl) ether, ug/kg dw | | <470 | <470 | <470 | <470 |
| 4-Methylphenol (p-cresol), ug/kg dw | | <470 | <470 | <470 | <470 |
| N-Nitroso-di-n-dipropylamine, ug/kg dw | | <470 | <470 | <470 | <470 |
| Hexachloroethane, ug/kg dw | | <470 | <470 | <470 | <470 |
| Nitrobenzene, ug/kg dw | | <470 | <470 | <470 | <470 |
| Isophorone, ug/kg dw | | <470 | <470 | <470 | <470 |
| 2-Nitrophenol, ug/kg dw | | <470 | <470 | <470 | <470 |
| 2,4-Dimethylphenol, ug/kg dw | | <470 | <470 | <470 | <470 |
| Benzoic acid, ug/kg dw | | <2400 | <2400 | <2400 | <2400 |
| bis(2-Chloroethoxy) methane, ug/kg dw | | <470 | <470 | <470 | <470 |
| 2,4-Dichlorophenol, ug/kg dw | | <470 | <470 | <470 | <470 |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10141

Received: 22 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89208/Olin, KC

REPORT OF ANALYTICAL RESULTS

Page 6.

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY | | | |
|-------------------------------------|---|------------|---------|---------|--|
| 10141-1 | SB-1 (11-21-89) | Client | | | |
| 10141-2 | SB-2 (11-21-89) | | | | |
| 10141-3 | SB-3 (11-21-89) | | | | |
| 10141-4 | SB-4 (11-21-89) | | | | |
| PARAMETER | 10141-1 | 10141-2 | 10141-3 | 10141-4 | |
| 1,2,4-Trichlorobenzene, ug/kg dw | <470 | <470 | <470 | <470 | |
| Naphthalene, ug/kg dw | <470 | <470 | <470 | <470 | |
| 4-Chloroaniline, ug/kg dw | <940 | <940 | <940 | <940 | |
| Hexachlorobutadiene, ug/kg dw | <470 | <470 | <470 | <470 | |
| 4-Chloro-3-methylphenol, ug/kg dw | <470 | <470 | <470 | <470 | |
| 2-Methylnaphthalene, ug/kg dw | <470 | <470 | <470 | <470 | |
| Hexachlorocyclopentadiene, ug/kg dw | <470 | <470 | <470 | <470 | |
| 2,4,6-Trichlorophenol, ug/kg dw | <470 | <470 | <470 | <470 | |
| 2,4,5-Trichlorophenol, ug/kg dw | <470 | <470 | <470 | <470 | |
| 2-Chloronaphthalene, ug/kg dw | <470 | <470 | <470 | <470 | |
| 2-Nitroaniline, ug/kg dw | <2400 | <2400 | <2400 | <2400 | |
| Dimethylphthalate, ug/kg dw | <470 | <470 | <470 | <470 | |
| Acenaphthylene, ug/kg dw | <470 | <470 | <470 | <470 | |
| 3-Nitroaniline, ug/kg dw | <2400 | <2400 | <2400 | <2400 | |
| Acenaphthene, ug/kg dw | <470 | <470 | <470 | <470 | |
| 2,4-Dinitrophenol, ug/kg dw | <2400 | <2400 | <2400 | <2400 | |
| 4-Nitrophenol, ug/kg dw | <2400 | <2400 | <2400 | <2400 | |
| Dibenzofuran, ug/kg dw | <470 | <470 | <470 | <470 | |
| 2,4-Dinitrotoluene, ug/kg dw | <470 | <470 | <470 | <470 | |
| 2,6-Dinitrotoluene, ug/kg dw | <470 | <470 | <470 | <470 | |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10141

Received: 22 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89208/Olin, KC

REPORT OF ANALYTICAL RESULTS

Page 3

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY | | | |
|-------------------------------------|---|------------|---------|---------|---------|
| 10141-1 | SB-1 (11-21-89) | Client | | | |
| 10141-2 | SB-2 (11-21-89) | | | | |
| 10141-3 | SB-3 (11-21-89) | | | | |
| 10141-4 | SB-4 (11-21-89) | | | | |
| PARAMETER | | 10141-1 | 10141-2 | 10141-3 | 10141-4 |
| Volatiles by GC/MS | | | | | |
| Chloromethane, ug/kg dw | | <10 | <10 | <10 | <10 |
| Bromomethane, ug/kg dw | | <10 | <10 | <10 | <10 |
| Vinyl Chloride, ug/kg dw | | <10 | <10 | <10 | <10 |
| Chloroethane, ug/kg dw | | <10 | <10 | <10 | <10 |
| Methylene Chloride, ug/kg dw | | <5 | <5 | <5 | <5 |
| Acetone, ug/kg dw | | <25 | <25 | <25 | <25 |
| Carbon Disulfide, ug/kg dw | | <5 | <5 | <5 | <5 |
| 1,1-Dichloroethylene, ug/kg dw | | <5 | <5 | <5 | <5 |
| 1,1-Dichloroethane, ug/kg dw | | <5 | <5 | <5 | <5 |
| 1,2-Dichloroethene, ug/kg dw | | <5 | <5 | <5 | <5 |
| Chloroform, ug/kg dw | | <5 | <5 | <5 | <5 |
| 1,2-Dichloroethane, ug/kg dw | | <5 | <5 | <5 | <5 |
| 2-Butanone, ug/kg dw | | <10 | <10 | <10 | <10 |
| 1,1,1-Trichloroethane, ug/kg dw | | <5 | <5 | <5 | <5 |
| Carbon Tetrachloride, ug/kg dw | | <5 | <5 | <5 | <5 |
| Vinyl Acetate, ug/kg dw | | <10 | <10 | <10 | <10 |
| Bromodichloromethane, ug/kg dw | | <5 | <5 | <5 | <5 |
| 1,1,2,2-Tetrachloroethane, ug/kg dw | | <5 | <5 | <5 | <5 |
| 1,2-Dichloropropane, ug/kg dw | | <5 | <5 | <5 | <5 |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10141

Received: 22 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89208/Olin, KC

REPORT OF ANALYTICAL RESULTS

Page 7

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY | | | |
|---|---|------------|---------|---------|---------|
| 10141-1 | SB-1 (11-21-89) | Client | | | |
| 10141-2 | SB-2 (11-21-89) | | | | |
| 10141-3 | SB-3 (11-21-89) | | | | |
| 10141-4 | SB-4 (11-21-89) | | | | |
| PARAMETER | | 10141-1 | 10141-2 | 10141-3 | 10141-4 |
| Diethylphthalate, ug/kg dw | | <470 | <470 | <470 | <470 |
| 4-Chlorophenyl-phenyl ether, ug/kg dw | | <470 | <470 | <470 | <470 |
| Fluorene, ug/kg dw | | <470 | <470 | <470 | <470 |
| 4-Nitroaniline, ug/kg dw | | <2400 | <2400 | <2400 | <2400 |
| 4,6-Dinitro-2-methylphenol, ug/kg dw | | <2400 | <2400 | <2400 | <2400 |
| N-Nitrosodiphenylamine/diphenylamine, ug/kg dw | | <470 | <470 | <470 | <470 |
| 4-Bromophenyl-phenyl-ether, ug/kg dw | | <470 | <470 | <470 | <470 |
| Hexachlorobenzene, ug/kg dw | | <470 | <470 | <470 | <470 |
| Pentachlorophenol, ug/kg dw | | <2400 | <2400 | <2400 | <2400 |
| Phenanthrene, ug/kg dw | | <470 | <470 | <470 | <470 |
| Anthracene, ug/kg dw | | <470 | <470 | <470 | <470 |
| Di-n-butylphthalate, ug/kg dw | | <470 | <470 | <470 | <470 |
| Fluoranthene, ug/kg dw | | <470 | <470 | <470 | <470 |
| Pyrene, ug/kg dw | | <470 | <470 | <470 | <470 |
| Butylbenzylphthalate, ug/kg dw | | <470 | <470 | <470 | <470 |
| 3,3'-Dichlorobenzidine, ug/kg dw | | <940 | <940 | <940 | <940 |
| Benzo(a)anthracene, ug/kg dw | | <470 | <470 | <470 | <470 |
| bis(2-Ethylhexyl) phthalate, ug/kg dw | | <470 | <470 | <470 | <470 |
| Chrysene, ug/kg dw | | <470 | <470 | <470 | <470 |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10141

Received: 22 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89208/Olin, KC

REPORT OF ANALYTICAL RESULTS

Page 8.

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY | | | |
|-----------------------------------|---|------------|---------|---------|--|
| 10141-1 | SB-1 (11-21-89) | Client | | | |
| 10141-2 | SB-2 (11-21-89) | | | | |
| 10141-3 | SB-3 (11-21-89) | | | | |
| 10141-4 | SB-4 (11-21-89) | | | | |
| PARAMETER | 10141-1 | 10141-2 | 10141-3 | 10141-4 | |
| Di-n-octylphthalate, ug/kg dw | <470 | <470 | <470 | <470 | |
| Benzo(b)fluoranthene, ug/kg dw | <470 | <470 | <470 | <470 | |
| Benzo(k)fluoranthene, ug/kg dw | <470 | <470 | <470 | <470 | |
| Benzo(a)pyrene, ug/kg dw | <470 | <470 | <470 | <470 | |
| Indeno (1,2,3-cd)pyrene, ug/kg dw | <470 | <470 | <470 | <470 | |
| Dibenzo (a,h)anthracene, ug/kg dw | <470 | <470 | <470 | <470 | |
| Benzo(g,h,i)perylene, ug/kg dw | <470 | <470 | <470 | <470 | |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10141

Received: 22 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89208/Olin, KC

REPORT OF ANALYTICAL RESULTS

Page 9

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY | | | |
|------------------------------|---|------------|---------|---------|---------|
| 10141-1 | SB-1 (11-21-89) | Client | | | |
| 10141-2 | SB-2 (11-21-89) | | | | |
| 10141-3 | SB-3 (11-21-89) | | | | |
| 10141-4 | SB-4 (11-21-89) | | | | |
| PARAMETER | | 10141-1 | 10141-2 | 10141-3 | 10141-4 |
| TCL Pesticides | | | | | |
| alpha-BHC, ug/kg dw | | <2.5 | <2.5 | <2.8 | <2.5 |
| beta-BHC, ug/kg dw | | <2.5 | <2.5 | <2.8 | <2.5 |
| delta-BHC, ug/kg dw | | <2.5 | <2.5 | <2.8 | <2.5 |
| gamma-BHC, ug/kg dw | | <2.5 | <2.5 | <2.8 | <2.5 |
| Heptachlor, ug/kg dw | | <2.5 | <2.5 | <2.8 | <2.5 |
| Aldrin, ug/kg dw | | <2.5 | <2.5 | <2.8 | <2.5 |
| Heptachlor epoxide, ug/kg dw | | <4.9 | <5.0 | <5.6 | <5.1 |
| Endosulfan I, ug/kg dw | | <4.9 | <5.0 | <5.6 | <5.1 |
| Dieldrin, ug/kg dw | | <4.9 | <5.0 | <5.6 | <5.1 |
| 4,4'-DDE, ug/kg dw | | <4.9 | <5.0 | <5.6 | <5.1 |
| Endrin, ug/kg dw | | <4.9 | <5.0 | <5.6 | <5.1 |
| Endosulfan II, ug/kg dw | | <12 | <13 | <14 | <13 |
| 4,4'-DDD, ug/kg dw | | <4.9 | <5.0 | <5.6 | <5.1 |
| Endosulfan sulfate, ug/kg dw | | <20 | <20 | <23 | <20 |
| 4,4'-DDT, ug/kg dw | | <12 | <13 | <14 | <13 |
| Endrin ketone, ug/kg dw | | <20 | <20 | <23 | <20 |
| Methoxychlor, ug/kg dw | | <99 | <100 | <110 | <100 |
| alpha-Chlordane, ug/kg dw | | <2.5 | <2.5 | <2.8 | <2.5 |
| gamma-Chlordane, ug/kg dw | | <2.5 | <2.5 | <2.8 | <2.5 |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10141

Received: 22 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89208/Olin, KC

REPORT OF ANALYTICAL RESULTS

Page 10

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY | | | |
|---------------------------|---|------------|---------|---------|--|
| 10141-1 | SB-1 (11-21-89) | Client | | | |
| 10141-2 | SB-2 (11-21-89) | | | | |
| 10141-3 | SB-3 (11-21-89) | | | | |
| 10141-4 | SB-4 (11-21-89) | | | | |
| PARAMETER | 10141-1 | 10141-2 | 10141-3 | 10141-4 | |
| Toxaphene, ug/kg dw | <200 | <200 | <230 | <200 | |
| Aroclor-1016, ug/kg dw | <99 | <100 | <110 | <100 | |
| Aroclor-1221, ug/kg dw | <99 | <100 | <110 | <100 | |
| Aroclor-1232, ug/kg dw | <99 | <100 | <110 | <100 | |
| Aroclor-1242, ug/kg dw | <99 | <100 | <110 | <100 | |
| Aroclor-1248, ug/kg dw | <99 | <100 | <110 | <100 | |
| Aroclor-1254, ug/kg dw | <99 | <100 | <110 | <100 | |
| Aroclor-1260, ug/kg dw | <99 | <100 | <110 | <100 | |
| NBS Library Search, ID | * | * | * | * | |
| pH, units | 7.9 | 7.7 | 8.1 | 8.0 | |
| Percent Solids, % | 81 % | 80 % | 71 % | 79 % | |
| Cyclohexylamine, ug/kg dw | <1900 | <1900 | <1900 | <1900 | |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10141

Received: 22 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89208/Olin, KC

REPORT OF ANALYTICAL RESULTS

Page 11

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY |
|----------------------------------|---|------------|
| 10141-5 | SB-5 (11-21-89) | Client |
| PARAMETER | 10141-5 | |
| Volatiles by GC/MS | | |
| Chloromethane, ug/kg | <10 | |
| Bromomethane, ug/kg | <10 | |
| Vinyl Chloride, ug/kg | <10 | |
| Chloroethane, ug/kg | <10 | |
| Methylene Chloride, ug/kg | <5 | |
| Acetone, ug/kg | <25 | |
| Carbon Disulfide, ug/kg | <5 | |
| 1,1-Dichloroethylene, ug/kg | <5 | |
| 1,1-Dichloroethane, ug/kg | <5 | |
| 1,2-Dichloroethene, ug/kg | <5 | |
| Chloroform, ug/kg | <5 | |
| 1,2-Dichloroethane, ug/kg | <5 | |
| 2-Butanone, ug/kg | <10 | |
| 1,1,1-Trichloroethane, ug/kg | <5 | |
| Carbon Tetrachloride, ug/kg | <5 | |
| Vinyl Acetate, ug/kg | <10 | |
| Bromodichloromethane, ug/kg | <5 | |
| 1,1,2,2-Tetrachloroethane, ug/kg | <5 | |
| 1,2-Dichloropropane, ug/kg | <5 | |
| Trans-1,3-Dichloropropene, ug/kg | <5 | |
| Trichloroethylene, ug/kg | 58 | |
| Dibromochloromethane, ug/kg | <5 | |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10141

Received: 22 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220


Project: 89208/Olin, KC

REPORT OF ANALYTICAL RESULTS

Page 12

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY |
|--------------------------------|---|------------|
| 10141-5 | SB-5 (11-21-89) | Client |
| PARAMETER | 10141-5 | |
| 1,1,2-Trichloroethane, ug/kg | <5 | |
| Benzene, ug/kg | <5 | |
| Cis-1,3-Dichloropropene, ug/kg | <5 | |
| Bromoform, ug/kg | <5 | |
| 2-Hexanone, ug/kg | <10 | |
| 4-methyl-2-pentanone, ug/kg | <10 | |
| Tetrachloroethylene, ug/kg | <5 | |
| Toluene, ug/kg | <5 | |
| Chlorobenzene, ug/kg | <5 | |
| Ethylbenzene, ug/kg | <5 | |
| Styrene, ug/kg | <5 | |
| Xylenes, ug/kg | <5 | |

Methods: SW-846.


Steven J. White

Organics Analysis Data Sheet

30.80g 81Z
FV = 1.0

| CAS Number | Compound Name | Fraction | RT or Scan Number | Estimated Concentration (ug/l or ug/kg) |
|-------------|-----------------------------------|----------|-------------------|---|
| 1. 79345 | Ethane, 1,1,2,2-tetrachloro- | BN/A | 6.678 | 260 |
| 2. 107415 | 2,4-Pentane diol, 2-methyl | BN/A | 7.484 | 2000 |
| 3. 35606372 | 2-Butanamine, N-methyl-N-nitroso- | BN/A | 11.524 | 690 |
| 4. 1696204 | Morpholine, 4-acetyl | BN/A | 12.660 | 990 |
| 5. | Unknown | BN/A | 14.101 | 180 |
| 6. | Unknown | BN/A | 14.485 | 370 |
| 7. 10544500 | Sulfur, mol. | BN/A | 23.084 | 1600 |
| 8. | | | | |
| 9. | | | | |
| 10. | | | | |
| 11. | | | | |
| 12. | | | | |
| 13. | | | | |
| 14. | | | | |
| 15. | | | | |
| 16. | | | | |
| 17. | | | | |
| 18. | | | | |
| 19. | | | | |
| 20. | | | | |
| 21. | | | | |
| 22. | | | | |
| 23. | | | | |
| 24. | | | | |
| 25. | | | | |
| 26. | | | | |
| 27. | | | | |
| 28. | | | | |
| 29. | | | | |
| 30. | | | | |

*Compound was identified by the comparison of the unknown peak with mass spectra stored in the National Bureau of Standards (NBS) library. No authentic standard available; concentration reported is semi-quantitative and based on the response factor of the internal standards added to the sample immediately before GC/MS analysis.

Laboratory Name: Savannah DivisionCase No: 1128A09A

Sample Number

10141-SB2

Organics Analysis Data Sheet

30.35g

FV 1.0

8090

| CAS Number | Compound Name | Fraction | RT or Scan Number | Estimated Concentration (ug/l or ug/kg) |
|-------------|------------------------------|----------|-------------------|---|
| 1. 100743 | Morpholine, 4-ethyl | BN/A | 5.613 | 270 |
| 2. 1008941 | Cyclohexanone | BN/A | 5.955 | 220 |
| 3. 79345 | Ethane, 1,1,2,2-tetrachloro- | BN/A | 6.696 | 280 |
| 4. | Unknown | BN/A | 7.196 | 580 |
| 5. 107415 | 2,4-Pentanediol, 2-methyl | BN/A | 7.448 | 390 |
| 6. | Unknown | BN/A | 11.543 | 690 |
| 7. | Unknown | BN/A | 13.128 | 3200 |
| 8. 10544500 | Sulfur, mol. | BN/A | 20.448 | 310 |
| 9. 10544500 | Sulfur, mol. | BN/A | 23.116 | 3500 |
| 10. | | | | |
| 11. | | | | |
| 12. | | | | |
| 13. | | | | |
| 14. | | | | |
| 15. | | | | |
| 16. | | | | |
| 17. | | | | |
| 18. | | | | |
| 19. | | | | |
| 20. | | | | |
| 21. | | | | |
| 22. | | | | |
| 23. | | | | |
| 24. | | | | |
| 25. | | | | |
| 26. | | | | |
| 27. | | | | |
| 28. | | | | |
| 29. | | | | |
| 30. | | | | |

*Compound was identified by the comparison of the unknown peak with mass spectra stored in the National Bureau of Standards (NBS) library. No authentic standard available; concentration reported is semi-quantitative and based on the response factor of the internal standards added to the sample immediately before GC/MS analysis.

Organics Analysis Data Sheet

30.23g 71%

FV = 1.0

| CAS Number | Compound Name | Fraction | RT or Scan Number | Estimated Concentration (ug/l or ug/kg) |
|------------|-----------------------------|----------|-------------------|---|
| 1. 79345 | Ethane, 1,1,2,2-tetrachloro | BN/A | 6.667 | 500 |
| 2. | | | | |
| 3. | | | | |
| 4. | | | | |
| 5. | | | | |
| 6. | | | | |
| 7. | | | | |
| 8. | | | | |
| 9. | | | | |
| 10. | | | | |
| 11. | | | | |
| 12. | | | | |
| 13. | | | | |
| 14. | | | | |
| 15. | | | | |
| 16. | | | | |
| 17. | | | | |
| 18. | | | | |
| 19. | | | | |
| 20. | | | | |
| 21. | | | | |
| 22. | | | | |
| 23. | | | | |
| 24. | | | | |
| 25. | | | | |
| 26. | | | | |
| 27. | | | | |
| 28. | | | | |
| 29. | | | | |
| 30. | | | | |

*Compound was identified by the comparison of the unknown peak with mass spectra stored in the National Bureau of Standards (NBS) library. No authentic standard available; concentration reported is semi-quantitative and based on the response factor of the internal standards added to the sample immediately before GC/MS analysis.

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10360

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 1

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY | | |
|---------------------|---|------------|---------|---------|
| 10360-1 | SB-10 1.5-3.5' (11.28.89) | Client | | |
| 10360-2 | SB-11 1.5-3.5' (11.28.89) | | | |
| 10360-3 | SB-12 1-3' (11.28.89) | | | |
| PARAMETER | | 10360-1 | 10360-2 | 10360-3 |
| Aluminum, mg/kg dw | | 9300 | 13000 | 7900 |
| Antimony, mg/kg dw | | <4.9 | <5.6 | <5.2 |
| Arsenic, mg/kg dw | | 3.7 | 9.6 | 2.3 |
| Barium, mg/kg dw | | 110 | 260 | 88 |
| Beryllium, mg/kg dw | | <0.48 | <0.56 | <0.52 |
| Cadmium, mg/kg dw | | 0.58 | 1.6 | <0.51 |
| Calcium, mg/kg dw | | 33000 | 11000 | 3300 |
| Chromium, mg/kg dw | | 14 | 260 | 14 |
| Cobalt, mg/kg dw | | 5.1 | 9.1 | 4.6 |
| Copper, mg/kg dw | | 10 | 24 | 5.9 |
| Iron, mg/kg dw | | 9700 | 19000 | 7200 |
| Lead, mg/kg dw | | 18 | 33 | 10 |
| Magnesium, mg/kg dw | | 3300 | 6700 | 1600 |
| Manganese, mg/kg dw | | 310 | 810 | 190 |
| Mercury, mg/kg dw | | 0.022 | 0.046 | 0.018 |
| Nickel, mg/kg dw | | 11 | 21 | 9.5 |
| Potassium, mg/kg dw | | 1600 | 2800 | 1000 |
| Selenium, mg/kg dw | | <0.97 | <1.1 | <1.0 |
| Silver, mg/kg dw | | <0.97 | <1.1 | <1.0 |
| Sodium, mg/kg dw | | 940 | 2400 | 860 |
| Thallium, mg/kg dw | | <0.87 | <1.1 | <1.0 |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10360

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 2

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY | | |
|--------------------|---|------------|---------|---------|
| 10360-1 | SB-10 1.5-3.5' (11.28.89) | Client | | |
| 10360-2 | SB-11 1.5-3.5' (11.28.89) | | | |
| 10360-3 | SB-12 1-3' (11.28.89) | | | |
| PARAMETER | | 10360-1 | 10360-2 | 10360-3 |
| Vanadium, mg/kg dw | | 19 | 36 | 13 |
| Zinc, mg/kg dw | | 46 | 100 | 32 |
| Cyanide, mg/kg dw | | <1.0 | <1.2 | <1.1 |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10360

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 3

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY | | |
|----------------------------------|---|------------|---------|---------|
| 10360-1 | SB-10 1.5-3.5' (11.28.89) | Client | | |
| 10360-2 | SB-11 1.5-3.5' (11.28.89) | | | |
| 10360-3 | SB-12 1-3' (11.28.89) | | | |
| PARAMETER | | 10360-1 | 10360-2 | 10360-3 |
| Volatiles by GC/MS | | | | |
| Chloromethane, ug/kg | | <1000 | <1000 | <10 |
| Bromomethane, ug/kg | | <1000 | <1000 | <10 |
| Vinyl Chloride, ug/kg | | <1000 | <1000 | <10 |
| Chloroethane, ug/kg | | <1000 | <1000 | <10 |
| Methylene Chloride, ug/kg | | <500 | <500 | <5 |
| Acetone, ug/kg | | <2500 | <2500 | <25 |
| Carbon Disulfide, ug/kg | | <500 | <500 | <5 |
| 1,1-Dichloroethylene, ug/kg | | <500 | <500 | <5 |
| 1,1-Dichloroethane, ug/kg | | <500 | <500 | <5 |
| 1,2-Dichloroethene, ug/kg | | <500 | <500 | <5 |
| Chloroform, ug/kg | | <500 | <500 | <5 |
| 1,2-Dichloroethane, ug/kg | | <500 | <500 | <5 |
| 2-Butanone, ug/kg | | <1000 | <1000 | <10 |
| 1,1,1-Trichloroethane, ug/kg | | <500 | <500 | <5 |
| Carbon Tetrachloride, ug/kg | | <500 | <500 | <5 |
| Vinyl Acetate, ug/kg | | <1000 | <1000 | <10 |
| Bromodichloromethane, ug/kg | | <500 | <500 | <5 |
| 1,1,2,2-Tetrachloroethane, ug/kg | | <500 | <500 | <5 |
| 1,2-Dichloropropane, ug/kg | | <500 | <500 | <5 |
| Trans-1,3-Dichloropropene, ug/kg | | <500 | <500 | <5 |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG' NO: 89-10360

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 4

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY | | |
|--------------------------------|---|------------|---------|---------|
| 10360-1 | SB-10 1.5-3.5' (11.28.89) | Client | | |
| 10360-2 | SB-11 1.5-3.5' (11.28.89) | | | |
| 10360-3 | SB-12 1-3' (11.28.89) | | | |
| PARAMETER | | 10360-1 | 10360-2 | 10360-3 |
| Trichloroethylene, ug/kg | | <500 | <500 | <5 |
| Dibromochloromethane, ug/kg | | <500 | <500 | <5 |
| 1,1,2-Trichloroethane, ug/kg | | <500 | <500 | <5 |
| Benzene, ug/kg | | <500 | <500 | <5 |
| Cis-1,3-Dichloropropene, ug/kg | | <500 | <500 | <5 |
| Bromoform, ug/kg | | <500 | <500 | <5 |
| 2-Hexanone, ug/kg | | <1000 | <1000 | <10 |
| 4-methyl-2-pentanone, ug/kg | | <1000 | <1000 | <10 |
| Tetrachloroethylene, ug/kg | | <500 | <500 | <5 |
| Toluene, ug/kg | | <500 | <500 | <5 |
| Chlorobenzene, ug/kg | | <500 | <500 | <5 |
| Ethylbenzene, ug/kg | | <500 | <500 | <5 |
| Styrene, ug/kg | | <500 | <500 | <5 |
| Xylenes, ug/kg | | 2700 | <500 | <5 |
| Additional Compounds: | | | | |
| 1,2 Dichlorobenzene, ug/kg | | 9300 | 5900 | — |
| 1,3 Dichlorobenzene, ug/kg | | <500 | <500 | — |
| 1,4 Dichlorobenzene, ug/kg | | 1700 | <500 | — |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10360

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 5

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY | | |
|---|---|------------|---------|---------|
| 10360-1 | SB-10 1.5-3.5' (11.28.89) | Client | | |
| 10360-2 | SB-11 1.5-3.5' (11.28.89) | | | |
| 10360-3 | SB-12 1-3' (11.28.89) | | | |
| PARAMETER | | 10360-1 | 10360-2 | 10360-3 |
| TCL Semivolatiles | | | | |
| Phenol, ug/kg dw | | <350 | <430 | <380 |
| bis(2-Chloroethyl) ether, ug/kg dw | | <350 | <430 | <380 |
| 2-Chlorophenol, ug/kg dw | | <350 | <430 | <380 |
| 1,3-Dichlorobenzene, ug/kg dw | | <350 | <430 | <380 |
| 1,4-Dichlorobenzene, ug/kg dw | | <350 | <430 | <380 |
| Benzyl alcohol, ug/kg dw | | <700 | <850 | <750 |
| 1,2-Dichlorobenzene, ug/kg dw | | <350 | <430 | <380 |
| 2-Methylphenol (o-cresol), ug/kg dw | | <350 | <430 | <380 |
| bis(2-Chloro-1-methylethyl) ether, ug/kg dw | | <350 | <430 | <380 |
| 4-Methylphenol (p-cresol), ug/kg dw | | <350 | <430 | <380 |
| N-Nitroso-di-n-dipropylamine, ug/kg dw | | <350 | <430 | <380 |
| Hexachloroethane, ug/kg dw | | <350 | <430 | <380 |
| Nitrobenzene, ug/kg dw | | <350 | <430 | <380 |
| Isophorone, ug/kg dw | | <350 | <430 | <380 |
| 2-Nitrophenol, ug/kg dw | | <350 | <430 | <380 |
| 2,4-Dimethylphenol, ug/kg dw | | <350 | <430 | <380 |
| Benzoic acid, ug/kg dw | | <1800 | <1900 | <1900 |
| bis(2-Chloroethoxy) methane, ug/kg dw | | <350 | <430 | <380 |
| 2,4-Dichlorophenol, ug/kg dw | | <350 | <430 | <380 |
| 1,2,4-Trichlorobenzene, ug/kg dw | | <350 | <430 | <380 |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

SAVANNAH LABORATORIES AND ENVIRONMENTAL SERVICES, INC.

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10360

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 6

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY | | |
|---------------------------------------|---|------------|---------|---------|
| 10360-1 | SB-10 1.5-3.5' (11.28.89) | Client | | |
| 10360-2 | SB-11 1.5-3.5' (11.28.89) | | | |
| 10360-3 | SB-12 1-3' (11.28.89) | | | |
| PARAMETER | | 10360-1 | 10360-2 | 10360-3 |
| Naphthalene, ug/kg dw | | 520 | <430 | <380 |
| 4-Chloroaniline, ug/kg dw | | <700 | <850 | <750 |
| Hexachlorobutadiene, ug/kg dw | | <350 | <430 | <380 |
| 4-Chloro-3-methylphenol, ug/kg dw | | <350 | <430 | <380 |
| 2-Methylnaphthalene, ug/kg dw | | <350 | <430 | <380 |
| Hexachlorocyclopentadiene, ug/kg dw | | <350 | <430 | <380 |
| 2,4,6-Trichlorophenol, ug/kg dw | | <350 | <430 | <380 |
| 2,4,5-Trichlorophenol, ug/kg dw | | <350 | <430 | <380 |
| 2-Chloronaphthalene, ug/kg dw | | <350 | <430 | <380 |
| 2-Nitroaniline, ug/kg dw | | <1800 | <1900 | <1900 |
| Dimethylphthalate, ug/kg dw | | <350 | <430 | <380 |
| Acenaphthylene, ug/kg dw | | <350 | <430 | <380 |
| 3-Nitroaniline, ug/kg dw | | <1800 | <1900 | <1900 |
| Acenaphthene, ug/kg dw | | <350 | <430 | <380 |
| 2,4-Dinitrophenol, ug/kg dw | | <1800 | <1900 | <1900 |
| 4-Nitrophenol, ug/kg dw | | <1800 | <1900 | <1900 |
| Dibenzofuran, ug/kg dw | | <350 | <430 | <380 |
| 2,4-Dinitrotoluene, ug/kg dw | | <350 | <430 | <380 |
| 2,6-Dinitrotoluene, ug/kg dw | | <350 | <430 | <380 |
| Diethylphthalate, ug/kg dw | | <350 | <430 | <380 |
| 4-Chlorophenyl-phenyl ether, ug/kg dw | | <350 | <430 | <380 |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10360

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 7

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY | | |
|--|---|------------|---------|---------|
| 10360-1 | SB-10 1.5-3.5' (11.28.89) | Client | | |
| 10360-2 | SB-11 1.5-3.5' (11.28.89) | | | |
| 10360-3 | SB-12 1-3' (11.28.89) | | | |
| PARAMETER | | 10360-1 | 10360-2 | 10360-3 |
| Fluorene, ug/kg dw | | <350 | <430 | <380 |
| 4-Nitroaniline, ug/kg dw | | <1800 | <1900 | <1900 |
| 4,6-Dinitro-2-methylphenol, ug/kg dw | | <1800 | <1900 | <1900 |
| N-Nitrosodiphenylamine/diphenylamine, ug/kg dw | | <350 | <430 | <380 |
| 4-Bromophenyl-phenyl-ether, ug/kg dw | | <350 | <430 | <380 |
| Hexachlorobenzene, ug/kg dw | | <350 | <430 | <380 |
| Pentachlorophenol, ug/kg dw | | 22000 | <1900 | <1900 |
| Phenanthrene, ug/kg dw | | 930 | <430 | <380 |
| Anthracene, ug/kg dw | | <350 | <430 | <380 |
| Di-n-butylphthalate, ug/kg dw | | <350 | <430 | <380 |
| Fluoranthene, ug/kg dw | | 1900 | <430 | <380 |
| Pyrene, ug/kg dw | | 2100 | <430 | <380 |
| Butylbenzylphthalate, ug/kg dw | | <350 | <430 | <380 |
| 3,3'-Dichlorobenzidine, ug/kg dw | | <700 | <850 | <750 |
| Benzo(a)anthracene, ug/kg dw | | 1300 | <430 | <380 |
| bis(2-Ethylhexyl) phthalate, ug/kg dw | | <350 | <430 | <380 |
| Chrysene, ug/kg dw | | 1500 | <430 | <380 |
| Di-n-octylphthalate, ug/kg dw | | <350 | <430 | <380 |
| Benzo(b)fluoranthene, ug/kg dw | | 2200 | <430 | <380 |
| Benzo(k)fluoranthene, ug/kg dw | | 1100 | <430 | <380 |
| Benzo(a)pyrene, ug/kg dw | | 1600 | <430 | <380 |
| Indeno (1,2,3-cd)pyrene, ug/kg dw | | 1200 | <430 | <380 |
| Dibenzo (a,h)anthracene, ug/kg dw | | <350 | <430 | <380 |
| Benzo(g,h,i)perylene, ug/kg dw | | 1100 | <430 | <380 |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10360

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 8

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY | | |
|------------------------------|---|------------|---------|---------|
| 10360-1 | SB-10 1.5-3.5' (11.28.89) | Client | | |
| 10360-2 | SB-11 1.5-3.5' (11.28.89) | | | |
| 10360-3 | SB-12 1-3' (11.28.89) | | | |
| PARAMETER | | 10360-1 | 10360-2 | 10360-3 |
| TCL Pesticides | | | | |
| alpha-BHC, ug/kg dw | | <2.2 | <2.6 | <2.3 |
| beta-BHC, ug/kg dw | | <2.2 | <2.6 | <2.3 |
| delta-BHC, ug/kg dw | | <2.2 | <2.6 | <2.3 |
| gamma-BHC, ug/kg dw | | <2.2 | <2.6 | <2.3 |
| Heptachlor, ug/kg dw | | <2.2 | <2.6 | <2.3 |
| Aldrin, ug/kg dw | | <2.2 | <2.6 | <2.3 |
| Heptachlor epoxide, ug/kg dw | | <4.3 | <5.2 | <4.6 |
| Endosulfan I, ug/kg dw | | <4.3 | <5.2 | <4.6 |
| Dieldrin, ug/kg dw | | <4.3 | <5.2 | <4.6 |
| 4,4'-DDE, ug/kg dw | | <4.3 | <5.2 | <4.6 |
| Endrin, ug/kg dw | | <4.3 | <5.2 | <4.6 |
| Endosulfan II, ug/kg dw | | <11 | <13 | <11 |
| 4,4'-DDD, ug/kg dw | | <4.3 | <5.2 | <4.3 |
| Endosulfan sulfate, ug/kg dw | | <17 | <21 | <18 |
| 4,4'-DDT, ug/kg dw | | <11 | <13 | <11 |
| Endrin ketone, ug/kg dw | | <17 | <21 | <18 |
| Methoxychlor, ug/kg dw | | <86 | <100 | <92 |
| alpha-Chlordane, ug/kg dw | | <2.2 | <2.6 | <2.3 |
| gamma-Chlordane, ug/kg dw | | <2.2 | <2.6 | <2.3 |
| Toxaphene, ug/kg dw | | <170 | <210 | <180 |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10360

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 9

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY | | |
|---------------------------|---|------------|---------|---------|
| 10360-1 | SB-10 1.5-3.5' (11.28.89) | Client | | |
| 10360-2 | SB-11 1.5-3.5' (11.28.89) | | | |
| 10360-3 | SB-12 1-3' (11.28.89) | | | |
| PARAMETER | | 10360-1 | 10360-2 | 10360-3 |
| Aroclor-1016, ug/kg dw | | <86 | <100 | <86 |
| Aroclor-1221, ug/kg dw | | <86 | <100 | <86 |
| Aroclor-1232, ug/kg dw | | <86 | <100 | <86 |
| Aroclor-1242, ug/kg dw | | <86 | <100 | <86 |
| Aroclor-1248, ug/kg dw | | <86 | <100 | <86 |
| Aroclor-1254, ug/kg dw | | <86 | <100 | <86 |
| Aroclor-1260, ug/kg dw | | <86 | <100 | <86 |
| Percent Solids, % | | 93 % | 77 % | 87 % |
| NBS Library Search, ID | | * | * | * |
| pH, units | | 9.7 | 9.1 | 8.4 |
| Cyclohexylamine, ug/kg dw | | <1400 | <1700 | <1500 |

Laboratory Name: SSVANNAH LABORATORIESCase No: 10360Sample Number
SB-10 1.5-3.5'

Organics Analysis Data Sheet

| CAS Number | Compound Name | Fraction | RT or Scan Number | Estimated Concentration (ug/l or ug/kg) |
|-------------|---|----------|-------------------|---|
| 1. 110918 | Morpholine | SV | 4.54 | 370.0 |
| 2. | UNKNOWN | SV | 6.79 | 650.0 |
| 3. 928949 | 2-Hexen-1-01 (Z) | SV | 7.79 | 53.0 |
| 4. | UNKNOWN | SV | 9.45 | 37.0 |
| 5. | UNKNOWN | SV | 12.86 | 61.0 |
| 6. | UNKNOWN | SV | 13.25 | 28.0 |
| 7. | UNKNOWN | SV | 13.39 | 25.0 |
| 8. | UNKNOWN | SV | 14.02 | 47.0 |
| 9. | UNKNOWN | SV | 14.46 | 35.0 |
| 10. | UNKNOWN | SV | 14.63 | 36.0 |
| 11. | UNKNOWN | SV | 14.76 | 23.0 |
| 12. | UNKNOWN | SV | 14.87 | 27.0 |
| 13. | UNKNOWN | SV | 15.12 | 67.0 |
| 14. 1483609 | Benzene, 2,4-dimethyl-1-(1 methyl/propyl) | SV | 15.36 | 32.0 |
| 15. 91576 | Naphthalene, 2-methyl- | SV | 15.84 | 41.0 |
| 16. | UNKNOWN | SV | 15.94 | 48.0 |
| 17. 569415 | Naphthalene, 1,8-dimethyl | SV | 17.22 | 46.0 |
| 18. 571584 | Naphthalene, 1-4-dimethyl- | SV | 17.43 | 94.0 |
| 19. 573988 | Naphthalene, 1,2-dimethyl- | SV | 17.69 | 40.0 |
| 20. | | | | |
| 21. | | | | |
| 22. | | | | |
| 23. | | | | |
| 24. | | | | |
| 25. | | | | |
| 26. | | | | |
| 27. | | | | |
| 28. | | | | |
| 29. | | | | |
| 30. | | | | |

*Compound was identified by the comparison of the unknown peak with mass spectra stored in the National Bureau of Standards (NBS) library. No authentic standard available; concentration reported is semi-quantitative and based on the response factor of the internal standards added to the sample immediately before GC/MS analysis.

Laboratory Name: SAVANNAH LABORATORIESCase No: 10360

Sample Number

SB-11 1.5-3.5⁷

Organics Analysis Data Sheet

| CAS Number | Compound Name | Fraction | RT or Scan Number | Estimated Concentration (ug/l or ug/kg) |
|--------------|------------------------------|----------|-------------------|---|
| 1. 110918 | Morpholine (ACN) | SV | 4.50 | 330 |
| 2. 79345 | Ethane, 1,1,2,2-tetrachloro- | SV | 8.05 | 11 |
| 3. | UNKNOWN | SV | 8.46 | 16 |
| 4. | UNKNOWN | SV | 9.93 | 5 |
| 5. | UNKNOWN | SV | 12.65 | 44 |
| 6. 1696204 | Morpholine 4-acetyl- | SV | 13.83 | 28 |
| 7. | UNKNOWN | SV | 14.84 | 4.0 |
| 8. | UNKNOWN | SV | 15.08 | 6.0 |
| 9. | UNKNOWN | SV | 15.91 | 5.0 |
| 10. | UNKNOWN | SV | 17.01 | 190 |
| 11. 569415 | Naphthalene, 1,8-dimethyl- | SV | 17.19 | 4.0 |
| 12. 569415 | Naphthalene, 1,8-dimethyl- | SV | 17.38 | 5.0 |
| 13. | UNKNOWN | SV | 18.52 | 5.0 |
| 14. | UNKNOWN | SV | 20.40 | 7.0 |
| 15. 10544500 | Sulfur, mol. | SV | 24.84 | 15.0 |
| 16. | | | | |
| 17. | | | | |
| 18. | | | | |
| 19. | | | | |
| 20. | | | | |
| 21. | | | | |
| 22. | | | | |
| 23. | | | | |
| 24. | | | | |
| 25. | | | | |
| 26. | | | | |
| 27. | | | | |
| 28. | | | | |
| 29. | | | | |
| 30. | | | | |

*Compound was identified by the comparison of the unknown peak with mass spectra stored in the National Bureau of Standards (NBS) library. No authentic standard available; concentration reported is semi-quantitative and based on the response factor of the internal standards added to the sample immediately before GC/MS analysis.

Laboratory Name: SAVANNAH LABORATORIESCase No: 10360

Sample Number

SB-10 5-7'

Organics Analysis Data Sheet

| CAS Number | Compound Name | Fraction | RT or Scan Number | Estimated Concentration (ug/l or ug/kg) |
|------------|------------------------------|----------|-------------------|---|
| 1. 79345 | Ethane, 1,1,2,2-tetrachloro- | SV | 7.93 | 460 |
| 2. | | | | |
| 3. | | | | |
| 4. | | | | |
| 5. | | | | |
| 6. | | | | |
| 7. | | | | |
| 8. | | | | |
| 9. | | | | |
| 10. | | | | |
| 11. | | | | |
| 12. | | | | |
| 13. | | | | |
| 14. | | | | |
| 15. | | | | |
| 16. | | | | |
| 17. | | | | |
| 18. | | | | |
| 19. | | | | |
| 20. | | | | |
| 21. | | | | |
| 22. | | | | |
| 23. | | | | |
| 24. | | | | |
| 25. | | | | |
| 26. | | | | |
| 27. | | | | |
| 28. | | | | |
| 29. | | | | |
| 30. | | | | |

*Compound was identified by the comparison of the unknown peak with mass spectra stored in the National Bureau of Standards (NBS) library. No authentic standard available; concentration reported is semi-quantitative and based on the response factor of the internal standards added to the sample immediately before GC/MS analysis.

Laboratory Name: SAVANNAH LABORATORIESCase No: 10360

Sample Number

SB-10 7-9'

Organics Analysis Data Sheet

| CAS Number | Compound Name | Fraction | RT or Scan Number | Estimated Concentration (ug/l or ug/kg) |
|------------|------------------------------|----------|-------------------|---|
| 1. 79345 | Ethane, 1,1,2,2-tetrachloro- | SV | 7.95 | 440 |
| 2. | | | | |
| 3. | | | | |
| 4. | | | | |
| 5. | | | | |
| 6. | | | | |
| 7. | | | | |
| 8. | | | | |
| 9. | | | | |
| 10. | | | | |
| 11. | | | | |
| 12. | | | | |
| 13. | | | | |
| 14. | | | | |
| 15. | | | | |
| 16. | | | | |
| 17. | | | | |
| 18. | | | | |
| 19. | | | | |
| 20. | | | | |
| 21. | | | | |
| 22. | | | | |
| 23. | | | | |
| 24. | | | | |
| 25. | | | | |
| 26. | | | | |
| 27. | | | | |
| 28. | | | | |
| 29. | | | | |
| 30. | | | | |

*Compound was identified by the comparison of the unknown peak with mass spectra stored in the National Bureau of Standards (NBS) library. No authentic standard available; concentration reported is semi-quantitative and based on the response factor of the internal standards added to the sample immediately before GC/MS analysis.

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10360

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 10

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY |
|----------------------------------|---|------------|
| 10360-4 | RR (11.28.89) | Client |
| PARAMETER | 10360-4 | |
| Volatiles by GC/MS | | |
| Chloromethane, ug/kg | <10 | |
| Bromomethane, ug/kg | <10 | |
| Vinyl Chloride, ug/kg | <10 | |
| Chloroethane, ug/kg | <10 | |
| Methylene Chloride, ug/kg | 8 | |
| Acetone, ug/kg | <25 | |
| Carbon Disulfide, ug/kg | <5 | |
| 1,1-Dichloroethylene, ug/kg | <5 | |
| 1,1-Dichloroethane, ug/kg | <5 | |
| 1,2-Dichloroethene, ug/kg | <5 | |
| Chloroform, ug/kg | <5 | |
| 1,2-Dichloroethane, ug/kg | <5 | |
| 2-Butanone, ug/kg | <10 | |
| 1,1,1-Trichloroethane, ug/kg | <5 | |
| Carbon Tetrachloride, ug/kg | <5 | |
| Vinyl Acetate, ug/kg | <10 | |
| Bromodichloromethane, ug/kg | <5 | |
| 1,1,2,2-Tetrachloroethane, ug/kg | <5 | |
| 1,2-Dichloropropane, ug/kg | <5 | |
| Trans-1,3-Dichloropropene, ug/kg | <5 | |
| Trichloroethylene, ug/kg | <5 | |
| Dibromochloromethane, ug/kg | <5 | |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858

LOG NO: 89-

Received: 30 N

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89:

REPORT OF ANALYTICAL RESULTS

Page

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED |
|--------------------------------|---|---------|
| 10360-4 | RR (11.28.89) | Clia |
| PARAMETER | 10360-4 | |
| 1,1,2-Trichloroethane, ug/kg | <5 | |
| Benzene, ug/kg | 7 | |
| Cis-1,3-Dichloropropene, ug/kg | <5 | |
| Bromoform, ug/kg | <5 | |
| 2-Hexanone, ug/kg | <10 | |
| 4-methyl-2-pentanone, ug/kg | <10 | |
| Tetrachloroethylene, ug/kg | <5 | |
| Toluene, ug/kg | 35 | |
| Chlorobenzene, ug/kg | <5 | |
| Ethylbenzene, ug/kg | <5 | |
| Styrene, ug/kg | <5 | |
| Xylenes, ug/kg | 16 | |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10360

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 12

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY |
|---|---|------------|
| 10360-4 | RR (11.28.89) | Client |
| PARAMETER | 10360-4 | |
| TCL Semivolatiles | | |
| Phenol, ug/kg dw | <8700 | |
| bis(2-Chloroethyl) ether, ug/kg dw | <8700 | |
| 2-Chlorophenol, ug/kg dw | <8700 | |
| 1,3-Dichlorobenzene, ug/kg dw | <8700 | |
| 1,4-Dichlorobenzene, ug/kg dw | <8700 | |
| Benzyl alcohol, ug/kg dw | <18000 | |
| 1,2-Dichlorobenzene, ug/kg dw | <8700 | |
| 2-Methylphenol (o-cresol), ug/kg dw | <8700 | |
| bis(2-Chloro-1-methylethyl) ether, ug/kg dw | <8700 | |
| 4-Methylphenol (p-cresol), ug/kg dw | <8700 | |
| N-Nitroso-di-n-dipropylamine, ug/kg dw | <8700 | |
| Hexachloroethane, ug/kg dw | <8700 | |
| Nitrobenzene, ug/kg dw | <8700 | |
| Isophorone, ug/kg dw | <8700 | |
| 2-Nitrophenol, ug/kg dw | <8700 | |
| 2,4-Dimethylphenol, ug/kg dw | <8700 | |
| Benzoic acid, ug/kg dw | <44000 | |
| bis(2-Chloroethoxy) methane, ug/kg dw | <8700 | |
| 2,4-Dichlorophenol, ug/kg dw | <8700 | |
| 1,2,4-Trichlorobenzene, ug/kg dw | <8700 | |
| Naphthalene, ug/kg dw | <8700 | |
| 4-Chloroaniline, ug/kg dw | <18000 | |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10360

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 13

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY |
|--|---|------------|
| 10360-4 | RR (11.28.89) | Client |
| PARAMETER | 10360-4 | |
| Hexachlorobutadiene, ug/kg dw | <8700 | |
| 4-Chloro-3-methylphenol, ug/kg dw | <8700 | |
| 2-Methylnaphthalene, ug/kg dw | <8700 | |
| Hexachlorocyclopentadiene, ug/kg dw | <8700 | |
| 2,4,6-Trichlorophenol, ug/kg dw | <8700 | |
| 2,4,5-Trichlorophenol, ug/kg dw | <8700 | |
| 2-Chloronaphthalene, ug/kg dw | <8700 | |
| 2-Nitroaniline, ug/kg dw | <44000 | |
| Dimethylphthalate, ug/kg dw | <8700 | |
| Acenaphthylene, ug/kg dw | <8700 | |
| 3-Nitroaniline, ug/kg dw | <44000 | |
| Acenaphthene, ug/kg dw | <8700 | |
| 2,4-Dinitrophenol, ug/kg dw | <44000 | |
| 4-Nitrophenol, ug/kg dw | <44000 | |
| Dibenzofuran, ug/kg dw | <8700 | |
| 2,4-Dinitrotoluene, ug/kg dw | <8700 | |
| 2,6-Dinitrotoluene, ug/kg dw | <8700 | |
| Diethylphthalate, ug/kg dw | <8700 | |
| 4-Chlorophenyl-phenyl ether, ug/kg dw | <8700 | |
| Fluorene, ug/kg dw | <8700 | |
| 4-Nitroaniline, ug/kg dw | <44000 | |
| 4,6-Dinitro-2-methylphenol, ug/kg dw | <44000 | |
| N-Nitrosodiphenylamine/diphenylamine, ug/kg dw | <8700 | |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10360

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 14

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY |
|---------------------------------------|---|------------|
| 10360-4 | RR (11.28.89) | Client |
| PARAMETER | 10360-4 | |
| 4-Bromophenyl-phenyl-ether, ug/kg dw | <8700 | |
| Hexachlorobenzene, ug/kg dw | <8700 | |
| Pentachlorophenol, ug/kg dw | <44000 | |
| Phenanthrene, ug/kg dw | <8700 | |
| Anthracene, ug/kg dw | <8700 | |
| Di-n-butylphthalate, ug/kg dw | <8700 | |
| Fluoranthene, ug/kg dw | <8700 | |
| Pyrene, ug/kg dw | 9100 | |
| Butylbenzylphthalate, ug/kg dw | <8700 | |
| 3,3'-Dichlorobenzidine, ug/kg dw | <18000 | |
| Benzo(a)anthracene, ug/kg dw | <8700 | |
| bis(2-Ethylhexyl) phthalate, ug/kg dw | <8700 | |
| Chrysene, ug/kg dw | <8700 | |
| Di-n-octylphthalate, ug/kg dw | <8700 | |
| Benzo(b)fluoranthene, ug/kg dw | <8700 | |
| Benzo(k)fluoranthene, ug/kg dw | <8700 | |
| Benzo(a)pyrene, ug/kg dw | <8700 | |
| Indeno (1,2,3-cd)pyrene, ug/kg dw | <8700 | |
| Dibenzo (a,h)anthracene, ug/kg dw | <8700 | |
| Benzo(g,h,i)perylene, ug/kg dw | <8700 | |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10360

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 15

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY |
|------------------------------|---|------------|
| 10360-4 | RR (11.28.89) | Client |
| PARAMETER | 10360-4 | |
| TCL Pesticides | | |
| alpha-BHC, ug/kg dw | <130 | |
| beta-BHC, ug/kg dw | <130 | |
| delta-BHC, ug/kg dw | <130 | |
| gamma-BHC, ug/kg dw | <130 | |
| Heptachlor, ug/kg dw | <130 | |
| Aldrin, ug/kg dw | <130 | |
| Heptachlor epoxide, ug/kg dw | <270 | |
| Endosulfan I, ug/kg dw | <270 | |
| Dieldrin, ug/kg dw | <270 | |
| 4,4'-DDE, ug/kg dw | <270 | |
| Endrin, ug/kg dw | <270 | |
| Endosulfan II, ug/kg dw | <670 | |
| 4,4'-DDD, ug/kg dw | <270 | |
| Endosulfan sulfate, ug/kg dw | <1100 | |
| 4,4'-DDT, ug/kg dw | <670 | |
| Endrin ketone, ug/kg dw | <1100 | |
| Methoxychlor, ug/kg dw | <5300 | |
| alpha-Chlordane, ug/kg dw | <130 | |
| gamma-Chlordane, ug/kg dw | <130 | |
| Toxaphene, ug/kg dw | <1100 | |
| Aroclor-1016, ug/kg dw | <5300 | |
| Aroclor-1221, ug/kg dw | <5300 | |
| Aroclor-1232, ug/kg dw | <5300 | |
| Aroclor-1242, ug/kg dw | <5300 | |
| Aroclor-1248, ug/kg dw | <5300 | |
| Aroclor-1254, ug/kg dw | <5300 | |
| Aroclor-1260, ug/kg dw | <5300 | |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10360

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 16

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY |
|---------------------------|---|------------|
| 10360-4 | RR (11.28.89) | Client |
| PARAMETER | 10360-4 | |
| Percent Solids, % | 75 % | |
| NBS Library Search, ID | * | |
| pH, units | 9.6 | |
| Cyclohexylamine, ug/kg dw | <35000 | |

Laboratory Name: SAVANNAH LABORATORIESCase No: 10360

Sample Number

RR

Organics Analysis Data Sheet

NO PEAKS FOUND

| CAS Number | Compound Name | Fraction | RT or Scan Number | Estimated Concentration (ug/l or ug/kg) |
|------------|---------------|----------|-------------------|---|
| 1. | | | | |
| 2. | | | | |
| 3. | | | | |
| 4. | | | | |
| 5. | | | | |
| 6. | | | | |
| 7. | | | | |
| 8. | | | | |
| 9. | | | | |
| 10. | | | | |
| 11. | | | | |
| 12. | | | | |
| 13. | | | | |
| 14. | | | | |
| 15. | | | | |
| 16. | | | | |
| 17. | | | | |
| 18. | | | | |
| 19. | | | | |
| 20. | | | | |
| 21. | | | | |
| 22. | | | | |
| 23. | | | | |
| 24. | | | | |
| 25. | | | | |
| 26. | | | | |
| 27. | | | | |
| 28. | | | | |
| 29. | | | | |
| 30. | | | | |

*Compound was identified by the comparison of the unknown peak with mass spectra stored in the National Bureau of Standards (NBS) library. No authentic standard available; concentration reported is semi-quantitative and based on the response factor of the internal standards added to the sample immediately before GC/MS analysis.

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10359

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 1

| LOG NO | SAMPLE DESCRIPTION , LIQUID SAMPLES | SAMPLED BY | | |
|---|-------------------------------------|------------|---------|---------|
| 10359-1 | MW-1 (11.29.89) | Client | | |
| 10359-2 | MW-2 (11.29.89) | | | |
| 10359-3 | MW-3 (11.29.89) | | | |
| PARAMETER | | 10359-1 | 10359-2 | 10359-3 |
| TCL Semivolatiles | | | | |
| Phenol, ug/l | | <80 | <80 | <80 |
| bis(2-Chloroethyl) ether, ug/l | | <80 | <80 | <80 |
| 2-Chlorophenol, ug/l | | <80 | <80 | <80 |
| 1,3-Dichlorobenzene, ug/l | | <80 | <80 | <80 |
| 1,4-Dichlorobenzene, ug/l | | <80 | <80 | <80 |
| Benzyl alcohol, ug/l | | <160 | <160 | <160 |
| 1,2-Dichlorobenzene, ug/l | | <80 | <80 | <80 |
| 2-Methylphenol (o-cresol), ug/l | | <80 | <80 | <80 |
| bis(2-Chloro-1-methylethyl) ether, ug/l | | <80 | <80 | <80 |
| 4-Methylphenol (p-cresol), ug/l | | <80 | <80 | <80 |
| N-Nitroso-di-n-dipropylamine, ug/l | | <80 | <80 | <80 |
| Hexachloroethane, ug/l | | <80 | <80 | <80 |
| Nitrobenzene, ug/l | | <80 | <80 | <80 |
| Isophorone, ug/l | | <80 | <80 | <80 |
| 2-Nitrophenol, ug/l | | <80 | <80 | <80 |
| 2,4-Dimethylphenol, ug/l | | <80 | <80 | <80 |
| Benzoic acid, ug/l | | <400 | <400 | <400 |
| bis(2-Chloroethoxy) methane, ug/l | | <80 | <80 | <80 |
| 2,4-Dichlorophenol, ug/l | | <80 | <80 | <80 |
| 1,2,4-Trichlorobenzene, ug/l | | <80 | <80 | <80 |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10359

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 2

| LOG NO | SAMPLE DESCRIPTION , LIQUID SAMPLES | SAMPLED BY | | |
|-----------------------------------|-------------------------------------|------------|---------|---------|
| 10359-1 | MW-1 (11.29.89) | Client | | |
| 10359-2 | MW-2 (11.29.89) | | | |
| 10359-3 | MW-3 (11.29.89) | | | |
| PARAMETER | | 10359-1 | 10359-2 | 10359-3 |
| Naphthalene, ug/l | | <80 | <80 | <80 |
| 4-Chloroaniline, ug/l | | <160 | <160 | <160 |
| Hexachlorobutadiene, ug/l | | <80 | <80 | <80 |
| 4-Chloro-3-methylphenol, ug/l | | <80 | <80 | <80 |
| 2-Methylnaphthalene, ug/l | | <80 | <80 | <80 |
| Hexachlorocyclopentadiene, ug/l | | <80 | <80 | <80 |
| 2,4,6-Trichlorophenol, ug/l | | <80 | <80 | <80 |
| 2,4,5-Trichlorophenol, ug/l | | <80 | <80 | <80 |
| 2-Chloronaphthalene, ug/l | | <80 | <80 | <80 |
| 2-Nitroaniline, ug/l | | <400 | <400 | <400 |
| Dimethylphthalate, ug/l | | <80 | <80 | <80 |
| Acenaphthylene, ug/l | | <80 | <80 | <80 |
| 3-Nitroaniline, ug/l | | <400 | <400 | <400 |
| Acenaphthene, ug/l | | <80 | <80 | <80 |
| 2,4-Dinitrophenol, ug/l | | <400 | <400 | <400 |
| 4-Nitrophenol, ug/l | | <400 | <400 | <400 |
| Dibenzofuran, ug/l | | <80 | <80 | <80 |
| 2,4-Dinitrotoluene, ug/l | | <80 | <80 | <80 |
| 2,6-Dinitrotoluene, ug/l | | <80 | <80 | <80 |
| Diethylphthalate, ug/l | | <80 | <80 | <80 |
| 4-Chlorophenyl-phenyl ether, ug/l | | <80 | <80 | <80 |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10359

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 3

| LOG NO | SAMPLE DESCRIPTION , LIQUID SAMPLES | SAMPLED BY | | |
|--|-------------------------------------|------------|---------|---------|
| 10359-1 | MW-1 (11.29.89) | Client | | |
| 10359-2 | MW-2 (11.29.89) | | | |
| 10359-3 | MW-3 (11.29.89) | | | |
| PARAMETER | | 10359-1 | 10359-2 | 10359-3 |
| Fluorene, ug/l | | <80 | <80 | <80 |
| 4-Nitroaniline, ug/l | | <400 | <400 | <400 |
| 4,6-Dinitro-2-methylphenol, ug/l | | <400 | <400 | <400 |
| N-Nitrosodiphenylamine/diphenylamine, ug/l | | <80 | <80 | <80 |
| 4-Bromophenyl-phenyl-ether, ug/l | | <80 | <80 | <80 |
| Hexachlorobenzene, ug/l | | <80 | <80 | <80 |
| Pentachlorophenol, ug/l | | <400 | <400 | <400 |
| Phenanthrene, ug/l | | <80 | <80 | <80 |
| Anthracene, ug/l | | <80 | <80 | <80 |
| Di-n-butylphthalate, ug/l | | <80 | <80 | <80 |
| Fluoranthene, ug/l | | <80 | <80 | <80 |
| Pyrene, ug/l | | <80 | <80 | <80 |
| Butylbenzylphthalate, ug/l | | <80 | <80 | <80 |
| 3,3'-Dichlorobenzidine, ug/l | | <160 | <160 | <160 |
| Benzo(a)anthracene, ug/l | | <80 | <80 | <80 |
| bis(2-Ethylhexyl) pthalate, ug/l | | <80 | <80 | <80 |
| Chrysene, ug/l | | <80 | <80 | <80 |
| Di-n-octylphthalate, ug/l | | <80 | <80 | <80 |
| Benzo(b)fluoranthene, ug/l | | <80 | <80 | <80 |
| Benzo(k)fluoranthene, ug/l | | <80 | <80 | <80 |
| Benzo(a)pyrene, ug/l | | <80 | <80 | <80 |
| Indeno (1,2,3-cd)pyrene, ug/l | | <80 | <80 | <80 |
| Dibenzo (a,h)anthracene, ug/l | | <80 | <80 | <80 |
| Benzo(g,h,i)perylene, ug/l | | <80 | <80 | <80 |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10359

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 5

| LOG NO | SAMPLE DESCRIPTION , LIQUID SAMPLES | SAMPLED BY | | |
|--------------------------|-------------------------------------|------------|---------|---------|
| 10359-1 | MW-1 (11.29.89) | Client | | |
| 10359-2 | MW-2 (11.29.89) | | | |
| 10359-3 | MW-3 (11.29.89) | | | |
| PARAMETER | | 10359-1 | 10359-2 | 10359-3 |
| TCL Pesticides | | | | |
| alpha-BHC, ug/l | | <0.010 | <0.010 | <0.010 |
| beta-BHC, ug/l | | <0.010 | <0.010 | <0.010 |
| delta-BHC, ug/l | | <0.010 | <0.010 | <0.010 |
| gamma-BHC, ug/l | | <0.010 | <0.010 | <0.010 |
| Heptachlor, ug/l | | <0.010 | <0.010 | <0.010 |
| Aldrin, ug/l | | <0.010 | <0.010 | <0.010 |
| Heptachlor epoxide, ug/l | | <0.020 | <0.020 | <0.020 |
| Endosulfan I, ug/l | | <0.020 | <0.020 | <0.020 |
| Dieldrin, ug/l | | <0.020 | <0.020 | <0.020 |
| 4,4'-DDE, ug/l | | <0.020 | <0.020 | <0.020 |
| Endrin, ug/l | | <0.020 | <0.020 | <0.020 |
| Endosulfan II, ug/l | | <0.050 | <0.050 | <0.050 |
| 4,4'-DDD, ug/l | | <0.020 | <0.020 | <0.020 |
| Endosulfan sulfate, ug/l | | <0.10 | <0.10 | <0.10 |
| 4,4'-DDT, ug/l | | <0.050 | <0.050 | <0.050 |
| Endrin ketone, ug/l | | <0.10 | <0.10 | <0.10 |
| Methoxychlor, ug/l | | <0.50 | <0.50 | <0.50 |
| alpha-Chlordane, ug/l | | <0.010 | <0.010 | <0.010 |
| gamma-Chlordane, ug/l | | <0.010 | <0.010 | <0.010 |
| Toxaphene, ug/l | | <1.0 | <1.0 | <1.0 |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10359

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 6

| LOG NO | SAMPLE DESCRIPTION , LIQUID SAMPLES | SAMPLED BY | | |
|--------------------|-------------------------------------|------------|---------|---------|
| 10359-1 | MW-1 (11.29.89) | Client | | |
| 10359-2 | MW-2 (11.29.89) | | | |
| 10359-3 | MW-3 (11.29.89) | | | |
| PARAMETER | | 10359-1 | 10359-2 | 10359-3 |
| Aroclor-1016, ug/l | | <0.50 | <0.50 | <0.50 |
| Aroclor-1221, ug/l | | <0.50 | <0.50 | <0.50 |
| Aroclor-1232, ug/l | | <0.50 | <0.50 | <0.50 |
| Aroclor-1242, ug/l | | <0.50 | <0.50 | <0.50 |
| Aroclor-1248, ug/l | | <0.50 | <0.50 | <0.50 |
| Aroclor-1254, ug/l | | <0.50 | <0.50 | <0.50 |
| Aroclor-1260, ug/l | | <0.50 | <0.50 | <0.50 |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

SAVANNAH LABORATORIES AND ENVIRONMENTAL SERVICES, INC.

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10359

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 7

| LOG NO | SAMPLE DESCRIPTION , LIQUID SAMPLES | SAMPLED BY | | |
|---------------------------------|-------------------------------------|------------|---------|---------|
| 10359-1 | MW-1 (11.29.89) | Client | | |
| 10359-2 | MW-2 (11.29.89) | | | |
| 10359-3 | MW-3 (11.29.89) | | | |
| PARAMETER | | 10359-1 | 10359-2 | 10359-3 |
| Volatiles by GC/MS | | | | |
| Chloromethane, ug/l | | <10 | <10 | <10 |
| Bromomethane, ug/l | | <10 | <10 | <10 |
| Vinyl Chloride, ug/l | | <10 | <10 | <10 |
| Chloroethane, ug/l | | <10 | <10 | <10 |
| Methylene Chloride, ug/l | | <5 | <5 | <5 |
| Acetone, ug/l | | <25 | <25 | <25 |
| Carbon Disulfide, ug/l | | <5 | <5 | <5 |
| 1,1-Dichloroethylene, ug/l | | <5 | <5 | <5 |
| 1,1-Dichloroethane, ug/l | | <5 | <5 | <5 |
| 1,2-Dichloroethene, ug/l | | <5 | 23 | <5 |
| Chloroform, ug/l | | <5 | <5 | <5 |
| 1,2-Dichloroethane, ug/l | | <5 | <5 | <5 |
| 2-Butanone, ug/l | | <10 | <10 | <10 |
| 1,1,1-Trichloroethane, ug/l | | <5 | <5 | <5 |
| Carbon Tetrachloride, ug/l | | <5 | <5 | <5 |
| Vinyl Acetate, ug/l | | <10 | <10 | <10 |
| Bromodichloromethane, ug/l | | <5 | <5 | <5 |
| 1,1,2,2-Tetrachloroethane, ug/l | | <5 | <5 | <5 |
| 1,2-Dichloropropane, ug/l | | <5 | <5 | <5 |
| Trans-1,3-Dichloropropene, ug/l | | <5 | <5 | <5 |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10360

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 19

| LOG NO | SAMPLE DESCRIPTION , QC SAMPLES | SAMPLED BY |
|---------|---------------------------------|------------|
| 10360-5 | Detection Limits | Client |
| 10360-6 | Accuracy (Mean % Recovery) | |
| 10360-7 | Precision (% RPD) | |

| PARAMETER | 10360-5 | 10360-6 | 10360-7 |
|----------------------------------|---------|---------|---------|
| Volatiles by GC/MS | | | |
| Chloromethane, ug/kg | 10 | — | — |
| Bromomethane, ug/kg | 10 | — | — |
| Vinyl Chloride, ug/kg | 10 | — | — |
| Chloroethane, ug/kg | 10 | — | — |
| Methylene Chloride, ug/kg | 5 | — | — |
| Acetone, ug/kg | 25 | — | — |
| Carbon Disulfide, ug/kg | 5 | — | — |
| 1,1-Dichloroethylene, ug/kg | 5 | 103 % | 4.9 % |
| 1,1-Dichloroethane, ug/kg | 5 | — | — |
| 1,2-Dichloroethene, ug/kg | 5 | — | — |
| Chloroform, ug/kg | 5 | — | — |
| 1,2-Dichloroethane, ug/kg | 5 | — | — |
| 2-Butanone, ug/kg | 10 | — | — |
| 1,1,1-Trichloroethane, ug/kg | 5 | — | — |
| Carbon Tetrachloride, ug/kg | 5 | — | — |
| Vinyl Acetate, ug/kg | 10 | — | — |
| Bromodichloromethane, ug/kg | 5 | — | — |
| 1,1,2,2-Tetrachloroethane, ug/kg | 5 | — | — |
| 1,2-Dichloropropane, ug/kg | 5 | — | — |
| Trans-1,3-Dichloropropene, ug/kg | 5 | — | — |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10360

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 20

| LOG NO | SAMPLE DESCRIPTION , QC SAMPLES | SAMPLED BY |
|---------|---------------------------------|------------|
| 10360-5 | Detection Limits | Client |
| 10360-6 | Accuracy (Mean % Recovery) | |
| 10360-7 | Precision (% RPD) | |

| PARAMETER | 10360-5 | 10360-6 | 10360-7 |
|--------------------------------|---------|---------|---------|
| Trichloroethylene, ug/kg | 5 | 85 % | 1.2 % |
| Dibromochloromethane, ug/kg | 5 | — | — |
| 1,1,2-Trichloroethane, ug/kg | 5 | — | — |
| Benzene, ug/kg | 5 | 100 % | 1.0 % |
| Cis-1,3-Dichloropropene, ug/kg | 5 | — | — |
| Bromoform, ug/kg | 5 | — | — |
| 2-Hexanone, ug/kg | 10 | — | — |
| 4-methyl-2-pentanone, ug/kg | 10 | — | — |
| Tetrachloroethylene, ug/kg | 5 | — | — |
| Toluene, ug/kg | 5 | 113 % | 0.9 % |
| Chlorobenzene, ug/kg | 5 | 101 % | 5.0 % |
| Ethylbenzene, ug/kg | 5 | — | — |
| Styrene, ug/kg | 5 | — | — |
| Xylenes, ug/kg | 5 | — | — |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10360

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 21

| LOG NO | SAMPLE DESCRIPTION , QC SAMPLES | SAMPLED BY |
|---------|---------------------------------|------------|
| 10360-5 | Detection Limits | Client |
| 10360-6 | Accuracy (Mean % Recovery) | |
| 10360-7 | Precision (% RPD) | |

| PARAMETER | 10360-5 | 10360-6 | 10360-7 |
|---|---------|---------|---------|
| TCL Semivolatiles | | | |
| Phenol, ug/kg dw | 330 | 72 % | 8.3 % |
| bis(2-Chloroethyl) ether, ug/kg dw | 330 | 76 % | 6.6 % |
| 2-Chlorophenol, ug/kg dw | 330 | — | — |
| 1,3-Dichlorobenzene, ug/kg dw | 330 | — | — |
| 1,4-Dichlorobenzene, ug/kg dw | 330 | 80 % | 6.3 % |
| Benzyl alcohol, ug/kg dw | 670 | — | — |
| 1,2-Dichlorobenzene, ug/kg dw | 330 | — | — |
| 2-Methylphenol (o-cresol), ug/kg dw | 330 | — | — |
| bis(2-Chloro-1-methylethyl) ether, ug/kg dw | 330 | — | — |
| 4-Methylphenol (p-cresol), ug/kg dw | 330 | — | — |
| N-Nitroso-di-n-dipropylamine, ug/kg dw | 330 | 81 % | 8.6 % |
| Hexachloroethane, ug/kg dw | 330 | — | — |
| Nitrobenzene, ug/kg dw | 330 | — | — |
| Isophorone, ug/kg dw | 330 | — | — |
| 2-Nitrophenol, ug/kg dw | 330 | — | — |
| 2,4-Dimethylphenol, ug/kg dw | 330 | — | — |
| Benzoic acid, ug/kg dw | 1700 | — | — |
| bis(2-Chloroethoxy) methane, ug/kg dw | 330 | — | — |
| 2,4-Dichlorophenol, ug/kg dw | 330 | — | — |
| 1,2,4-Trichlorobenzene, ug/kg dw | 330 | 84 % | 4.7 % |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

SAVANNAH LABORATORIES AND ENVIRONMENTAL SERVICES, INC.

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10360

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 22

| LOG NO | SAMPLE DESCRIPTION , QC SAMPLES | SAMPLED BY | | |
|---------------------------------------|---------------------------------|------------|---------|---------|
| 10360-5 | Detection Limits | Client | | |
| 10360-6 | Accuracy (Mean % Recovery) | | | |
| 10360-7 | Precision (% RPD) | | | |
| PARAMETER | | 10360-5 | 10360-6 | 10360-7 |
| Naphthalene, ug/kg dw | | 330 | — | — |
| 4-Chloroaniline, ug/kg dw | | 670 | — | — |
| Hexachlorobutadiene, ug/kg dw | | 330 | — | — |
| 4-Chloro-3-methylphenol, ug/kg dw | | 330 | 80 % | 5.0 % |
| 2-Methylnaphthalene, ug/kg dw | | 330 | — | — |
| Hexachlorocyclopentadiene, ug/kg dw | | 330 | — | — |
| 2,4,6-Trichlorophenol, ug/kg dw | | 330 | — | — |
| 2,4,5-Trichlorophenol, ug/kg dw | | 330 | — | — |
| 2-Chloronaphthalene, ug/kg dw | | 330 | — | — |
| 2-Nitroaniline, ug/kg dw | | 1700 | — | — |
| Dimethylphthalate, ug/kg dw | | 330 | — | — |
| Acenaphthylene, ug/kg dw | | 330 | — | — |
| 3-Nitroaniline, ug/kg dw | | 1700 | — | — |
| Acenaphthene, ug/kg dw | | 330 | 79 % | 2.5 % |
| 2,4-Dinitrophenol, ug/kg dw | | 1700 | — | — |
| 4-Nitrophenol, ug/kg dw | | 1700 | 72 % | 25 % |
| Dibenzofuran, ug/kg dw | | 330 | — | — |
| 2,4-Dinitrotoluene, ug/kg dw | | 330 | 65 % | 15 % |
| 2,6-Dinitrotoluene, ug/kg dw | | 330 | — | — |
| Diethylphthalate, ug/kg dw | | 330 | — | — |
| 4-Chlorophenyl-phenyl ether, ug/kg dw | | 330 | — | — |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10360

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 23

| LOG NO | SAMPLE DESCRIPTION , QC SAMPLES | SAMPLED BY | | |
|--|---------------------------------|------------|---------|---------|
| 10360-5 | Detection Limits | Client | | |
| 10360-6 | Accuracy (Mean % Recovery) | | | |
| 10360-7 | Precision (% RPD) | | | |
| PARAMETER | | 10360-5 | 10360-6 | 10360-7 |
| Fluorene, ug/kg dw | | 330 | — | — |
| 4-Nitroaniline, ug/kg dw | | 1700 | — | — |
| 4,6-Dinitro-2-methylphenol, ug/kg dw | | 1700 | — | — |
| N-Nitrosodiphenylamine/diphenylamine, ug/kg dw | | 330 | — | — |
| 4-Bromophenyl-phenyl-ether, ug/kg dw | | 330 | — | — |
| Hexachlorobenzene, ug/kg dw | | 330 | — | — |
| Pentachlorophenol, ug/kg dw | | 1700 | 81 % | 8.6 % |
| Phenanthrene, ug/kg dw | | 330 | — | — |
| Anthracene, ug/kg dw | | 330 | — | — |
| Di-n-butylphthalate, ug/kg dw | | 330 | — | — |
| Fluoranthene, ug/kg dw | | 330 | — | — |
| Pyrene, ug/kg dw | | 330 | 88 % | 0 % |
| Butylbenzylphthalate, ug/kg dw | | 330 | — | — |
| 3,3'-Dichlorobenzidine, ug/kg dw | | 670 | — | — |
| Benzo(a)anthracene, ug/kg dw | | 330 | — | — |
| bis(2-Ethylhexyl) phthalate, ug/kg dw | | 330 | — | — |
| Chrysene, ug/kg dw | | 330 | — | — |
| Di-n-octylphthalate, ug/kg dw | | 330 | — | — |
| Benzo(b)fluoranthene, ug/kg dw | | 330 | — | — |
| Benzo(k)fluoranthene, ug/kg dw | | 330 | — | — |
| Benzo(a)pyrene, ug/kg dw | | 330 | — | — |
| Indeno (1,2,3-cd)pyrene, ug/kg dw | | 330 | — | — |
| Dibenzo (a,h)anthracene, ug/kg dw | | 330 | — | — |
| Benzo(g,h,i)perylene, ug/kg dw | | 330 | — | — |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10360

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 24

| LOG NO | SAMPLE DESCRIPTION , QC SAMPLES | SAMPLED BY |
|---------|---------------------------------|------------|
| 10360-5 | Detection Limits | Client |
| 10360-6 | Accuracy (Mean % Recovery) | |
| 10360-7 | Precision (% RPD) | |

| PARAMETER | 10360-5 | 10360-6 | 10360-7 |
|------------------------------|---------|---------|---------|
| TCL Pesticides | | | |
| alpha-BHC, ug/kg dw | 2.0 | — | — |
| beta-BHC, ug/kg dw | 2.0 | — | — |
| delta-BHC, ug/kg dw | 2.0 | — | — |
| gamma-BHC, ug/kg dw | 2.0 | 124 % | 4.0 % |
| Heptachlor, ug/kg dw | 2.0 | 125 % | 5.6 % |
| Aldrin, ug/kg dw | 2.0 | 116 % | 6.0 % |
| Heptachlor epoxide, ug/kg dw | 4.0 | — | — |
| Endosulfan I, ug/kg dw | 4.0 | — | — |
| Dieldrin, ug/kg dw | 4.0 | 116 % | 0.9 % |
| 4,4'-DDE, ug/kg dw | 4.0 | — | — |
| Endrin, ug/kg dw | 4.0 | 118 % | 0.8 % |
| Endosulfan II, ug/kg dw | 10 | — | — |
| 4,4'-DDD, ug/kg dw | 4.0 | — | — |
| Endosulfan sulfate, ug/kg dw | 16 | — | — |
| 4,4'-DDT, ug/kg dw | 10 | 126 % | 6.3 % |
| Endrin ketone, ug/kg dw | 16 | — | — |
| Methoxychlor, ug/kg dw | 80 | — | — |
| alpha-Chlordane, ug/kg dw | 2.0 | — | — |
| gamma-Chlordane, ug/kg dw | 2.0 | — | — |
| Toxaphene, ug/kg dw | 160 | — | — |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10360

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220


Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 25

| LOG NO | SAMPLE DESCRIPTION , QC SAMPLES | SAMPLED BY | | |
|------------------------|---------------------------------|------------|---------|---------|
| 10360-5 | Detection Limits | Client | | |
| 10360-6 | Accuracy (Mean % Recovery) | | | |
| 10360-7 | Precision (% RPD) | | | |
| PARAMETER | | 10360-5 | 10360-6 | 10360-7 |
| Aroclor-1016, ug/kg dw | | 80 | — | — |
| Aroclor-1221, ug/kg dw | | 80 | — | — |
| Aroclor-1232, ug/kg dw | | 80 | — | — |
| Aroclor-1242, ug/kg dw | | 80 | — | — |
| Aroclor-1248, ug/kg dw | | 80 | — | — |
| Aroclor-1254, ug/kg dw | | 80 | — | — |
| Aroclor-1260, ug/kg dw | | 80 | — | — |

Methods: EPA SW-846.


Steven J. White

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10359

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 10

| LOG NO | SAMPLE DESCRIPTION , QC SAMPLES | SAMPLED BY |
|---------|---------------------------------|------------|
| 10359-4 | Detection Limits | Client |
| 10359-5 | Accuracy (Mean % Recovery) | |
| 10359-6 | Precision (% RPD) | |

| PARAMETER | 10359-4 | 10359-5 | 10359-6 |
|---|---------|---------|---------|
| TCL Semivolatiles | | | |
| Phenol, ug/l | 10 | 61 % | 3.3 % |
| bis(2-Chloroethyl) ether, ug/l | 10 | — | — |
| 2-Chlorophenol, ug/l | 10 | 50 % | 4.0 % |
| 1,3-Dichlorobenzene, ug/l | 10 | — | — |
| 1,4-Dichlorobenzene, ug/l | 10 | 56 % | 7.1 % |
| Benzyl alcohol, ug/l | 20 | — | — |
| 1,2-Dichlorobenzene, ug/l | 10 | — | — |
| 2-Methylphenol (o-cresol), ug/l | 10 | — | — |
| bis(2-Chloro-1-methylethyl) ether, ug/l | 10 | — | — |
| 4-Methylphenol (p-cresol), ug/l | 10 | — | — |
| N-Nitroso-di-n-dipropylamine, ug/l | 10 | 82 % | 4.9 % |
| Hexachloroethane, ug/l | 10 | — | — |
| Nitrobenzene, ug/l | 10 | — | — |
| Isophorone, ug/l | 10 | — | — |
| 2-Nitrophenol, ug/l | 10 | — | — |
| 2,4-Dimethylphenol, ug/l | 10 | — | — |
| Benzoic acid, ug/l | 50 | — | — |
| bis(2-Chloroethoxy) methane, ug/l | 10 | — | — |
| 2,4-Dichlorophenol, ug/l | 10 | — | — |
| 1,2,4-Trichlorobenzene, ug/l | 10 | 98 % | 4.1 % |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10359

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 11

| LOG NO | SAMPLE DESCRIPTION , QC SAMPLES | SAMPLED BY | | |
|-----------------------------------|---------------------------------|------------|---------|--|
| 10359-4 | Detection Limits | Client | | |
| 10359-5 | Accuracy (Mean % Recovery) | | | |
| 10359-6 | Precision (% RPD) | | | |
| PARAMETER | 10359-4 | 10359-5 | 10359-6 | |
| Naphthalene, ug/l | 10 | — | — | |
| 4-Chloroaniline, ug/l | 20 | — | — | |
| Hexachlorobutadiene, ug/l | 10 | — | — | |
| 4-Chloro-3-methylphenol, ug/l | 10 | 76 % | 7.9 % | |
| 2-Methylnaphthalene, ug/l | 10 | — | — | |
| Hexachlorocyclopentadiene, ug/l | 10 | — | — | |
| 2,4,6-Trichlorophenol, ug/l | 10 | — | — | |
| 2,4,5-Trichlorophenol, ug/l | 10 | — | — | |
| 2-Chloronaphthalene, ug/l | 10 | — | — | |
| 2-Nitroaniline, ug/l | 50 | — | — | |
| Dimethylphthalate, ug/l | 10 | — | — | |
| Acenaphthylene, ug/l | 10 | — | — | |
| 3-Nitroaniline, ug/l | 50 | — | — | |
| Acenaphthene, ug/l | 10 | 100 % | 4.0 % | |
| 2,4-Dinitrophenol, ug/l | 50 | — | — | |
| 4-Nitrophenol, ug/l | 50 | 37 % | 16 % | |
| Dibenzofuran, ug/l | 10 | — | — | |
| 2,4-Dinitrotoluene, ug/l | 10 | 83 % | 2.4 % | |
| 2,6-Dinitrotoluene, ug/l | 10 | — | — | |
| Diethylphthalate, ug/l | 10 | — | — | |
| 4-Chlorophenyl-phenyl ether, ug/l | 10 | — | — | |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10359

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 12

| LOG NO | SAMPLE DESCRIPTION , QC SAMPLES | SAMPLED BY |
|---------|---------------------------------|------------|
| 10359-4 | Detection Limits | Client |
| 10359-5 | Accuracy (Mean % Recovery) | |
| 10359-6 | Precision (% RPD) | |

| PARAMETER | 10359-4 | 10359-5 | 10359-6 |
|--|---------|---------|---------|
| Fluorene, ug/l | 10 | — | — |
| 4-Nitroaniline, ug/l | 50 | — | — |
| 4,6-Dinitro-2-methylphenol, ug/l | 50 | — | — |
| N-Nitrosodiphenylamine/diphenylamine, ug/l | 10 | — | — |
| 4-Bromophenyl-phenyl-ether, ug/l | 10 | — | — |
| Hexachlorobenzene, ug/l | 10 | — | — |
| Pentachlorophenol, ug/l | 50 | 67 % | 2.9 % |
| Phenanthrene, ug/l | 10 | — | — |
| Anthracene, ug/l | 10 | — | — |
| Di-n-butylphthalate, ug/l | 10 | — | — |
| Fluoranthene, ug/l | 10 | — | — |
| Pyrene, ug/l | 10 | 85 % | 2.4 % |
| Butylbenzylphthalate, ug/l | 10 | — | — |
| 3,3'-Dichlorobenzidine, ug/l | 20 | — | — |
| Benzo(a)anthracene, ug/l | 10 | — | — |
| bis(2-Ethylhexyl) phthalate, ug/l | 10 | — | — |
| Chrysene, ug/l | 10 | — | — |
| Di-n-octylphthalate, ug/l | 10 | — | — |
| Benzo(b)fluoranthene, ug/l | 10 | — | — |
| Benzo(k)fluoranthene, ug/l | 10 | — | — |
| Benzo(a)pyrene, ug/l | 10 | — | — |
| Indeno (1,2,3-cd)pyrene, ug/l | 10 | — | — |
| Dibenzo (a,h)anthracene, ug/l | 10 | — | — |
| Benzo(g,h,i)perylene, ug/l | 10 | — | — |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10359

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 13

| LOG NO | SAMPLE DESCRIPTION , QC SAMPLES | SAMPLED BY |
|---------|---------------------------------|------------|
| 10359-4 | Detection Limits | Client |
| 10359-5 | Accuracy (Mean % Recovery) | |
| 10359-6 | Precision (% RPD) | |

| PARAMETER | 10359-4 | 10359-5 | 10359-6 |
|--------------------------|---------|---------|---------|
| TCL Pesticides | | | |
| alpha-BHC, ug/l | 0.010 | — | — |
| beta-BHC, ug/l | 0.010 | — | — |
| delta-BHC, ug/l | 0.010 | — | — |
| gamma-BHC, ug/l | 0.010 | 107 % | 1.9 % |
| Heptachlor, ug/l | 0.010 | 101 % | 3.0 % |
| Aldrin, ug/l | 0.010 | 94 % | 3.2 % |
| Heptachlor epoxide, ug/l | 0.020 | — | — |
| Endosulfan I, ug/l | 0.020 | — | — |
| Dieldrin, ug/l | 0.020 | 100 % | 8.0 % |
| 4,4'-DDE, ug/l | 0.020 | — | — |
| Endrin, ug/l | 0.020 | 118 % | 5.1 % |
| Endosulfan II, ug/l | 0.050 | — | — |
| 4,4'-DDD, ug/l | 0.020 | — | — |
| Endosulfan sulfate, ug/l | 0.10 | — | — |
| 4,4'-DDT, ug/l | 0.050 | — | — |
| Endrin ketone, ug/l | 0.10 | — | — |
| Methoxychlor, ug/l | 0.50 | — | — |
| alpha-Chlordane, ug/l | 0.010 | — | — |
| gamma-Chlordane, ug/l | 0.010 | — | — |
| Toxaphene, ug/l | 1.0 | — | — |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10359

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 14

| LOG NO | SAMPLE DESCRIPTION , QC SAMPLES | SAMPLED BY | | |
|--------------------|---------------------------------|------------|---------|---------|
| 10359-4 | Detection Limits | Client | | |
| 10359-5 | Accuracy (Mean % Recovery) | | | |
| 10359-6 | Precision (% RPD) | | | |
| PARAMETER | | 10359-4 | 10359-5 | 10359-6 |
| Aroclor-1016, ug/l | | 0.50 | — | — |
| Aroclor-1221, ug/l | | 0.50 | — | — |
| Aroclor-1232, ug/l | | 0.50 | — | — |
| Aroclor-1242, ug/l | | 0.50 | — | — |
| Aroclor-1248, ug/l | | 0.50 | — | — |
| Aroclor-1254, ug/l | | 0.50 | — | — |
| Aroclor-1260, ug/l | | 0.50 | — | — |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10359

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 15

| LOG NO | SAMPLE DESCRIPTION , QC SAMPLES | SAMPLED BY |
|---------|---------------------------------|------------|
| 10359-4 | Detection Limits | Client |
| 10359-5 | Accuracy (Mean % Recovery) | |
| 10359-6 | Precision (% RPD) | |

| PARAMETER | 10359-4 | 10359-5 | 10359-6 |
|---------------------------------|---------|---------|---------|
| Volatiles by GC/MS | | | |
| Chloromethane, ug/l | 10 | — | — |
| Bromomethane, ug/l | 10 | — | — |
| Vinyl Chloride, ug/l | 10 | — | — |
| Chloroethane, ug/l | 10 | — | — |
| Methylene Chloride, ug/l | 5 | — | — |
| Acetone, ug/l | 25 | — | — |
| Carbon Disulfide, ug/l | 5 | — | — |
| 1,1-Dichloroethylene, ug/l | 5 | 91 % | 1.1 % |
| 1,1-Dichloroethane, ug/l | 5 | — | — |
| 1,2-Dichloroethene, ug/l | 5 | — | — |
| Chloroform, ug/l | 5 | — | — |
| 1,2-Dichloroethane, ug/l | 5 | — | — |
| 2-Butanone, ug/l | 10 | — | — |
| 1,1,1-Trichloroethane, ug/l | 5 | — | — |
| Carbon Tetrachloride, ug/l | 5 | — | — |
| Vinyl Acetate, ug/l | 10 | — | — |
| Bromodichloromethane, ug/l | 5 | — | — |
| 1,1,2,2-Tetrachloroethane, ug/l | 5 | — | — |
| 1,2-Dichloropropane, ug/l | 5 | — | — |
| Trans-1,3-Dichloropropene, ug/l | 5 | — | — |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10359

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

REPORT OF ANALYTICAL RESULTS

Page 16

| LOG NO | SAMPLE DESCRIPTION , QC SAMPLES | SAMPLED BY |
|---------|---------------------------------|------------|
| 10359-4 | Detection Limits | Client |
| 10359-5 | Accuracy (Mean % Recovery) | |
| 10359-6 | Precision (% RPD) | |

| PARAMETER | 10359-4 | 10359-5 | 10359-6 |
|-------------------------------|---------|---------|---------|
| Trichloroethylene, ug/l | 5 | 98 % | 4.1 % |
| Dibromochloromethane, ug/l | 5 | — | — |
| 1,1,2-Trichloroethane, ug/l | 5 | — | — |
| Benzene, ug/l | 5 | 99 % | 3.0 % |
| Cis-1,3-Dichloropropene, ug/l | 5 | — | — |
| Bromoform, ug/l | 5 | — | — |
| 2-Hexanone, ug/l | 10 | — | — |
| 4-methyl-2-pentanone, ug/l | 10 | — | — |
| Tetrachloroethylene, ug/l | 5 | — | — |
| Toluene, ug/l | 5 | 97 % | 3.1 % |
| Chlorobenzene, ug/l | 5 | 99 % | 3.0 % |
| Ethylbenzene, ug/l | 5 | — | — |
| Styrene, ug/l | 5 | — | — |
| Xylenes, ug/l | 5 | — | — |
| Cyanide, mg/l | 0.020 | 79 % | 13 % |
| Aluminum (Dissolved), mg/l | 0.10 | 112 % | 0.89 % |
| Antimony (Dissolved), mg/l | 0.050 | 103 % | 0 % |
| Arsenic (Dissolved), mg/l | 0.010 | 125 % | 0 % |
| Barium (Dissolved), mg/l | 0.010 | 104 % | 3.8 % |
| Beryllium (Dissolved), mg/l | 0.0050 | 95 % | 1.0 % |
| Cadmium (Dissolved), mg/l | 0.0050 | 115 % | 1.7 % |

Laboratory Name: SAVANNAH LABORATORIESCase No: 10360

Sample Number

SB-12 1-3'

Organics Analysis Data Sheet

| CAS Number | Compound Name | Fraction | RT or Scan Number | Estimated Concentration (ug/l or <u>ug/kg</u>) |
|------------|---------------|----------|-------------------|---|
| 1. | UNKNOWN | SV | 12.06 | 16.0 |
| 2. | | | | |
| 3. | | | | |
| 4. | | | | |
| 5. | | | | |
| 6. | | | | |
| 7. | | | | |
| 8. | | | | |
| 9. | | | | |
| 10. | | | | |
| 11. | | | | |
| 12. | | | | |
| 13. | | | | |
| 14. | | | | |
| 15. | | | | |
| 16. | | | | |
| 17. | | | | |
| 18. | | | | |
| 19. | | | | |
| 20. | | | | |
| 21. | | | | |
| 22. | | | | |
| 23. | | | | |
| 24. | | | | |
| 25. | | | | |
| 26. | | | | |
| 27. | | | | |
| 28. | | | | |
| 29. | | | | |
| 30. | | | | |

*Compound was identified by the comparison of the unknown peak with mass spectra stored in the National Bureau of Standards (NBS) library. No authentic standard available; concentration reported is semi-quantitative and based on the response factor of the internal standards added to the sample immediately before GC/MS analysis.

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 00-10360

Received: 12 DEC 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

PARTIAL
REPORT OF ANALYTICAL RESULTS

Page 1

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY | |
|---|---|------------|---------|
| 10360-1 | SB-10 5-7' | Client | |
| 10360-2 | SB-10 7-9' | | |
| PARAMETER | | 10360-1 | 10360-2 |
| TCL Semivolatiles | | | |
| Phenol, ug/kg dw | | <470 | <440 |
| bis(2-Chloroethyl) ether, ug/kg dw | | <470 | <440 |
| 2-Chlorophenol, ug/kg dw | | <470 | <440 |
| 1,3-Dichlorobenzene, ug/kg dw | | <470 | <440 |
| 1,4-Dichlorobenzene, ug/kg dw | | <470 | <440 |
| Benzyl alcohol, ug/kg dw | | <470 | <440 |
| 1,2-Dichlorobenzene, ug/kg dw | | <470 | <440 |
| 2-Methylphenol (o-cresol), ug/kg dw | | <470 | <440 |
| bis(2-Chloro-1-methylethyl) ether, ug/kg dw | | <470 | <440 |
| 4-Methylphenol (p-cresol), ug/kg dw | | <470 | <440 |
| N-Nitroso-di-n-dipropylamine, ug/kg dw | | <470 | <440 |
| Hexachloroethane, ug/kg dw | | <470 | <440 |
| Nitrobenzene, ug/kg dw | | <470 | <440 |
| Isophorone, ug/kg dw | | <470 | <440 |
| 2-Nitrophenol, ug/kg dw | | <470 | <440 |
| 2,4-Dimethylphenol, ug/kg dw | | <470 | <440 |
| Benzoic acid, ug/kg dw | | <2400 | <2200 |
| bis(2-Chloroethoxy) methane, ug/kg dw | | <470 | <440 |
| 2,4-Dichlorophenol, ug/kg dw | | <470 | <440 |
| 1,2,4-Trichlorobenzene, ug/kg dw | | <470 | <440 |
| Naphthalene, ug/kg dw | | <470 | <440 |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 00-10360

Received: 12 DEC 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

PARTIAL
REPORT OF ANALYTICAL RESULTS

Page 2

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY | |
|---------------------------------------|---|------------|--|
| 10360-1 | SB-10 5-7' | Client | |
| 10360-2 | SB-10 7-9' | | |
| PARAMETER | 10360-1 | 10360-2 | |
| 4-Chloroaniline, ug/kg dw | <940 | <880 | |
| Hexachlorobutadiene, ug/kg dw | <470 | <440 | |
| 4-Chloro-3-methylphenol, ug/kg dw | <470 | <440 | |
| 2-Methylnaphthalene, ug/kg dw | <470 | <440 | |
| Hexachlorocyclopentadiene, ug/kg dw | <470 | <440 | |
| 2,4,6-Trichlorophenol, ug/kg dw | <470 | <440 | |
| 2,4,5-Trichlorophenol, ug/kg dw | <470 | <440 | |
| 2-Chloronaphthalene, ug/kg dw | <470 | <440 | |
| 2-Nitroaniline, ug/kg dw | <2400 | <2200 | |
| Dimethylphthalate, ug/kg dw | <470 | <440 | |
| Acenaphthylene, ug/kg dw | <470 | <440 | |
| 3-Nitroaniline, ug/kg dw | <2400 | <2200 | |
| Acenaphthene, ug/kg dw | <470 | <440 | |
| 2,4-Dinitrophenol, ug/kg dw | <2400 | <2200 | |
| 4-Nitrophenol, ug/kg dw | <2400 | <2200 | |
| Dibenzofuran, ug/kg dw | <470 | <440 | |
| 2,4-Dinitrotoluene, ug/kg dw | <470 | <440 | |
| 2,6-Dinitrotoluene, ug/kg dw | <470 | <440 | |
| Diethylphthalate, ug/kg dw | <470 | <440 | |
| 4-Chlorophenyl-phenyl ether, ug/kg dw | <470 | <440 | |
| Fluorene, ug/kg dw | <470 | <440 | |
| 4-Nitroaniline, ug/kg dw | <2400 | <2200 | |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 00-10360

Received: 12 DEC 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204

**PARTIAL
REPORT OF ANALYTICAL RESULTS**

Page 3

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY | |
|--|---|------------|--|
| 10360-1 | SB-10 5-7' | Client | |
| 10360-2 | SB-10 7-9' | | |
| PARAMETER | 10360-1 | 10360-2 | |
| 4,6-Dinitro-2-methylphenol, ug/kg dw | <2400 | <2200 | |
| N-Nitrosodiphenylamine/diphenylamine, ug/kg dw | <470 | <440 | |
| 4-Bromophenyl-phenyl-ether, ug/kg dw | <470 | <440 | |
| Hexachlorobenzene, ug/kg dw | <470 | <440 | |
| Pentachlorophenol, ug/kg dw | <2400 | <2200 | |
| Phenanthrene, ug/kg dw | <470 | <440 | |
| Anthracene, ug/kg dw | <470 | <440 | |
| Di-n-butylphthalate, ug/kg dw | <470 | <440 | |
| Fluoranthene, ug/kg dw | <470 | <440 | |
| Pyrene, ug/kg dw | <470 | <440 | |
| Butylbenzylphthalate, ug/kg dw | <470 | <440 | |
| 3,3'-Dichlorobenzidine, ug/kg dw | <940 | <880 | |
| Benzo(a)anthracene, ug/kg dw | <470 | <440 | |
| bis(2-Ethylhexyl) phthalate, ug/kg dw | <470 | <440 | |
| Chrysene, ug/kg dw | <470 | <440 | |
| Di-n-octylphthalate, ug/kg dw | <470 | <440 | |
| Benzo(b)fluoranthene, ug/kg dw | <470 | <440 | |
| Benzo(k)fluoranthene, ug/kg dw | <470 | <440 | |
| Benzo(a)pyrene, ug/kg dw | <470 | <440 | |
| Indeno (1,2,3-cd)pyrene, ug/kg dw | <470 | <440 | |
| Dibenzo (a,h)anthracene, ug/kg dw | <470 | <440 | |
| Benzo(g,h,i)perylene, ug/kg dw | <470 | <440 | |

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 00-10360

Received: 12 DEC 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220


Project: 89204

PARTIAL
REPORT OF ANALYTICAL RESULTS

Page 4

| LOG NO | SAMPLE DESCRIPTION , SOLID OR SEMISOLID SAMPLES | SAMPLED BY | |
|---------------------------|---|------------|---------|
| 10360-1 | SB-10 5-7' | Client | |
| 10360-2 | SB-10 7-9' | | |
| PARAMETER | | 10360-1 | 10360-2 |
| NBS Library Search | | | |
| Cyclohexylamine, ug/kg dw | | <1900 | <1900 |

Methods: EPA SW-846.


Steven J. White

James W. Andrews, Ph.D.
President

Janette Davis Long
Vice-President

**SAVANNAH LABORATORIES
AND ENVIRONMENTAL SERVICES, INC.**

5102 LaRoche Avenue (31404)
P. O. Box 13548 • Savannah, GA 31416-0548
(912) 354-7858



LOG NO: 89-10359

Received: 30 NOV 89

Mr. Marty Knuth
Civil & Env. Consultants Inc.
790 Holiday Drive
Pittsburgh, PA 15220

Project: 89204


REPORT OF ANALYTICAL RESULTS

Page 17

| LOG NO | SAMPLE DESCRIPTION , QC SAMPLES | SAMPLED BY |
|---------|---------------------------------|------------|
| 10359-4 | Detection Limits | Client |
| 10359-5 | Accuracy (Mean % Recovery) | |
| 10359-6 | Precision (% RPD) | |

| PARAMETER | 10359-4 | 10359-5 | 10359-6 |
|-----------------------------|---------|---------|---------|
| Calcium (Dissolved), mg/l | 0.050 | 75 % | 0 % |
| Chromium (Dissolved), mg/l | 0.010 | 107 % | 0 % |
| Cobalt (Dissolved), mg/l | 0.010 | 106 % | 0.94 % |
| Copper (Dissolved), mg/l | 0.010 | 105 % | 0.95 % |
| Iron (Dissolved), mg/l | 0.010 | 106 % | 0 % |
| Lead (Dissolved) | 0.0050 | 85 % | 0 % |
| Magnesium (Dissolved), mg/l | 0.050 | 99 % | 1.0 % |
| Manganese (Dissolved), mg/l | 0.010 | 97 % | 1.0 % |
| Mercury (Dissolved), mg/l | 0.00020 | 116 % | 0.86 % |
| Nickel (Dissolved), mg/l | 0.010 | 106 % | 0.94 % |
| Potassium (Dissolved), mg/l | 1.0 | 121 % | 6.6 % |
| Selenium (Dissolved), mg/l | 0.010 | 108 % | 2.7 % |
| Silver (Dissolved) | 0.010 | 76 % | 0 % |
| Sodium (Dissolved), mg/l | 0.050 | 118 % | 1.0 % |
| Thallium (Dissolved), mg/l | 0.010 | 102 % | 13 % |
| Vanadium (Dissolved), mg/l | 0.010 | 109 % | 0 % |
| Zinc (Dissolved), mg/l | 0.010 | 114 % | 0.88 % |

Methods: EPA 40 CFR Part 136.


Steven J. White

Laboratory Name: SAVANNAH LABORATORIESCase No: 1128A11A

Sample Number

10141 SB-4

Organics Analysis Data Sheet

30.38g 79%

FV = 1.0

| CAS Number | Compound Name | Fraction | RT or Scan Number | Estimated Concentration (ug/l or ug/kg) |
|-------------|------------------------------|----------|-------------------|---|
| 1. 79345 | Ethane, 1,1,2,2-tetrachloro- | BN/A | 6.667 | 310 |
| 2. 11544500 | Sulfur, mol. | BN/A | 23.114 | 9700 |
| 3. | Unknown | BN/A | 30.715 | 200 |
| 4. | | | | |
| 5. | | | | |
| 6. | | | | |
| 7. | | | | |
| 8. | | | | |
| 9. | | | | |
| 10. | | | | |
| 11. | | | | |
| 12. | | | | |
| 13. | | | | |
| 14. | | | | |
| 15. | | | | |
| 16. | | | | |
| 17. | | | | |
| 18. | | | | |
| 19. | | | | |
| 20. | | | | |
| 21. | | | | |
| 22. | | | | |
| 23. | | | | |
| 24. | | | | |
| 25. | | | | |
| 26. | | | | |
| 27. | | | | |
| 28. | | | | |
| 29. | | | | |
| 30. | | | | |

*Compound was identified by the comparison of the unknown peak with mass spectra stored in the National Bureau of Standards (NBS) library. No authentic standard available; concentration reported is semi-quantitative and based on the response factor of the internal standards added to the sample immediately before GC/MS analysis.